Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

NFPA® 92

Standard for Smoke Control Systems

2012 Edition

NFPA, 1 Batterymarch Park, Quincy, MA 02169-7471
An International Codes and Standards Organization

Become a Member
Subscribe to the NATIONAL FIRE CODES SUBSCRIPTION SERVICE
Register for Seminars, Webinars, and Online Courses
Visit the NFPA Catalog

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® DOCUMENTS
NOTICE AND DISCLAIMER OF LIABILITY CONCERNING THE USE OF NFPA DOCUMENTS

NFPA® codes, standards, recommended practices, and guides ("NFPA Documents"), of which the document contained herein is one, are developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on fire and other safety issues. While the NFPA administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in NFPA Documents.

The NFPA disclaims liability for any personal injury, property or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on NFPA Documents. The NFPA also makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

In issuing and making NFPA Documents available, the NFPA is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the NFPA undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The NFPA has no power, nor does it undertake, to police or enforce compliance with the contents of NFPA Documents. Nor does the NFPA list, certify, test, or inspect products, designs, or installations for compliance with this document. Any certification or other statement of compliance with the requirements of this document shall not be attributable to the NFPA and is solely the responsibility of the certifier or maker of the statement.

ISBN: 978-145590134-0 (Print)
ISBN: 978-145590144-9 (PDF) 12/09

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA DOCUMENTS

ADDITIONAL NOTICES AND DISCLAIMERS

Updating of NFPA Documents

Users of NFPA codes, standards, recommended practices, and guides ("NFPA Documents") should be aware that these documents may be superseded at any time by the issuance of new editions or may be amended from time to time through the issuance of Tentative Interim Amendments. An official NFPA Document at any point in time consists of the current edition of the document together with any Tentative Interim Amendments and any Errata then in effect. In order to determine whether a given document is the current edition and whether it has been amended through the issuance of Tentative Interim Amendments or corrected through the issuance of Errata, consult appropriate NFPA publications such as the National Fire Codes® Subscription Service, visit the NFPA website at www.nfpa.org, or contact the NFPA at the address listed below.

Interpretations of NFPA Documents

A statement, written or oral, that is not processed in accordance with Section 6 of the Regulations Governing Committee Projects shall not be considered the official position of NFPA or any of its Committees and shall not be considered to be, nor be relied upon as, a Formal Interpretation.

Patents

The NFPA does not take any position with respect to the validity of any patent rights referenced in, related to, or asserted in connection with an NFPA Document. The users of NFPA Documents bear the sole responsibility for determining the validity of any such patent rights, as well as the risk of infringement of such rights, and the NFPA disclaims liability for the infringement of any patent resulting from the use of or reliance on NFPA Documents.

NFPA adheres to the policy of the American National Standards Institute (ANSI) regarding the inclusion of patents in American National Standards ("the ANSI Patent Policy"), and hereby gives the following notice pursuant to that policy:

NOTICE: The user's attention is called to the possibility that compliance with an NFPA Document may require use of an invention covered by patent rights. NFPA takes no position as to the validity of any such patent rights or as to whether such patent rights constitute or include essential patent claims under the ANSI Patent Policy. If, in connection with the ANSI Patent Policy, a patent holder has filed a statement of willingness to grant licenses under these rights on reasonable and nondiscriminatory terms and conditions to applicants desiring to obtain such a license, copies of such filed statements can be obtained, on request, from NFPA. For further information, contact the NFPA at the address listed below.

Law and Regulations

Users of NFPA Documents should consult applicable federal, state, and local laws and regulations. NFPA does not, by the publication of its codes, standards, recommended practices, and guides, intend to urge action that is not in compliance with applicable laws, and these documents may not be construed as doing so.

Copyrights

NFPA Documents are copyrighted by the NFPA. They are made available for a wide variety of both public and private uses. These include both use, by reference, in laws and regulations, and use in private self-regulation, standardization, and the promotion of safe practices and methods. By making these documents available for use and adoption by public authorities and private users, the NFPA does not waive any rights in copyright to these documents.

Use of NFPA Documents for regulatory purposes should be accomplished through adoption by reference. The term "adoption by reference" means the citing of title, edition, and publishing information only. Any deletions, additions, and changes desired by the adopting authority should be noted separately in the adopting instrument. In order to assist NFPA in following the uses made of its documents, adopting authorities are requested to notify the NFPA (Attention: Secretary, Standards Council) in writing of such use. For technical assistance and questions concerning adoption of NFPA Documents, contact NFPA at the address below.

For Further Information

All questions or other communications relating to NFPA Documents and all requests for information on NFPA procedures governing its codes and standards development process, including information on the procedures for requesting Formal Interpretations, for proposing Tentative Interim Amendments, and for proposing revisions to NFPA documents during regular revision cycles, should be sent to NFPA headquarters, addressed to the attention of the Secretary, Standards Council, NFPA, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02169-7471; email: stds_admin@nfpa.org

For more information about NFPA, visit the NFPA website at www.nfpa.org.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Copyright © 2011 National Fire Protection Association®. All Rights Reserved.

NFPA® 92

Standard for

Smoke Control Systems

2012 Edition

This edition of NFPA 92, *Standard for Smoke Control Systems*, was prepared by the Technical Committee on Smoke Management Systems. It was issued by the Standards Council on May 31, 2011, with an effective date of June 20, 2011.

This edition of NFPA 92 was approved as an American National Standard on June 20, 2011.

Origin and Development of NFPA 92

The NFPA Standards Council established the Technical Committee on Smoke Management Systems in 1985 and charged it with addressing the need for guidelines and materials on smoke management in buildings. The Committee's first document, NFPA 92A, *Recommended Practice for Smoke-Control Systems*, was published in 1988 and addressed smoke control utilizing barriers, airflows, and pressure differentials so as to confine the smoke of a fire to the zone of fire origin to maintain a tenable environment in other zones. The complex problem of maintaining tenable conditions within large zones of fire origin such as atria and shopping malls represented a more difficult issue in terms of the physics involved and thus was reserved for another document, NFPA 92B, *Guide for Smoke Management Systems in Malls, Atria, and Large Areas*, first published in 1991.

Between 1991 and 2009, NFPA 92A and NFPA 92B were separately maintained. In 2006, NFPA 92A was rewritten as a standard with mandatory provisions regarding design, installation, and testing of smoke-control systems and was renamed *Smoke-Control Systems Utilizing Barriers and Pressure Differences*. In 2005 and 2006, both documents were reorganized to comply with the *Manual of Style for NFPA Technical Committee Documents*. Both documents eventually contained many of the same requirements for design objectives, activation, and installation.

In the Annual 2011 revision cycle, NFPA 92A and NFPA 92B were withdrawn and replaced with a new document, NFPA 92, *Standard for Smoke Control Systems*. NFPA 92 was created using requirements from both of the original documents, removing duplicate provisions and making numerous editorial changes. The new document uses the term *smoke control systems* to address both containment and management systems.

With the consolidation effort, the new standard now covers the following topics: design of smoke management systems and calculations, design of smoke containment systems, design of stairwell pressurization systems, and testing requirements.

NFPA and National Fire Protection Association are registered trademarks of the National Fire Protection Association, Quincy, Massachusetts 02169.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Committee on Smoke Management Systems

Randolph W. Tucker, *Chair*
The Woodlands, TX [SE]
Rep. The RJA Group, Inc.

Elyahu Avidor, Charlottesville, VA [RT]
Rep. Standards Institution of Israel
Justin B. Biller, Roanoke County Office of Building Safety, VA [E]
Flora F. Chen, City of Hayward, CA [E]
Paul David Compton, Colt International, Ltd., United Kingdom [M]
Richard J. Davis, FM Global, MA [I]
Michael Earl Dillon, Dillon Consulting Engineers, Inc., CA [SE]
Robert G. Dittrich, Honeywell, Inc., IL [M]
Rep. National Electrical Manufacturers Association
Douglas H. Evans, Clark County Building Department, NV [E]
Michael J. Ferreira, Hughes Associates, Inc., MD [SE]
Geoffrey Harris, Smoke and Fire Engineering Technology Ltd., United Kingdom [SE]
Rep. ISO TC on Smoke and Heat Control Systems and Components
John E. Kampmeyer, Triad Fire Protection Engineering Corporation, PA [SE]
Rep. National Society of Professional Engineers
David A. Killian, Walt Disney Parks & Resorts, CA [U]
William E. Koffel, Koffel Associates, Inc., MD [M]
Rep. AAMA Smoke Vent Task Group
Gary D. Lougheed, National Research Council of Canada, Canada [RT]
Anthony J. Militello, U.S. Department of the Navy, DC [E]
James A. Milke, University of Maryland, MD [SE]
Timothy J. Orris, AMCA International, Inc., IL [M]
Rep. Air Movement & Control Association
Robert C. Sampson, Acralight International, ME [M]
Lawrence J. Shudak, Underwriters Laboratories Inc., IL [RT]
Jeffrey S. Tubbs, Arup, MA [SE]
Paul G. Turnbull, Siemens Building Technologies, Inc., IL [M]
Robert Van Becelaere, Ruskin Manufacturing, MO [M]
Rep. American Society of Mechanical Engineers
Allyn J. Vaughn, JBA Consulting Engineers, NV [SE]
Stacy N. Welch, Marriott International, Inc., DC [U]
Peter J. Willse, XL Global Asset Protection Services, CT [I]
Steven D. Wolin, Code Consultants, Inc., MO [SE]

Alternates

Sanjay Aggarwal, The RJA Group, Inc., CA [SE]
(Alt. to R. W. Tucker)
Craig L. Beyler, Hughes Associates, Inc., MD [SE]
(Alt. to M. J. Ferreira)
Diane B. Copeland, Dillon Consulting Engineers, Inc., CA [SE]
(Alt. to M. E. Dillon)
Gregory R. Miller, Code Consultants, Inc., MO [SE]
(Alt. to S. D. Wolin)
Blake M. Shugarman, Underwriters Laboratories Inc., IL [RT]
(Alt. to L. J. Shudak)
Rick Thornberry, The Code Consortium, Inc., CA [M]
(Alt. to W. E. Koffel)
Yibing Xin, FM Global, MA [I]
(Alt. to R. J. Davis)

Nonvoting

Bent A. Borresen, Techno Consult, Norway
(Alt. to C. N. Madsen)
Christian Norgaard Madsen, Techno Consultant, Norway
Harold E. Nelson, Annandale, VA [SE]
(Member Emeritus)

Tracy L. Golinveaux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the design, installation, testing, operation, and maintenance of systems for the control, removal, or venting of heat or smoke from fires in buildings.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Contents

Chapter 1 Administration 92– 4
1.1 Scope 92– 4
1.2 Purpose 92– 4
1.3 Retroactivity 92– 4
1.4 Equivalency 92– 4
1.5 Units and Formulas. (Reserved) 92– 4

Chapter 2 Referenced Publications 92– 4
2.1 General 92– 4
2.2 NFPA Publications 92– 4
2.3 Other Publications 92– 4
2.4 References for Extracts in Mandatory Sections 92– 4

Chapter 3 Definitions 92– 5
3.1 General 92– 5
3.2 NFPA Official Definitions 92– 5
3.3 General Definitions 92– 5

Chapter 4 Design Fundamentals 92– 6
4.1 Design Objectives 92– 6
4.2 Design Basis 92– 6
4.3 Design Approaches 92– 7
4.4 Design Criteria 92– 7
4.5 System Operation 92– 8
4.6 Stairwell Pressurization Systems 92– 8
4.7 Elevator Pressurization Systems 92– 9
4.8 Zoned Smoke Control 92– 9
4.9 Combination of Systems 92– 9
4.10 Vestibules 92– 9
4.11 Doors 92– 9

Chapter 5 Smoke Management Calculation Procedures 92– 9
5.1 Introduction 92– 9
5.2 Design Fire 92– 9
5.3 Mass Consumption 92–11
5.4 Smoke Layer Calculations 92–11
5.5 Rate of Smoke Mass Production 92–12
5.6 Number of Exhaust Inlets 92–13
5.7 Volumetric Flow Rate 92–14
5.8 Density of Smoke 92–14
5.9 Varying Cross-Sectional Geometries and Complex Geometries 92–14
5.10 Opposed Airflow 92–14
5.11 Scaling Laws 92–16

Chapter 6 Building Equipment and Controls 92–16
6.1 General 92–16
6.2 Heating, Ventilating, and Air-Conditioning (HVAC) Equipment 92–16
6.3 Smoke Dampers 92–16
6.4 Smoke Control Systems 92–16
6.5 Energy Management 92–19
6.6 Materials 92–19
6.7 Electric Services Installation 92–19

Chapter 7 Smoke Control System Documentation 92–19
7.1 Documentation Required 92–19
7.2 Detailed Design Report 92–19
7.3 Operations and Maintenance Manual 92–19

Chapter 8 Testing 92–19
8.1 General 92–19
8.2 Preliminary Building Inspections 92–20
8.3 Component System Testing 92–20
8.4 Acceptance Testing 92–20
8.5 Testing Documentation 92–21
8.6 Periodic Testing 92–22
8.7 Modifications 92–22

Annex A Explanatory Material 92–22

Annex B Predicting the Rate of Heat Release of Fires 92–41

Annex C Computer-Based Models for Atria and Malls 92–53

Annex D Additional Design Objectives 92–57

Annex E Stratification of Smoke 92–60

Annex F Types of Stairwell Pressurization Systems 92–61

Annex G HVAC Air-Handling System Types 92–62

Annex H Fire Fighters' Smoke-Control Station (FSCS) Considerations 92–63

Annex I Information on Testing for Leakage Between Smoke Zones 92–65

Annex J Advisory Information on Acceptance Testing 92–66

Annex K Example Problems Illustrating the Use of Equations 92–67

Annex L Comparison of Equations 92–69

Annex M Informational References 92–72

Index 92–76

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

NFPA 92

Standard for

Smoke Control Systems

2012 Edition

IMPORTANT NOTE: This NFPA document is made available for use subject to important notices and legal disclaimers. These notices and disclaimers appear in all publications containing this document and may be found under the heading "Important Notices and Disclaimers Concerning NFPA Documents." They can also be obtained on request from NFPA or viewed at www.nfpa.org/disclaimers.

NOTICE: An asterisk (*) following the number or letter designating a paragraph indicates that explanatory material on the paragraph can be found in Annex A.

A reference in brackets [ ] following a section or paragraph indicates material that has been extracted from another NFPA document. As an aid to the user, the complete title and edition of the source documents for extracts in mandatory sections of the document are given in Chapter 2 and those for extracts in informational sections are given in Annex M. Extracted text may be edited for consistency and style and may include the revision of internal paragraph references and other references as appropriate. Requests for interpretations or revisions of extracted text shall be sent to the technical committee responsible for the source document.

Information on referenced publications can be found in Chapter 2 and Annex M.

Chapter 1 Administration

1.1* Scope. This standard shall apply to the design, installation, acceptance testing, operation, and ongoing periodic testing of smoke control systems.

1.2 Purpose.

1.2.1 The purpose of this standard shall be to establish requirements for smoke control systems to accomplish one or more of the following:

(1) Inhibit smoke from entering stairwells, means of egress, smoke refuge areas, elevator shafts, or similar areas
(2) Maintain a tenable environment in smoke refuge areas and means of egress during the time required for evacuation
(3) Inhibit the migration of smoke from the smoke zone
(4) Provide conditions outside the smoke zone that enable emergency response personnel to conduct search and rescue operations and to locate and control the fire
(5) Contribute to the protection of life and to the reduction of property loss

1.2.2 The requirements specifying the conditions under which a smoke control system shall be provided are addressed by other codes and standards.

1.2.3 Specific design objectives are established in other codes and standards.

1.3 Retroactivity.

1.3.1 Unless otherwise noted, it is not intended that the provisions of this document be applied to facilities, equipment, structures, or installations that were existing or approved for construction or installation prior to the effective date of this document.

1.3.2 In those cases where the authority having jurisdiction determines that the existing situation involves a distinct hazard to life or property, retroactive application of the provisions of this document shall be permitted.

1.3.3 Where a smoke control system is being altered, extended, or renovated, the requirements of this standard shall apply only to the work being undertaken.

1.3.4 Verification is required to ensure that new or modified systems do not adversely affect the performance of existing smoke control systems.

1.4 Equivalency. Nothing in this standard is intended to prevent the use of systems, methods, or devices of equivalent or superior quality, strength, fire resistance, effectiveness, durability, and safety over those prescribed by this standard.

1.4.1 Technical documentation shall be submitted to the authority having jurisdiction to demonstrate equivalency.

1.4.2 The system, method, or device shall be approved for the intended purpose by the authority having jurisdiction.

1.5 Units and Formulas. (Reserved)

Chapter 2 Referenced Publications

2.1 General. The documents or portions thereof listed in this chapter are referenced within this standard and shall be considered part of the requirements of this document.

2.2 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 70®, National Electrical Code®, 2011 edition.

NFPA 72®, National Fire Alarm and Signaling Code, 2010 edition.

NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems,* 2012 edition.

NFPA *101®, Life Safety Code®,* 2012 edition.

NFPA 110, *Standard for Emergency and Standby Power Systems,* 2010 edition.

NFPA 221, *Standard for High Challenge Fire Walls, Fire Walls, and Fire Barrier Walls,* 2012 edition.

2.3 Other Publications.

2.3.1 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062-2096.

ANSI/UL 555, *Standard for Fire Dampers,* 2006, Revised 2010.

ANSI/UL 555S, *Standard for Smoke Dampers,* 1999, Revised 2010.

ANSI/UL 864, *Standard for Control Units and Accessories for Fire Alarm Systems,* 2003, Revised 2010.

2.3.2 Other Publications.

Merriam-Webster's Collegiate Dictionary, 11th edition, Merriam-Webster, Inc., Springfield, MA, 2003.

2.4 References for Extracts in Mandatory Sections.

NFPA 1, *Fire Code,* 2012 edition.

NFPA *101®, Life Safety Code®,* 2012 edition.

NFPA 318, *Standard for the Protection of Semiconductor Fabrication Facilities,* 2012 edition.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Chapter 3 Definitions

3.1 General. The definitions contained in this chapter shall apply to the terms used in this standard. Where terms are not defined in this chapter or within another chapter, they shall be defined using their ordinarily accepted meanings within the context in which they are used. *Merriam-Webster's Collegiate Dictionary,* 11th edition, shall be the source for the ordinarily accepted meaning.

3.2 NFPA Official Definitions.

3.2.1* Approved. Acceptable to the authority having jurisdiction.

3.2.2* Authority Having Jurisdiction (AHJ). An organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, an installation, or a procedure.

3.2.3 Labeled. Equipment or materials to which has been attached a label, symbol, or other identifying mark of an organization that is acceptable to the authority having jurisdiction and concerned with product evaluation, that maintains periodic inspection of production of labeled equipment or materials, and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.

3.2.4* Listed. Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or service meets appropriate designated standards or has been tested and found suitable for a specified purpose.

3.2.5 Shall. Indicates a mandatory requirement.

3.2.6 Should. Indicates a recommendation or that which is advised but not required.

3.2.7 Standard. A document, the main text of which contains only mandatory provisions using the word "shall" to indicate requirements and which is in a form generally suitable for mandatory reference by another standard or code or for adoption into law. Nonmandatory provisions shall be located in an appendix or annex, footnote, or fine-print note and are not to be considered a part of the requirements of a standard.

3.3 General Definitions.

3.3.1 Atrium. A large-volume space created by a floor opening or series of floor openings connecting two or more stories that is covered at the top of the series of openings and is used for purposes other than an enclosed stairway; an elevator hoistway; an escalator opening; or as a utility shaft used for plumbing, electrical, air-conditioning, or communications facilities. [***101***, 2012]

3.3.2* Ceiling Jet. A flow of smoke under the ceiling, extending radially from the point of fire plume impingement on the ceiling.

3.3.3 Covered Mall. A single building enclosing a number of tenants and occupancies wherein two or more tenants have a main entrance into one or more malls.

3.3.4* Design Pressure Difference. The desired pressure difference between the protected space and an adjacent space measured at the boundary of the protected space under a specified set of conditions with the smoke control system operating.

3.3.5 Draft Curtain. A solid material, beam, girder, or similar material or construction that is used to channel or contain smoke and that is attached to the underside of the ceiling and protrudes a limited distance downward.

3.3.6 End-to-End Verification. A self-testing method that provides positive confirmation that the desired result (e.g., airflow or damper position) has been achieved when a controlled device has been activated, such as during smoke control, testing, or manual override operations.

3.3.7 Fire.

3.3.7.1 ***Fuel Limited Fire.*** A fire that has a heat release rate that is controlled by the material burning.

3.3.7.2 ***Sprinkler Controlled Fire.*** A fire that has a constant or decaying heat release rate due to the action of sprinkler spray.

3.3.7.3 ***Steady Fire.*** A fire that has a constant heat release rate.

3.3.7.4 ***t-squared (t^2) Fire.*** A fire that has a heat release rate that grows proportionally to the square of time from ignition. *[See Annex B for further information on t-squared (t^2) profile fires.]*

3.3.7.5 ***Unsteady Fire.*** A fire that has a heat release rate that varies with respect to time.

3.3.7.6 ***Ventilation Limited Fire.*** A fire where every object in the fire compartment is fully involved in fire and the heat release rate depends on the airflow through the openings to the fire compartment.

3.3.8* Fire Fighters' Smoke Control Station (FSCS). A system that provides graphical monitoring and manual overriding capability over smoke control systems and equipment at designated location(s) within the building for use by the fire department.

3.3.9 Growth Time (t_g). The time interval from the time of effective ignition until the heat release rate of the fire is 1000 Btu/sec (1055 kW).

3.3.10 Plugholing. The condition in which air from below the smoke layer is pulled through the smoke layer into the smoke exhaust due to a high exhaust rate.

3.3.11* Plume. A column of smoke that rises above a fire.

3.3.11.1* ***Axisymmetric Plume.*** A plume that rises above a fire, does not come into contact with walls or other obstacles, and is not disrupted or deflected by airflow.

3.3.11.2* ***Balcony Spill Plume.*** A smoke plume that originates from a compartment fire, flows out the doorway, flows under a balcony, and flows upward after passing the balcony edge.

3.3.11.3* ***Window Plume.*** A plume that flows out of an opening to a room or other compartment that is involved in a ventilation limited fire.

3.3.12 Pressurized Stairwells. A type of containment smoke control system in which stair shafts are mechanically pressurized, with respect to the fire area, with outdoor air to keep smoke from contaminating them during a fire incident.

3.3.13 Smoke. The airborne solid and liquid particulates and gases evolved when a material undergoes pyrolysis or combustion, together with the quantity of air that is entrained or otherwise mixed into the mass. [**318**, 2012]

3.3.13.1* ***First Indication of Smoke.*** The boundary between the transition zone and the smoke free air.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

3.3.14* Smoke Barrier. For the purposes of this standard, a continuous membrane, either vertical or horizontal, such as a wall, floor, or ceiling assembly, that is designed and constructed to restrict the movement of smoke in conjunction with a smoke control system.

3.3.15* Smoke Containment. A smoke control method that uses mechanical equipment to produce pressure differences across smoke barriers.

3.3.16 Smoke Control Mode. A predefined operational configuration of a system or device for the purpose of smoke control.

3.3.17 Space.

3.3.17.1 ***Large-Volume Space.*** An uncompartmented space, generally two or more stories in height, within which smoke from a fire either in the space or in a communicating space can move and accumulate without restriction.

3.3.17.2 ***Separated Spaces.*** Spaces within a building that are isolated from large-volume spaces by smoke barriers.

3.3.17.3* ***Communicating Space.*** A space within a building that has an open pathway to a large-volume space such that smoke from a fire either in the communicating space or in a large-volume space can move from one to another without restriction.

3.3.18 System.

3.3.18.1 ***Compensated System.*** A system that adjusts for changing conditions either by modulating supply airflows or by relieving excess pressure.

3.3.18.2* ***Dedicated Smoke Control System.*** Smoke control systems and components that are installed for the sole purpose of providing smoke control and that upon activation of the systems operate specifically to perform the smoke control function.

3.3.18.3* ***Nondedicated Smoke Control Systems.*** A smoke-control system that shares components with some other system(s), such as the building HVAC system, which changes its mode of operation to achieve the smoke-control objective. [**1,** 2012]

3.3.18.4 ***Pressurization System.***

3.3.18.4.1 ***Multiple-Injection Pressurization System.*** A type of smoke control system that has pressurization air supplied from multiple locations.

3.3.18.4.2 ***Single-Injection Pressurization System.*** A type of containment smoke control system that has pressurization air supplied from only one location.

3.3.18.5 ***Smoke Control System.*** An engineered system that includes all methods that can be used singly or in combination to modify smoke movement.

3.3.18.6* ***Smoke Exhaust System.*** A mechanical or gravity system intended to move smoke from the smoke zone to the exterior of the building, including smoke removal, purging, and venting systems, as well as the function of exhaust fans utilized to reduce the pressure in a smoke zone.

3.3.18.7 ***Zoned Smoke Control System.*** A smoke control system that includes a combination of smoke containment and smoke management methods for smoke exhaust for the smoke zone and pressurization for all contiguous smoke control zones.

3.3.19 Smoke Damper. A device within the air distribution system to control the movement of smoke.

3.3.20* Smoke Layer. The accumulated thickness of smoke below a physical or thermal barrier.

3.3.21* Smoke Layer Interface. The theoretical boundary between a smoke layer and the smoke-free air.

3.3.22 Smoke Management. A smoke control method that utilizes natural or mechanical systems to maintain a tenable environment in the means of egress from a large-volume space or to control and reduce the migration of smoke between the fire area and communicating spaces

3.3.23 Smoke Refuge Area. An area of the building separated from other spaces by fire resistance–rated smoke barriers in which a tenable environment is maintained for the period of time that such areas might need to be occupied at the time of fire.

3.3.24 Stack Effect. The vertical airflow within buildings caused by the temperature-created density differences between the building interior and exterior or between two interior spaces.

3.3.25* Tenable Environment. An environment in which smoke and heat are limited or otherwise restricted to maintain the impact on occupants to a level that is not life threatening.

3.3.26 Zone.

3.3.26.1 ***Smoke Control Zone.*** A space within a building enclosed by smoke barriers, including the top and bottom, that is part of a zoned smoke control system.

3.3.26.2 ***Smoke Zone.*** The smoke control zone in which the fire is located.

3.3.26.3* ***Transition Zone.*** The layer between the smoke layer interface and the first indication of smoke in which the smoke layer temperature decreases to ambient.

Chapter 4 Design Fundamentals

4.1 Design Objectives.

4.1.1* The methods for accomplishing smoke control shall include one or more of the following:

(1) The containment of smoke to the zone of origin by establishment and maintenance of pressure differences across smoke zone boundaries
(2) The management of smoke within a large-volume space and any unseparated spaces that communicate with the large-volume space

4.1.2* The specific objectives to be achieved over the design interval time shall include one or more of the following:

(1) Containing the smoke to the zone of fire origin
(2) Maintaining a tenable environment within exit stairwells for the time necessary to allow occupants to exit the building
(3) Maintaining a tenable environment within all exit access and smoke refuge area access paths for the time necessary to allow occupants to reach an exit or smoke refuge area
(4) Maintaining the smoke layer interface to a predetermined elevation in large volume spaces

4.2 Design Basis.

4.2.1* Smoke Containment Systems. A smoke control system in a given building designed to contain smoke to a given zone or keep smoke from entering another zone.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

4.2.1.1 The design pressure difference shall be based on the following:

(1) Whether the smoke zone is sprinklered
(2) The height of the ceiling in the smoke zone
(3) Maximum and minimum pressure differentials

4.2.2 Smoke Management Systems. The design basis for smoke management within a given large-volume space and any unseparated spaces shall include the determination of the following parameters:

(1) The design basis fires used to calculate smoke production (i.e., type, location, and quantity of fuel for each design basis fire, extent of coverage and reliability of automatic suppression, and extent and type of ventilation)
(2) Height, cross-sectional area, and plan area of the large-volume space to be protected
(3) Height, cross-sectional area, and plan area of each unseparated space that communicates with the large-volume space
(4) Type and location of occupancies within and communicating with the large-volume space
(5) Barriers, if any, that separate the communicating space from the large-volume space
(6) Egress routes from the large-volume space and any communicating space
(7) Any areas of refuge

4.2.3 Temperature Ratings.

4.2.3.1 The temperature ratings for the equipment used for smoke control systems shall be based on the expected temperature experienced by the equipment while the equipment is intended to be operational.

4.2.3.2 Temperature ratings shall be based on the following:

(1) Proximity to the fire
(2) Effects of dilution of the smoke and hot gases by entrained air

4.3 Design Approaches.

4.3.1 Smoke Containment Systems. The design approach for smoke containment systems shall be one of or a combination of the following:

(1) Stairwell pressurization
(2) Zoned pressurization
(3) Elevator pressurization
(4) Vestibule pressurization
(5) Smoke refuge area pressurization

4.3.2* Smoke Management Systems. The design approach for smoke management within large-volume spaces and communicating spaces shall be one of or a combination of the following:

(1) Natural smoke filling of an unoccupied volume or smoke reservoir and calculating or modeling of smoke layer descent to determine whether the smoke layer interface will reach a height at which occupants will be exposed to smoke prior to their ability to egress from the space
(2)*Mechanical smoke exhaust capacity to remove smoke from a space to maintain the smoke layer interface at a predefined height in the space for the design interval time
(3) Mechanical smoke exhaust capacity to remove smoke from a space to slow the rate of smoke layer descent for a period that allows occupants to safely egress from the space
(4) Gravity smoke venting to maintain the smoke layer interface at a predefined height in the space for the design interval time
(5) Gravity smoke venting to slow the rate of smoke layer descent for a period that allows occupants to egress from the space
(6)*Opposed airflow to prevent smoke movement between a large-volume space and a communicating space

4.4 Design Criteria.

4.4.1* Weather Data. Designs shall incorporate the effect of outdoor temperature and wind on the performance of systems.

4.4.2 Pressure Differences. The maximum and minimum allowable pressure differences across the boundaries of smoke control zones shall be established for containment systems.

4.4.2.1 Pressure Differences Across Spaces.

4.4.2.1.1* Except as specified by 4.4.2.1.2, the pressure differences in Table 4.4.2.1.1 shall be used for designs that are based on maintaining minimum pressure differences between specified spaces.

Table 4.4.2.1.1 Minimum Design Pressure Differences Across Smoke Barriers

Building Type	Ceiling Height (ft)	Design Pressure Difference* (in. w.g.)
AS	Any	0.05
NS	9	0.10
NS	15	0.14
NS	21	0.18

For SI units, 1 ft = 0.305 m; 0.1 in. w.g. = 25 Pa.
AS: Sprinklered. NS: Nonsprinklered.
Notes:
(1) The table presents minimum design pressure differences developed for a gas temperature of 1700°F (927°C) next to the smoke barrier.
(2) For design purposes, a smoke control system must maintain these minimum pressure differences under specified design conditions of stack effect or wind.
*For zoned smoke control systems, the pressure difference is required to be measured between the smoke zone and adjacent spaces while the affected areas are in the smoke control mode.

4.4.2.1.2 Where the system designer has determined that a higher minimum pressure difference is necessary to achieve the smoke control system objectives, the higher minimum pressure difference shall be used.

4.4.2.1.3 The minimum allowable pressure difference shall restrict smoke leakage during building evacuation to a level that maintains a tenable environment in areas outside the smoke zone.

4.4.2.1.4 The minimum pressure difference for smoke control systems shall be established at a level that is high enough that it will not be overcome by the forces of wind, stack effect, or buoyancy of hot smoke.

4.4.2.1.5 The calculations shall take into account the design number of doors to be opened simultaneously.

4.4.2.2* Pressure Differences Across Doors. The pressure differences across doors shall not cause the maximum force permitted to begin opening the door to exceed the value stipulated in NFPA *101, Life Safety Code*, or local codes and regulations.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

4.4.3 Fire Location. The source of the smoke from the design basis fires shall consider fire locations within the large-volume space and within unseparated communicating spaces.

4.4.4 Smoke Movement and Airflow.

4.4.4.1* Makeup Air. Makeup air for smoke management systems shall be provided by fans or by openings to the outside.

4.4.4.1.1 The supply points for the makeup air shall be located beneath the smoke layer interface.

4.4.4.1.2 Mechanical makeup air shall be less than the mass flow rate of the mechanical smoke exhaust.

4.4.4.1.3 The makeup air shall not cause door-opening force to exceed allowable limits.

4.4.4.1.4* The makeup air velocity shall not exceed 200 ft/min (1.02 m/sec) where the makeup air could come into contact with the plume unless a higher makeup air velocity is supported by engineering analysis.

4.4.4.2 Communicating Spaces.

4.4.4.2.1 Managing Smoke Spread to Communicating Spaces.

4.4.4.2.1.1 Managing smoke spread to communicating spaces shall be accomplished by one of the following methods:

(1) Maintaining the smoke layer interface at a level higher than that of the highest opening to the communicating space
(2) Providing a smoke barrier to limit smoke spread into the communicating space
(3) Providing an opposed airflow through the opening to prohibit smoke spread into the communicating space

4.4.4.2.1.2 When smoke barriers are used to limit smoke spread into the communicating space, engineering calculations shall be provided to verify whether a pressure difference applied across the smoke barrier will be needed to prevent smoke migration.

4.4.4.2.1.3 When the airflow method is used to prevent smoke movement from the large-volume space into communicating spaces for large openings, the flow shall be nearly perpendicular to the plane of the opening.

4.4.4.2.2* Managing Smoke from Communicating Spaces.

4.4.4.2.2.1 When communicating spaces are designed to allow the smoke to spill into the large-volume space, the smoke spilling into the large-volume space shall be handled by the smoke management system to maintain the design smoke layer interface height.

4.4.4.2.2.2 When the smoke control systems are designed to use airflow to prevent the movement of smoke into the large-volume space, sufficient exhaust from the communicating space shall be provided to establish a minimum flow between the communicating space and the large-volume space. *(See 5.10.1.)*

4.4.4.3* Openings and Leakage Areas. Designs shall incorporate the effect of openings and leakage areas in smoke barriers on the performance of smoke control systems.

4.4.4.4 Special Considerations Related to Natural Venting. Smoke management system designs that use a mix of natural and mechanical ventilation shall have supporting engineering analysis or physical (scale) modeling to verify the design functions as intended.

4.4.5* Gaseous Fire Suppression Systems. The operation of the smoke control system shall not compromise the performance of gaseous agent fire protection systems.

4.5* System Operation.

4.5.1 Limitations

4.5.1.1* Tenability. Where the design of the smoke control system is based on the potential for occupants being exposed to smoke, the tenability conditions shall be assessed.

4.5.1.2* Egress Analysis. Where the design of the smoke control system is based on occupants exiting a space before being exposed to smoke or before tenability thresholds are reached, there shall be sufficient time for the movement of the occupant as determined by a timed egress analysis.

4.5.1.3* Minimum Design Smoke Layer Depth. The minimum design depth of the smoke layer for a smoke management system shall be either of the following:

(1) Twenty percent of the floor-to-ceiling height
(2) Based on an engineering analysis

4.5.2 Activation. Activation of smoke control systems shall be accomplished by an approved automatic means.

4.5.3 System Startup.

4.5.3.1 The smoke control system shall achieve full operation prior to conditions in the space reaching the design smoke conditions.

4.5.3.2 The determination of the time it takes for the system to become operational shall consider the following events (as appropriate to the specific design objectives):

(1) Time for detection of the fire incident
(2) HVAC system activation time, including shutdown and startup of air-handling equipment, opening and closing of dampers, and opening and closing of natural ventilation devices

4.5.4 Duration.

4.5.4.1 When the design of the smoke management system is based on occupants exiting a space before being exposed to smoke or before tenability thresholds are reached, the following shall be met:

(1) A timed egress analysis shall be conducted.
(2) The system shall remain operational for the duration required.

4.5.4.2 Smoke management systems designed to maintain tenable conditions shall not be required to prevent the descent of a smoke layer in spaces where tenable conditions are demonstrated.

4.6 Stairwell Pressurization Systems.

4.6.1* General. When stairwell pressurization systems are provided, the pressure difference between the smoke zone and the stairwell, with zero and the design number of doors open, shall be as follows:

(1) Not less than the minimum pressure difference specified in 4.4.2
(2) Not greater than the maximum pressure difference specified in 4.4.2.2

4.6.2 Location of Supply Air Source. To limit smoke from entering the stairwell through the supply air intake, the supply air intake shall be separated from all building exhausts, outlets from smoke shafts and roof smoke and heat vents, open vents from elevator shafts, and other building openings that might expel smoke from the building in a fire.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

4.6.3 Supply Air Fans.

4.6.3.1* Propeller Fans. Roof or exterior wall-mounted propeller fans shall be permitted to be used in single-injection systems, provided that wind shields are provided for the fan.

4.6.3.2 Other Types of Fans. Centrifugal or in-line axial fans shall be permitted to be used in single- or multiple-injection systems.

4.6.4* Single- and Multiple-Injection Systems.

4.6.4.1 Single-Injection Systems.

4.6.4.1.1* The air injection point for a single-injection system shall be permitted to be located at any location within the stairwell.

4.6.4.1.2* Design analysis shall be performed for all single-bottom-injection systems and for all other single-injection systems for stairwells in excess of 100 ft (30.5 m) in height.

4.6.4.2* Multiple-Injection Systems. For system designs with injection points more than three stories apart, a design analysis shall be performed to ensure that loss of pressurization air through open doors does not lead to stairwell pressurization below the minimum design pressure.

4.7* Elevator Pressurization Systems. Where elevator pressurization is provided, elevator hoistways shall be pressurized to maintain a minimum positive pressure in accordance with 4.4.2. The minimum pressure shall be maintained with the elevator car at the recall floor and elevator doors and the hoistway vents open.

4.8* Zoned Smoke Control.

4.8.1 Smoke Control Zones.

4.8.1.1 When zoned smoke control is to be used to provide containment, the building shall be divided into smoke control zones, with each zone separated from the others by smoke barriers.

4.8.1.1.1* A smoke control zone shall be permitted to consist of one or more floors.

4.8.1.1.2 A floor shall be permitted to consist of one or more smoke control zones.

4.8.1.2 The zoned smoke control system shall be designed such that when zoned smoke control is active, the pressure differences between the adjacent non–smoke zones and the smoke zone meet or exceed the minimum design pressure differences given in 4.4.2, and at locations with doors, the pressure difference shall not exceed the values given in 4.4.2.2.

4.8.2 Smoke Zone Exhaust.

4.8.2.1 The smoke zone exhaust shall discharge to the outside of the building.

4.8.2.2 The smoke zone exhaust shall be permitted to be either mechanical or natural ventilation.

4.8.3* Smoke Refuge Areas.

4.8.3.1 A non–smoke zone of a zoned smoke control system shall be permitted to be used as an area intended to protect occupants for the period of time needed for evacuation or to provide a smoke refuge area.

4.8.3.2 For areas of refuge adjacent to stairwells or elevators, provisions shall be made to prevent the loss of pressure or excessive pressures due to the interaction between the smoke refuge area smoke control and the shaft smoke control.

4.9* Combination of Systems. Smoke control systems shall be designed such that where multiple smoke control systems operate simultaneously, each system will meet its individual design objectives.

4.10 Vestibules.

4.10.1* Vestibules shall not be required but shall be permitted as part of the building smoke control system.

4.10.2* Where vestibules are provided, either pressurized or nonpressurized vestibules shall be permitted.

4.11* Doors. Doors located in smoke barriers shall be self-closing or shall be arranged to close automatically upon activation of the smoke control system.

Chapter 5 Smoke Management Calculation Procedures

5.1* Introduction. The method of analysis used for design of a smoke management system shall be one of the methods given in 5.1.1 through 5.1.3.

5.1.1* Algebraic Equations. The algebraic equations in Chapter 5 shall be permitted to be used to provide a means of calculating individual factors that collectively can be used to establish the design requirements of a smoke management system.

5.1.2* Scale Modeling.

5.1.2.1 In a scale model, the model shall be proportional in all dimensions to the actual building.

5.1.2.2 The size of the fire and the interpretation of the results shall be governed by the scaling laws, as given in Section 5.11.

5.1.3* Compartment Fire Models. Compartment fire models shall be zone fire models or computational fluid dynamics (CFD) models. *(For information about zone fire models and CFD models, see Annex C.)*

5.2 Design Fire.

5.2.1* General. This section presents the equations that shall be used to calculate the heat release rates for design fires. *(For information about the heat release rates of fires, see Annex B.)*

5.2.2 Design Fire Types. Design fires shall be one of the following:

(1) Steady fire with a constant heat release rate
(2) Unsteady fire with a heat release rate that varies with time

5.2.3 Steady Design Fires.

5.2.3.1 The heat release rate of steady design fires shall be based on available or developed test data.

5.2.3.2 Where the available fuel mass is used to limit the duration of a steady design fire, the duration of the fire shall be calculated using Equation 5.2.3.2 as follows:

$$\Delta t = \frac{mH_c}{Q} \qquad \textbf{(5.2.3.2)}$$

where:
Δt = duration of fire (sec)
m = total fuel mass consumed (lb or kg)
H_c = heat of combustion of fuel (Btu/lb or kJ/kg)
Q = heat release rate (Btu/sec or kW)

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

5.2.4 Unsteady Design Fires. Unsteady design fires shall include a growth phase and shall include a steady phase or a decay phase, as depicted in Figure 5.2.4(a) and Figure 5.2.4(b), where steady or decay phases are justified based on test data, fuel configuration, or proposed protection systems.



FIGURE 5.2.4(a) Unsteady Design Fire with Steady Phase.



FIGURE 5.2.4(b) Unsteady Design Fire with Decay Phase.

5.2.4.1 Growth Phase. The growth phase of the fire shall be described using one of the following:

(1) Fire test data
(2) *t*-squared fire growth model
(3) Other fire growth models acceptable to the authority having jurisdiction

5.2.4.2 *t*-squared Fire Growth Model.

5.2.4.2.1 Where used, the heat release rate of a t-squared design fire shall be calculated according to Equation 5.2.4.2.1a or 5.2.4.2.1b as follows:

$$Q = 1000\left(\frac{t}{t_g}\right)^2 \qquad \textbf{(5.2.4.2.1a)}$$

where:
Q = heat release rate of design fire (Btu/sec)
t = time after effective ignition (sec)
t_g = growth time (sec)

$$Q = 1055\left(\frac{t}{t_g}\right)^2 \qquad \textbf{(5.2.4.2.1b)}$$

where:
Q = heat release rate of design fire (kW)
t = time after effective ignition (sec)
t_g = growth time (sec)

5.2.4.2.2 Where the available fuel mass is used to limit the duration of a t-squared fire, the duration of the fire shall be calculated using Equation 5.2.4.2.2 as follows:

$$\Delta t = \left(\frac{mH_c t_g^2}{333}\right)^{1/3} \qquad \textbf{(5.2.4.2.2)}$$

where:
Δt = duration of fire (sec)
m = total fuel mass consumed (lb or kg)
H_c = heat of combustion of fuel (Btu or kJ/kg)
t_g = growth time (sec)

5.2.4.3 Steady Phase. The growth of an unsteady design fire shall be permitted to reach a steady heat release rate based on one of the following:

(1) Fire test data
(2) Engineering analysis of fire growth and sprinkler response

5.2.4.4* Decay Phase. The heat release rate of a design fire shall be permitted to decay based on one of the following:

(1) Fire test data
(2) Analysis of the effect of sprinkler protection on the fuel at the prevailing ceiling height

5.2.5* Separation Distance.

5.2.5.1 The design fire shall be determined by considering the type of fuel, fuel spacing, and configuration.

5.2.5.2 The selection of the design fire shall start with a determination of the base fuel package, which is the maximum probable size fuel package likely to be involved in fire.

5.2.5.3 The design fire shall be increased if other combustibles are within the separation distance, R, as determined from Equation 5.2.5.3 as follows:

$$R = \left(\frac{Q_r}{4\pi q_r''}\right)^{1/2} \qquad \textbf{(5.2.5.3)}$$

where:
R = separation distance from target to center of fuel package (ft or m)
Q_r = radiative portion of the heat release rate of the fire (Btu/ft or kW)
q_r = incident radiant flux required for piloted ignition (Btu/ft^2 · s or kW/m^2)

5.2.5.4 The radiative portion of the heat release rate of the fire shall be determined from Equation 5.2.5.4 as follows:

$$Q_r = \xi Q \qquad \textbf{(5.2.5.4)}$$

where:
Q_r = radiative portion of the heat release rate of the fire (Btu/sec or kW)
ξ = radiative fraction (dimensionless)
Q = heat release rate of the fire (Btu/sec or kW)

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

5.2.5.5 A value of 0.3 shall be used for the radiative fraction unless another value is substantiated in accordance with test data.

5.2.5.6 If the base fuel package is not circular, an equivalent radius shall be calculated by equating the floor area covered by the fuel package with that subtended by a circle of the equivalent radius.

5.2.5.7 A value of 0.9 Btu/ft^2 · sec (10 kW/m^2) shall be used for the incident radiant heat flux required for piloted ignition unless another value is substantiated in accordance with approved test data.

5.3 Mass Consumption.

5.3.1 For a steady fire, the total mass consumption required to sustain the steady heat release rate shall be determined in accordance with Equation 5.3.1 as follows:

$$m = \frac{Q\Delta t}{H_c} \qquad \textbf{(5.3.1)}$$

where:
m = total fuel mass consumed (lb or kg)
Q = heat release rate (Btu/sec or kW)
Δt = duration of fire (sec)
H_c = heat of combustion of fuel (Btu/lb or kJ/kg)

5.3.2 For a *t*-squared fire, the total mass consumed shall be determined in accordance with Equation 5.3.2 as follows:

$$m = \frac{333\Delta t^3}{H_c t_g^2} \qquad \textbf{(5.3.2)}$$

where:
m = total fuel mass consumed (lb or kg)
Δt = duration of fire (sec)
H_c = heat of combustion of fuel (Btu/lb or kJ/kg)
t_g = growth time (sec)

5.4 Smoke Layer Calculations.

5.4.1* General. The position of the first indication of smoke at any time or the smoke layer interface height shall be determined from the relations in 5.4.2 and 5.5.

5.4.2 Height of First Indication of Smoke with No Smoke Exhaust Operating.

5.4.2.1* Steady Fires. Where all the following conditions occur, the height of the first indication of smoke above the fire surface, z, shall be calculated using either Equation 5.4.2.1a or 5.4.2.1b:

(1) Uniform cross-sectional areas with respect to height
(2) A/H^2 ratios in the range from 0.9 to 14
(3) $z/H > 0.2$
(4) Steady fires
(5) No smoke exhaust operating

$$\frac{z}{H} = 0.67 - 0.28 \ln\left(\frac{\frac{tQ^{1/3}}{H^{4/3}}}{\frac{A}{H^2}}\right) \qquad \textbf{(5.4.2.1a)}$$

where:
z = distance above the base of the fire to the first indication of smoke (ft)
H = ceiling height above the fire surface (ft)
t = time (sec)
Q = heat release rate from steady fire (Btu/sec)
A = cross-sectional area of the space being filled with smoke (ft^2)

$$\frac{z}{H} = 1.11 - 0.28 \ln\left(\frac{\frac{tQ^{1/3}}{H^{4/3}}}{\frac{A}{H^2}}\right) \qquad \textbf{(5.4.2.1b)}$$

where:
z = distance above the base of the fire to the first indication of smoke (m)
H = ceiling height above the fire surface (m)
t = time (sec)
Q = heat release rate from steady fire (kW)
A = cross-sectional area of the space being filled with smoke (m^2)

5.4.2.2* Unsteady Fires. Where all the following conditions occur, the descent of the height of the initial indication of smoke shall be calculated for *t*-squared fires using Equation 5.4.2.2a or 5.4.2.2b:

(1) Uniform cross-sectional areas with respect to height
(2) A/H^2 ratios in the range from 0.9 to 23
(3) $z/H > 0.2$
(4) Unsteady fires
(5) No smoke exhaust operating

$$\frac{z}{H} = 0.23\left(\frac{t}{t_g^{2/5} H^{4/5}\left(\frac{A}{H^2}\right)^{3/5}}\right)^{-1.45} \qquad \textbf{(5.4.2.2a)}$$

where:
z = distance above the base of the fire to the first indication of smoke (ft)
H = ceiling height above the fire surface (ft)
t = time (sec)
t_g = growth time (sec)
A = cross-sectional area of the space being filled with smoke (ft^2)

$$\frac{z}{H} = 0.91\left(\frac{t}{t_g^{2/5} H^{4/5}\left(\frac{A}{H^2}\right)^{3/5}}\right)^{-1.45} \qquad \textbf{(5.4.2.2b)}$$

where:
z = distance above the base of the fire to the first indication of smoke (m)
H = ceiling height above the fire surface (m)
t = time (sec)
t_g = growth time (sec)
A = cross-sectional area of the space being filled with smoke (m^2)

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

5.5 Rate of Smoke Mass Production.

5.5.1 Axisymmetric Plumes.

5.5.1.1* Where the plume is axisymmetric, the mass rate of smoke production shall be calculated using Equation 5.5.1.1a, 5.5.1.1b, or 5.5.1.1c or Equation 5.5.1.1d, 5.5.1.1e, or 5.5.1.1f as follows:

$$z_l = 0.533 Q_c^{2/5} \quad \textbf{(5.5.1.1a)}$$

$$\text{when } z > z_l,\ m = \left(0.022 Q_c^{1/3} z^{5/3}\right) + 0.0042 Q_c \quad \textbf{(5.5.1.1b)}$$

$$\text{when } z \le z_l,\ m = 0.0208 Q_c^{3/5} z \quad \textbf{(5.5.1.1c)}$$

where:
z_l = limiting elevation (ft)
Q_c = convective portion of heat release rate (Btu/sec)
z = distance above the base of the fire to the smoke layer interface (ft)
m = mass flow rate in plume at height z (lb/sec)

$$z_l = 0.166 Q_c^{2/5} \quad \textbf{[5.5.1.1d]}$$

$$\text{when } z > z_l,\ m = \left(0.071 Q_c^{1/3} z^{5/3}\right) + 0.0018 Q_c \quad \textbf{[5.5.1.1e]}$$

$$\text{when } z \le z_l,\ m = 0.032 Q_c^{3/5} z \quad \textbf{[5.5.1.1f]}$$

where:
z_l = limiting elevation (m)
Q_c = convective portion of heat release rate (kW)
z = distance above the base of the fire to the smoke layer interface (m)
m = mass flow rate in plume at height z (kg/sec)

5.5.1.2 Equations 5.5.1.1b, 5.5.1.1c, 5.5.1.1e, and 5.5.1.1f shall not be used when the temperature rise above ambient ($T_p - T_o$) is less than 4°F (2.2°C). *(See 5.5.5.)*

5.5.1.3 The convective portion of the heat release rate of the fire shall be determined from Equation 5.5.1.3 as follows:

$$Q_c = \chi Q \quad \textbf{(5.5.1.3)}$$

where:
Q_c = convective portion of the heat release rate of the fire (Btu/s or kW)
χ = convective fraction (dimensionless)
Q = heat release rate of the fire (Btu/ft or kW)

5.5.1.4 A value of 0.7 shall be used for the convective fraction unless another value is substantiated in accordance with test data.

5.5.2 Balcony Spill Plumes.

5.5.2.1* Where the smoke plume is a balcony spill plume and the height, z_b, of the smoke layer is <50 ft (15 m), the mass rate of smoke production shall be calculated using either Equation 5.5.2.1a or 5.5.2.1b as follows:

$$m = 0.12\left(QW^2\right)^{1/3}\left(z_b + 0.25H\right) \quad \textbf{(5.5.2.1a)}$$

where:
m = mass flow rate in plume (lb/sec)
Q = heat release rate of the fire (Btu/sec)
W = width of the plume as it spills under the balcony (ft)
z_b = height above the underside of the balcony to the smoke layer interface (ft)
H = height of balcony above base of fire (ft)

$$m = 0.36\left(QW^2\right)^{1/3}\left(z_b + 0.25H\right) \quad \textbf{(5.5.2.1b)}$$

where:
m = mass flow rate in plume (kg/sec)
Q = heat release rate of the fire (kW)
W = width of the plume as it spills under the balcony (m)
z_b = height above the underside of the balcony to the smoke layer interface (m)
H = height of balcony above base of fire (m)

5.5.2.2 Equations 5.5.2.1a and 5.5.2.1b shall not be used when the temperature rise above ambient ($T_p - T_o$) is less than 4°F (2.2°C). *(See 5.5.5.)*

5.5.2.3 The width of the plume, W, shall be permitted to be determined by considering the presence of any physical barriers such as draft curtains protruding below the balcony to restrict horizontal smoke migration under the balcony.

5.5.2.4 Where draft curtains are used, they shall be perpendicular to the opening, in order to channel smoke, and extend below the balcony ceiling a distance of at least 10 percent of the floor-to-ceiling height of the balcony.

5.5.2.5* In the absence of any barriers, the equivalent width shall be calculated using Equation 5.5.2.5 as follows:

$$W = w + b \quad \textbf{(5.5.2.5)}$$

where:
W = width of the plume (ft or m)
w = width of the opening from the area of origin (ft or m)
b = distance from the opening to the balcony edge (ft or m)

5.5.2.6* Where the smoke plume is a balcony spill plume and the height, z_b, of the smoke layer is <50 ft (15 m) and the width of the plume determined using Equation 5.5.2.5a or 5.5.2.5b is <32.8 ft (10 m), the mass flow rate of smoke production shall be calculated using either Equation 5.5.2.6a or 5.5.2.6b.

$$\dot{m}_b = 0.32 \dot{Q}_c^{1/3} W^{1/5}\left(z_b + 0.098 W^{7/15} H + 19.5 W^{7/15} - 49.2\right) \quad \textbf{(5.5.2.6a)}$$

where:
$\dot{m}_b$ = mass flow entering the smoke layer at height z_b (lb/sec)
$\dot{Q}_c$ = convective heat output (Btu/sec)
W = length of the spill (ft)
z_b = height of plume above the balcony edge (ft)
H = height of balcony above the base of the fire (ft)

$$\dot{m}_b = 0.59 \dot{Q}^{1/3} W^{1/5}\left(z_b + 0.17 W^{7/15} H + 10.35 W^{7/15} - 15\right) \quad \textbf{(5.5.2.6b)}$$

where:
$\dot{m}_b$ = mass flow entering the smoke layer at height z_b (kg/s)
$\dot{Q}_c$ = convective heat output (kW)
W = length of the spill (m)
z_b = height of plume above the balcony edge (m)
H = height of balcony above the base of the fire (m)

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

5.5.2.7* Where the smoke plume is a balcony spill plume and the height, z_b, of the smoke layer is ≥50 ft (15 m) and the width of the plume determined using Equation 5.5.2.5a or 5.5.2.5b is ≥32.8 ft (10 m) and ≤45.9 ft (14 m), the mass flow rate of smoke production shall be calculated using Equation 5.5.2.7a or 5.5.2.7b.

$$\dot{m}_b = 0.062\left(\dot{Q}_c W^2\right)^{1/3}\left(z_b + 0.51H + 52\right) \quad \textbf{(5.5.2.7a)}$$

where:
$\dot{m}_b$ = mass flow entering the smoke layer at height z_b (lb/sec)
$\dot{Q}_c$ = convective heat output (Btu/sec)
W = length of the spill (ft)
z_b = height of plume above the balcony edge (ft)
H = height of balcony above the base of the fire (ft)

$$\dot{m}_b = 0.2\left(\dot{Q}_c W^2\right)^{1/3}\left(z_b + 0.51H + 15.75\right) \quad \textbf{(5.5.2.7b)}$$

where:
$\dot{m}_b$ = mass flow entering the smoke layer at height z_b (kg/sec)
$\dot{Q}_c$ = convective heat output (kW)
W = length of the spill (m)
z_b = height of plume above the balcony edge (m)
H = height of balcony above the base of the fire (m)

5.5.2.8* For high smoke layer interface heights ($z_b \geq 50$ ft [15 m]), both a balcony spill plume fire scenario and an atrium fire scenario (axisymmetric plume using Equation 5.5.1.1b or 5.5.1.1e) with appropriate design fire sizes shall be evaluated and the higher mass flow rate used for the design of the atrium smoke management system.

5.5.3* Window Plumes.

5.5.3.1* Where the smoke plume is a window plume, the total heat release rate of a ventilation-limited fire shall be calculated using Equation 5.5.3.1a or 5.5.3.1b as follows:

$$Q = 61.2A_w H_w^{1/2} \quad \textbf{(5.5.3.1a)}$$

where:
Q = heat release rate (Btu/sec)
A_w = area of ventilation opening (ft^2)
H_w = height of ventilation opening (ft)

$$Q = 1260A_w H_w^{1/2} \quad \textbf{(5.5.3.1b)}$$

where:
Q = heat release rate (kW)
A_w = area of ventilation opening (m^2)
H_w = height of ventilation opening (m)

5.5.3.2* Where the smoke plume is a window plume, the mass entrainment for window plumes shall be determined using Equation 5.5.3.2a or 5.5.3.2b as follows:

$$m = \left[0.077\left(A_w H_w^{1/2}\right)^{1/3}\left(z_w + a\right)^{5/3}\right] + 0.18A_w H_w^{1/2} \quad \textbf{(5.5.3.2a)}$$

where:
m = mass flow rate plume at height z_w (lb/sec)
A_w = area of ventilation opening (ft^2)
H_w = height of ventilation opening (ft)
z_w = height above the top of the window (ft)
a = $[2.40A_w^{2/5} H_w^{1/5}] - 2.1H_w$ (ft)

$$m = \left[0.68\left(A_w H_w^{1/2}\right)^{1/3}\left(z_w + a\right)^{5/3}\right] + 1.59A_w H_w^{1/2} \quad \textbf{(5.5.3.2b)}$$

where:
m = mass flow rate plume at height z_w (kg/sec)
A_w = area of ventilation opening (m^2)
H_w = height of ventilation opening (m)
z_w = height above the top of the window (m)
a = $[2.40A_w^{2/5} H_w^{1/5}] - 2.1H_w$ (m)

5.5.3.3 Equations 5.5.1.1b, 5.5.1.1c, 5.5.2.1, and 5.5.3.2 shall not be used when the temperature rise above ambient ($T_p - T_o$) is less than 4°F (2.2°C). *(See 5.5.5.)*

5.5.4* Axisymmetric Plume Diameter.

5.5.4.1 Calculation. The diameter of an axisymmetric plume shall be calculated using Equation 5.5.4.1. The diameter constant can range from 0.25 to 0.5, and the following values shall be used: $K_d = 0.5$ for plume contact with walls and $K_d = 0.25$ for beam detection of the smoke plume

$$d_p = K_d \cdot z \quad \textbf{(5.5.4.1)}$$

where:
d_p = axisymmetric plume diameter (ft or m)
K_d = diameter constant
z = distance above the base of the fire (ft or m)

5.5.4.2 Plume Contact with Walls. When the calculated plume diameter indicates that the plume will come into contact with all the walls of the large-volume space or with two parallel walls of the large-volume space, the point of contact shall be the smoke layer interface.

5.5.5* Smoke Layer Temperature. The temperature of the smoke layer shall be determined in accordance with Equation 5.5.5 as follows:

$$T_s = T_o + \frac{K_s Q_c}{mC_p} \quad \textbf{(5.5.5)}$$

where:
T_s = smoke layer temperature (°F or °C)
T_o = ambient temperature (°F or °C)
K_s = fraction of convective heat release contained in smoke layer
Q_c = convective portion of heat release (Btu/sec or kW)
m = mass flow rate of the plume at elevation z (lb/sec or kg/sec)
C_p = specific heat of plume gases (0.24 Btu/lb-°F or 1.0 kJ/kg-°C)

5.5.5.1 For calculating the volumetric flow rate of smoke exhaust, a value of 1.0 shall be used for the fraction of convective heat release contained in the smoke layer, K_s, unless another value is substantiated in accordance with test data.

5.5.5.2 For calculating the maximum volumetric flow rate, V_{max}, that can be exhausted without plugholing, a value of 0.5 shall be used for the fraction of convective heat release contained in the smoke layer, K_s, unless another value is substantiated in accordance with approved test data.

5.6* Number of Exhaust Inlets.

5.6.1 The minimum number of exhaust inlets shall be determined so that the maximum flow rates for exhaust without plugholing are not exceeded.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

5.6.2 More than the minimum number of exhaust inlets required shall be permitted.

5.6.3* The maximum volumetric flow rate that can be exhausted by a single exhaust inlet without plugholing shall be calculated using Equation 5.6.3a or 5.6.3b.

$$V_{max} = 452\gamma d^{5/2}\left(\frac{T_s - T_o}{T_o}\right)^{1/2} \quad \textbf{(5.6.3a)}$$

where:
V_{max} = maximum volumetric flow rate without plugholing at T_s (ft^3/min)
γ = exhaust location factor (dimensionless)
d = depth of smoke layer below the lowest point of the exhaust inlet (ft)
T_s = absolute temperature of the smoke layer (R)
T_o = absolute ambient temperature (R)

$$V_{max} = 4.16\gamma d^{5/2}\left(\frac{T_s - T_o}{T_o}\right)^{1/2} \quad \textbf{(5.6.3b)}$$

where:
V_{max} = maximum volumetric flow rate without plugholing at T_s (m^3/sec)
γ = exhaust location factor (dimensionless)
d = depth of smoke layer below the lowest point of the exhaust inlet (m)
T_s = absolute temperature of the smoke layer (K)
T_o = absolute ambient temperature (K)

5.6.4* For exhaust inlets centered no closer than twice the diameter from the nearest wall, a value of 1.0 shall be used for γ.

5.6.5* For exhaust inlets centered less than twice the diameter from the nearest wall, a value of 0.5 shall be used for γ.

5.6.6* For exhaust inlets on a wall, a value of 0.5 shall be used for the value of γ.

5.6.7* The ratio d/D_i shall be greater than 2, where D_i is the diameter of the inlet.

5.6.8 For rectangular exhaust inlets, D_i shall be calculated using Equation 5.6.8

$$D_i = \frac{2ab}{a+b} \quad \textbf{(5.6.8)}$$

where:
D_i = diameter of the inlet
a = length of the inlet
b = width of the inlet

5.6.9 Where multiple exhaust inlets are required to prevent plugholing *(see 5.6.1)*, the minimum separation distance shall be calculated using Equation 5.6.9a or 5.6.9b as follows:

$$S_{min} = 0.065V_e^{1/2} \quad \textbf{(5.6.9a)}$$

where:
S_{min} = minimum edge-to-edge separation between inlets (ft)
V_e = volumetric flow rate of one exhaust inlet (ft^3/min)

$$S_{min} = 0.9V_e^{1/2} \quad \textbf{(5.6.9b)}$$

where:
S_{min} = minimum edge-to-edge separation between inlets (m)
V_e = volumetric flow rate of one exhaust inlet (m^3/sec)

5.7* Volumetric Flow Rate. The volumetric flow rate of smoke exhaust shall be determined using Equation 5.7a or 5.7b as follows:

$$V = 60\frac{m}{\rho} \quad \textbf{(5.7a)}$$

where:
V = volumetric flow rate of smoke exhaust (ft^3/min)
m = mass flow rate of smoke exhaust (lb/sec)
ρ = density of smoke (lb/ft^3)

$$V = \frac{m}{\rho} \quad \textbf{(5.7b)}$$

where:
V = volumetric flow rate of smoke exhaust (m^3/sec)
m = mass flow rate of smoke exhaust (kg/sec)
ρ = density of smoke (kg/m^3)

5.8* Density of Smoke. The density of smoke shall be determined using Equation 5.8a or 5.8b as follows:

$$\rho = \frac{144P_{atm}}{R(T+460)} \quad \textbf{(5.8a)}$$

where:
ρ = density of smoke at temperature (lb/ft^3)
P_{atm} = atmospheric pressure ($lb/in.^2$)
R = gas constant (53.34)
T = temperature of smoke (°F)

$$\rho = \frac{P_{atm}}{RT} \quad \textbf{(5.8b)}$$

where:
ρ = density of smoke at temperature (kg/m^3)
P_{atm} = atmospheric pressure (Pa)
R = gas constant (287)
T = absolute temperature of smoke (K)

5.9* Varying Cross-Sectional Geometries and Complex Geometries. When the large space has a nonuniform cross-sectional area, the design analysis shall take into account the variation of cross-sectional area with height.

5.10 Opposed Airflow.

5.10.1 Where opposed airflow is used to prevent smoke originating in a communicating space from propagating into the large-volume space, as shown in Figure 5.10.1, the communicating space shall be exhausted at a sufficient rate to cause the average air velocity in the opening from the large-volume space to exceed the limiting average air velocity, v_e, calculated using Equation 5.10.1a or 5.10.1b as follows:

$$v_e = 38\left(gH\frac{T_f - T_o}{T_f}\right)^{1/2} \quad \textbf{(5.10.1a)}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

where:
v_e = limiting average air velocity (ft/min)
g = acceleration of gravity (32.2 ft/sec^2)
H = height of the opening as measured from the bottom of the opening (ft)
T_f = temperature of heated smoke (R)
T_o = temperature of ambient air (R)

$$v_e = 0.64\left(gH\frac{T_f - T_o}{T_f}\right)^{1/2} \quad \textbf{(5.10.1b)}$$

where:
v_e = limiting average air velocity (m/sec)
g = acceleration of gravity (9.81 m/sec^2)
H = height of the opening as measured from the bottom of the opening (m)
T_f = temperature of heated smoke (K)
T_o = temperature of ambient air (K)



FIGURE 5.10.1 Use of Airflow to Prevent Smoke Propagation from a Communicating Space to a Large-Volume Space.

5.10.2 Where opposed airflow is used to prevent smoke originating from the plume within the large-volume space from propagating into a communicating space below the smoke layer interface, as illustrated in Figure 5.10.2, air shall be supplied from the communicating space at the limiting average velocity, v_e, as calculated in accordance with Equation 5.10.2a or 5.10.2b as follows:

$$v_e = 17\left(\frac{Q}{z}\right)^{1/3} \quad \textbf{(5.10.2a)}$$

where:
v_e = limiting average air velocity (ft/min)
Q = heat release rate of the fire (Btu/sec)
z = distance above the base of the fire to the bottom of the opening (ft)

$$v_e = 0.057\left(\frac{Q}{z}\right)^{1/3} \quad \textbf{(5.10.2b)}$$

where:
v_e = limiting average air velocity (m/sec)
Q = heat release rate of the fire (kW)
z = distance above the base of the fire to the bottom of the opening (m)

5.10.2.1 Where the limiting average air velocity, v_e, calculated from Equation 5.10.2a or 5.10.2b exceeds 200 ft/min (1.02 m/sec), the opposed airflow method shall not be used for the purpose of this subsection.

5.10.2.2 Equations 5.10.2a and 5.10.2b shall not be used when z is less than 10 ft (3 m).

5.10.3 Where opposed airflow is used to prevent smoke originating in the large-volume space from propagating into a communicating space above the smoke layer interface, as shown in Figure 5.10.3, air shall be supplied from the communicating space at the limiting average velocity,



FIGURE 5.10.2 Use of Airflow to Prevent Smoke Propagation from the Plume Within the Large-Volume Space to a Communicating Space Located Below the Smoke Layer Interface.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.



FIGURE 5.10.3 Use of Airflow to Prevent Smoke Propagation from a Large-Volume Space to a Communicating Space Located Above the Smoke Layer Interface.

v_e, as determined in accordance with Equation 5.10.3a or 5.10.3b as follows:

$$v_e = 38\left(gH\frac{T_f - T_o}{T_f}\right)^{1/2} \quad \textbf{(5.10.3a)}$$

where:
v_e = limiting average air velocity (ft/min)
g = acceleration of gravity (32.2 ft/sec^2)
H = height of the opening as measured from the bottom of the opening (ft)
T_f = temperature of heated smoke (R)
T_o = temperature of ambient air (R)

$$v_e = 0.64\left(gH\frac{T_f - T_o}{T_f}\right)^{1/2} \quad \textbf{(5.10.3b)}$$

where:
v_e = limiting average air velocity (m/sec)
g = acceleration of gravity (9.81 m/sec^2)
H = height of the opening as measured from the bottom of the opening (m)
T_f = temperature of heated smoke (K)
T_o = temperature of ambient air (K)

5.10.3.1 Where the limiting average air velocity, v_e, calculated from Equation 5.10.3a or 5.10.3b exceeds 200 ft/min (1.02 m/sec), the opposed airflow method shall not be used for the purpose of this subsection.

5.10.3.2 The mass flow rate of air supply from the communicating space shall be included in the design of the smoke exhaust for the large-volume space.

5.11* Scaling Laws.

5.11.1 The scale model shall be based on the relationships in Table 5.11.1.

5.11.2 The model shall be made large enough that the height of one story in the scale model or the design height of the smoke interface is not less than 1 ft (0.3 m).

Table 5.11.1 Scaling Expressions

Characteristic Relationship	Expression
Geometric position	$x_m = x_F\,(l_m/l_F)$
Temperature	$T_m = T_F$
Pressure difference	$\Delta p_m = \Delta p_F\,(l_m/l_F)$
Velocity	$v_m = v_F\,(l_m/l_F)^{1/2}$
Total heat release rate	$Q_m = Q_F\,(l_m/l_F)^{5/2}$
Convective heat release rate	$Q_{c,m} = Q_{c,F}\,(l_m/l_F)^{5/2}$
Volumetric exhaust rate	$V_{fan,m} = V_{fan,F}\,(l_m/l_F)^{5/2}$
Time	$t_m = t_F\,(l_m/l_F)^{1/2}$

where:
l = length
Δp = pressure difference
Q = heat release rate
t = time
T = temperature (ambient and smoke)
v = velocity
V = volumetric exhaust rate
x = position
Subscripts:
c = convective
F = full-scale
m = small-scale model

Chapter 6 Building Equipment and Controls

6.1 General. Equipment and controls used for smoke control purposes shall be in accordance with this chapter.

6.2* Heating, Ventilating, and Air-Conditioning (HVAC) Equipment.

6.2.1 General. HVAC equipment used for smoke control purposes shall be permitted to be located within the conditioned space, within adjacent spaces, or within remote mechanical equipment rooms.

6.2.2 Outside Air. HVAC systems used for smoke control purposes shall be provided with outside air for pressurization.

6.2.3 Where supply and return air systems are interconnected as part of normal HVAC operation, smoke dampers shall be provided to separate the supply and exhaust during smoke control operation.

6.2.4* Makeup Air System. For smoke management systems with makeup air supplied by fans, supply fan actuation shall be sequenced with exhaust fan activation.

6.3 Smoke Dampers.

6.3.1 Smoke dampers used to protect openings in smoke barriers or used as safety-related dampers in engineered smoke control systems shall be listed and labeled in accordance with ANSI/UL 555S, *Standard for Smoke Dampers.*

6.3.2 Combination fire and smoke dampers shall be listed and labeled in accordance with ANSI/UL 555, *Standard for Fire Dampers,* and ANSI/UL 555S, *Standard for Smoke Dampers.*

6.4* Smoke Control Systems.

6.4.1 Control systems shall be listed in accordance with ANSI/UL 864, *Standard for Control Units and Accessories for Fire Alarm Systems,* category UUKL, for their intended purpose.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

6.4.2 Coordination. A single control system shall coordinate the functions provided by the fire alarm system, fire fighters' smoke control station (FSCS), and any other related systems with the operation of the building HVAC systems and dedicated smoke control equipment.

6.4.3* HVAC System Controls. Operating controls of the HVAC system shall be designed or modified to provide the smoke control mode with the highest priority over all other control modes.

6.4.4 Activation and Deactivation.

6.4.4.1 Automatic Activation.

6.4.4.1.1* Smoke control systems shall be automatically activated in response to signals received from a specific fire detection device or a combination of fire detection devices.

6.4.4.1.2* In the event that signals are received from more than one smoke zone, the system shall continue automatic operation in the mode determined by the first signal received except as provided for in 6.4.4.1.3.

6.4.4.1.3* For systems designed for operation of multiple zones using only heat-activated detection devices, it shall be permitted to expand the control strategy to accommodate additional zones, up to the limits of the mechanical system design.

6.4.4.1.4* Schedule. The equipment to be operated for each automatically activated smoke control configuration shall be fully defined in the project documents.

6.4.4.1.5* Stratification of Smoke. For large spaces where smoke stratification can occur, one of the following detection schemes shall be used:

(1)*An upward beam to detect the smoke layer
(2)*Detection of the smoke layer at various levels
(3)*Horizontal beams to detect the smoke plume

6.4.4.2 Manual Activation.

6.4.4.2.1* Where approved by the authority having jurisdiction, manual activation by an authorized user shall be permitted.

6.4.4.2.2* Manual fire alarm pull stations shall not be used to activate smoke control systems that require information on the location of the fire.

6.4.4.2.3* Stairwell pressurization systems or other smoke management systems where the response of the system is identical for all zone alarms shall be permitted to be activated from a manual fire alarm pull station.

6.4.4.2.4 Fire alarm pull stations shall be permitted to cause doors in smoke barrier walls to close.

6.4.4.2.5* Manual activation and deactivation shall be permitted to be at a controlled device, at a local control panel, at the building's main control center, or at the fire command station.

6.4.4.2.6 Key-operated manual switches that are clearly marked to identify their function shall be permitted to manually activate the smoke control system.

6.4.5 FSCS Activation.

6.4.5.1 Smoke control systems shall be capable of being activated from the FSCS by switches clearly marked to identify the location and function.

6.4.5.2 Sequence of Control Priorities. Smoke control systems shall be subject to the sequences of control priorities given in 6.4.5.2.1, 6.4.5.2.2, and 6.4.5.2.2.2.

6.4.5.2.1 Automatic Activation.

6.4.5.2.1.1 Automatic activation of systems and equipment for smoke control shall have the highest priority over all other sources of automatic control within the building.

6.4.5.2.1.2* Except as provided for in 6.4.5.2.1.3, where equipment used for smoke control is also used for normal building operation, control of this equipment shall be preempted or overridden as required for smoke control.

6.4.5.2.1.3 The following controls shall not be automatically overridden:

(1) Static pressure high limits
(2) Duct smoke detectors on supply air systems

6.4.5.2.2 Manual Activation and Deactivation.

6.4.5.2.2.1 Manual activation or deactivation of smoke control systems and equipment shall have priority over automatic activation of smoke control systems and equipment and all other sources of automatic control within the building and over prior manual smoke control activation or deactivation commands.

6.4.5.2.2.2 If equipment used for smoke control is subject to automatic activation in response to an alarm from an automatic fire detector of a fire alarm system, or if such equipment is subject to automatic control according to building occupancy schedules, energy management strategies, or other nonemergency purposes, such automatic control shall be preempted or overridden by manual activation or deactivation of the smoke control equipment.

6.4.5.2.2.3 Manual controls provided specifically for manual activation or deactivation for smoke control purposes shall be clearly marked to indicate the location and function served.

6.4.5.2.2.4 Operation of manual controls that are shared both for smoke control functions and for other building control purposes, as in a building's main control center, shall fully cover the smoke control functionality in operational documentation for the control center.

6.4.5.2.3 FSCS Activation. The FSCS shall have the highest priority control over all smoke control systems and equipment.

6.4.5.3 Response Time.

6.4.5.3.1 The smoke control mode shall be initiated within 10 seconds after an automatic, manual, or FSCS activation command is received at the smoke control system.

6.4.5.3.2* Smoke control systems shall activate individual components (e.g., dampers, fans) in the sequence necessary to prevent physical damage to the fans, dampers, ducts, and other equipment.

6.4.5.3.3* Smoke Containment Systems. The time necessary for individual smoke containment components to achieve their desired state or operational mode from when the component receives the signal shall not exceed the following time periods:

(1) Fan operation at the desired state: 60 seconds
(2) Completion of damper travel: 75 seconds

6.4.5.3.4* Smoke Management Systems. The total response time, including that necessary for detection, shutdown of smoke management operating equipment, and smoke control system startup, shall allow for full operational mode to be achieved before the conditions in the space exceed the design smoke conditions.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

6.4.5.4* Fire Fighters' Smoke Control Station (FSCS).

6.4.5.4.1 An FSCS shall be provided for all smoke control systems.

6.4.5.4.2 The FSCS shall be installed at a location acceptable to the authority having jurisdiction.

6.4.5.4.3* The FSCS shall provide status indication, fault condition indication, and manual control of all smoke control system components.

6.4.5.4.4 Status indicators and controls shall be arranged and labeled to convey the intended system objectives.

6.4.5.4.5 Operator controls, status indication, and fault indication shall be provided for each smoke control zone, each piece of equipment capable of activation for smoke control, or a combination of these approaches.

6.4.5.4.6 Positive status indication (ON and OFF) shall be provided individually or by zone in accordance with 6.4.5.4.5 for the following:

(1) Dedicated smoke control system fans
(2) Nondedicated fans used for smoke control having a capacity in excess of 2000 ft^3/min (57 m^3/min)

6.4.5.4.7* ON status shall be sensed by a pressure difference, an airflow switch, or some other positive proof of airflow.

6.4.5.4.8 Positive status indication (fully open and fully closed) of damper position shall be provided if individual controls for the damper are provided on the FSCS.

6.4.5.4.9 Provision shall be included for testing the pilot lamps on the FSCS control panel(s) by means of one or more "LAMP TEST" momentary push buttons or other self-restoring means.

6.4.5.4.10 Diagrams and graphic representations of the system shall be used.

6.4.5.4.11 The FSCS shall have the highest priority control over all smoke control systems and equipment.

6.4.5.4.12 Where manual controls for control of smoke control systems are also provided at other building locations, the control mode selected from the FSCS shall prevail.

6.4.5.4.13 FSCS control shall override or bypass other building controls such as hand-off-auto and start/stop switches located on fan motor controllers, freeze detection devices, and duct smoke detectors except as provided by 6.4.5.4.13.1.

6.4.5.4.13.1 The FSCS fan control capability shall not be required to bypass hand-off-auto or start/stop switches located on motor controllers of nondedicated smoke control system fans where both of the following conditions exist:

(1) Such fan motor controllers are located in mechanical or electrical equipment rooms or in other areas accessible only to authorized personnel.
(2) The use of such a motor controller switch to turn a fan on or off will cause an off-normal indication at the building's main control center during normal HVAC or building control operations of the nondedicated fan.

6.4.5.4.14 FSCS control shall not take precedence over fire suppression, electrical protection, or personnel protection devices.

6.4.6 Controls for Stairwell Pressurization Systems. When stairwell pressurization systems are provided, they shall be activated as described in 6.4.6.1 through 6.4.6.4.1.

6.4.6.1 Automatic Activation.

6.4.6.1.1* Operation of any zone of the building fire alarm system shall cause all stairwell pressurization fans to start except as indicated in 6.4.6.1.2.

6.4.6.1.2 Where an engineering analysis determines that operation of all stairwell pressurization fans is not required to achieve the design objective, only the stairwell pressurization fans identified during the analysis shall be required to be activated.

6.4.6.2 Smoke Detection.

6.4.6.2.1 A smoke detector shall be provided in the air supply to the pressurized stairwell.

6.4.6.2.2 On detection of smoke in the air supply, the supply fan(s) shall be stopped.

6.4.6.3 Manual Pull Stations. Stairwell pressurization systems where the response of the system is identical for all zone alarms shall be permitted to be activated from a manual fire alarm pull station.

6.4.6.4 FSCS Activation.

6.4.6.4.1 Manual activation and deactivation control of the stairwell pressurization systems shall be provided at the FSCS.

6.4.6.4.2 An override switch shall be permitted to be provided at the FSCS to restart the stairwell pressurization fan(s) after shutdown from the smoke detector.

6.4.7 Controls for Zoned Smoke Control Systems.

6.4.7.1 General. When zoned smoke control systems are provided, they shall be activated as described in 6.4.7.2.1 and 6.4.7.2.2.

6.4.7.2 Automatic Activation.

6.4.7.2.1* When signals from fire alarm systems are used to activate the zoned smoke control system(s), the fire alarm zones shall be arranged to coincide with the smoke containment zones.

6.4.7.2.2 Where an automatic smoke detection system is used to automatically activate a zoned smoke control system, the smoke detection system shall be permitted to be of limited coverage having spacing greater than 900 ft^2 (84 m^2) per detector.

6.4.7.2.3 Where an automatic smoke detection system is used to automatically activate a zoned smoke control system, the location of smoke detectors and the zoning of the detectors shall be arranged to detect smoke before it leaves the smoke zone.

6.4.7.2.4 Where a waterflow switch or heat detector is used to activate a zoned smoke control system, zoning of such systems shall coincide with the smoke containment zone.

6.4.7.3* Zoned smoke control systems shall not be activated from manual fire alarm pull stations.

6.4.8* Control System Verification.

6.4.8.1 Every dedicated smoke control system and each dedicated smoke control subsystem in a nondedicated smoke control system shall have a means of verifying correct operation when activated.

6.4.8.2 Verification shall include positive confirmation of activation, testing, manual override, and the presence of operating power downstream of all circuit disconnects.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

6.4.8.3 Failure to receive positive confirmation after activation or cessation of such positive confirmation while the system or subsystem remains activated shall result in an off-normal indication at the smoke control system within 200 seconds.

6.4.8.4 Fire alarm signaling paths to the smoke control system shall be monitored for integrity in accordance with 10.17.1 of *NFPA 72, National Fire Alarm and Signaling Code*, with trouble annunciation provided at the FSCS, unless both of the following conditions are met:

(1) The interconnecting wiring between the fire alarm system and the smoke control system is located within 20 ft (6.1 m) of each other.
(2) The conductors are installed in conduit or equivalently protected against mechanical injury.

6.4.8.5 Ground-fault annunciation shall not be required where receipt of the activation signal by the smoke control system is not affected by a single ground fault.

6.4.8.6 Operational capability of dedicated smoke control equipment shall be verified using the weekly self-test function provided by the UUKL-listed smoke control panel mandated by 6.4.1.

6.5 Energy Management. Energy management systems, particularly those that cycle supply, return, and exhaust fans for energy conservation, shall be overridden when their control or operation is in conflict with a smoke control mode.

6.6 Materials.

6.6.1 Materials used for systems providing smoke control shall conform to NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, and other applicable NFPA documents.

6.6.2 Duct materials shall be selected and ducts shall be designed to convey smoke, to withstand additional pressure (both positive and negative) by the supply and exhaust fans when operating in a smoke control mode, and to maintain their structural integrity during the period for which the system is designed to operate.

6.6.3* Equipment, including but not limited to fans, ducts, and balance dampers, shall be suitable for its intended use and the probable temperatures to which it is likely to be exposed.

6.7 Electric Services Installation.

6.7.1 All electrical installations shall meet the requirements of *NFPA 70, National Electrical Code*.

6.7.2 The smoke control system shall be designed so that loss of normal power for a period of up to 15 minutes will result in the components automatically performing their function upon restoration of power.

6.7.3 Where standby power is provided in accordance with NFPA 110, *Standard for Emergency and Standby Power Systems*, the standby power source and related transfer switches shall be separated from transformers and switch gear for the primary power supply and enclosed in a room with a 1-hour fire resistance–rated fire barrier wall installed in accordance with NFPA 221, *Standard for High Challenge Fire Walls, Fire Walls, and Fire Barrier Walls*.

Chapter 7 Smoke Control System Documentation

7.1 Documentation Required. The following documents shall be generated by the designer during the design process:

(1) Detailed design report
(2) Operations and maintenance manual

7.2 Detailed Design Report.

7.2.1 The detailed design report shall provide documentation of the smoke control system as it is designed and intended to be installed.

7.2.2 The design report shall include the following elements, if applicable:

(1) System purpose
(2) System design objectives
(3) Design approach
(4) Design assumptions (building height, ambient conditions, reliance on other fire protection systems, leakage, etc.)
(5) Location of smoke zone(s)
(6) Design pressure differences
(7) Building use limitations that arise out of the system design
(8) Design calculations
(9) Fan and duct specifications
(10) Damper specifications
(11) Detailed inlet or exhaust inlets site information
(12) Detailed method of activation
(13) Smoke control system operation logic
(14) System commissioning procedures

7.3* Operations and Maintenance Manual. The operations and maintenance manual shall provide the requirements to ensure the proper operation of the system over the life of the building.

7.3.1 The operations and maintenance manual shall include the following:

(1) The procedures used in the initial commissioning of the system as well as the measured performance of the system at the time of commissioning
(2) The testing and inspection requirements for the system and system components and the required frequency of testing *(see Chapter 8)*
(3) The critical design assumptions used in the design and limitations on the building and its use that arise out of the design assumptions and limitations
(4) The purpose of the smoke control system

7.3.2 Copies of the operations and maintenance manual shall be provided to the owner and the authorities having jurisdiction.

7.3.3 The building owner shall be responsible for all system testing and shall maintain records of all periodic testing and maintenance in accordance with the operations and maintenance manual.

7.3.4 The building owner shall be responsible for limiting the use of the space in a manner consistent with the limitations provided in the operations and maintenance manual.

Chapter 8 Testing

8.1* General.

8.1.1 Each smoke control system shall be tested against its specific design criteria.

8.1.2 Testing shall confirm that the design objectives described in Section 4.1 are achieved.

8.1.3 Design documents shall include all acceptance testing procedures and pass/fail criteria.

8.1.4* Responsibility for each phase of the testing shall be defined clearly prior to commencing inspection and testing.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

8.2 Preliminary Building Inspections.

8.2.1 Prior to testing, the party responsible for testing shall verify completeness of building construction.

8.2.2 The following architectural features, where applicable, shall be inspected:

(1) Smoke barriers, including joints therein
(2) Shaft integrity
(3) Firestopping
(4) Doors/closers
(5) Glazing, including that enclosing a large-volume space
(6) Partitions and ceilings

8.3* Component System Testing.

8.3.1 An operational test of each smoke control system component and subsystem shall be performed prior to the acceptance test.

8.3.2 Operational tests shall be performed prior to interconnection of individual components and subsystems to the smoke control system.

8.3.3* Smoke control system operational testing shall include all subsystems to the extent that they affect the operation of the smoke control system.

8.3.4 Requirements and responsibilities for each component test shall be identified in the design documentation.

8.3.5 All documentation from component system testing relative to the smoke control system shall be included in the final testing documentation.

8.4 Acceptance Testing.

8.4.1* General. Acceptance testing shall demonstrate that the final integrated system installation complies with the specific design and is functioning properly.

8.4.2* Test Parameters. Where appropriate to the design, all parameters shall be measured during acceptance testing.

8.4.3* Measurement Locations. The locations for measurement of the parameters identified in 8.4.2 shall be in accordance with nationally recognized methods.

8.4.4 Testing Procedures. The acceptance testing shall include the procedures described in 8.4.4.1 through 8.4.4.4.

8.4.4.1* Prior to beginning acceptance testing, all building equipment shall be placed in the normal operating mode, including equipment that is not used to implement smoke control.

8.4.4.2* If standby power has been provided for the operation of the smoke control system, the acceptance testing shall be conducted while on both normal and standby power.

8.4.4.3 The acceptance testing shall include demonstrating that the correct outputs are produced for a given input for each control sequence specified.

8.4.4.4 The complete smoke control sequence shall be demonstrated for the following:

(1) Normal mode
(2)*Automatic smoke control mode for first alarm
(3) Transfer to standby power if provided.
(4) Return to normal

8.4.4.5 The force necessary to open each egress door shall be measured using a spring-type scale and recorded.

8.4.4.6 Door-opening forces shall not exceed those allowed by the building code.

8.4.4.7 Activation of each smoke control system response to all means of activation, both automatic and manual, as specified in the design report and operations and maintenance manual in Chapter 7, shall be verified and recorded.

8.4.4.8 The proper operation of all fans, dampers, and related equipment, as outlined by the project documents referenced in 6.4.4.1.4, shall be verified and recorded.

8.4.5* Testing of Smoke Management Systems in Large-Volume Spaces. Acceptance testing to verify systems performance shall include the following:

(1) Prior to performance testing:
   (a) Verify the exact location of the perimeter of each large-volume space smoke management system, identify any door openings into that space, and identify all adjacent areas that are to remain open and that are to be protected by airflow alone.
   (b) For larger openings, measure the velocity by making appropriate traverses of the opening.
(2) Activate the smoke management system, then do the following:
   (a) Verify and record the operation of all fans, dampers, doors, and related equipment.
   (b) Measure fan exhaust capacities and air velocities through inlet doors and grilles or at supply grilles if there is a mechanical makeup air system.
   (c) Measure the force to open exit doors.
(3) Where appropriate to the design, measure and record the pressure difference across all doors that separate the smoke management system area from adjacent spaces and the velocities at interfaces with open areas.

8.4.6 Testing of Smoke Containment Systems.

8.4.6.1 Pressure Testing.

8.4.6.1.1 With the containment system activated, the pressure difference across each smoke barrier shall be measured and recorded with all interior doors closed.

8.4.6.1.2 If an exterior door would normally be open during evacuation, it shall be open during testing.

8.4.6.1.3 The HVAC system shall be off unless the normal mode is to leave the HVAC system on during smoke control operations.

8.4.6.1.4* With the containment system activated and the number of egress doors used in the system design open, the pressure difference across the barrier shall be measured and recorded.

8.4.6.1.5 No pressure difference shall be less than the minimum design pressure differences in Table 4.4.2.1.1 or the pressures specified in the design documents.

8.4.6.2* Force Testing.

8.4.6.2.1 With the containment system activated and the number of doors used in the system design open, the force necessary to open each egress door shall be measured and recorded.

8.4.6.2.2 All other doors shall be closed when the measurements specified in 8.4.6.2.1 are made.

8.4.6.3 Stairwell Pressurization Systems.

8.4.6.3.1 The requirements in 8.4.6.3 shall apply where stairwell pressurization is the only smoke control system in the building.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

8.4.6.3.2 Where stairwell pressurization is used in combination with zoned smoke control, the requirements of 8.4.6.7.1 shall apply.

8.4.6.3.3 Pressurized stairwell vestibules shall be treated as a zone in a zoned smoke control system. *(See 8.4.6.4.)*

8.4.6.4* Zoned Smoke Control System.

8.4.6.4.1 The requirements in 8.4.6.4 shall apply where zoned smoke control is the only smoke control system in the building.

8.4.6.4.2 Normal HVAC Mode.

8.4.6.4.2.1 The pressure difference across all smoke control zones that divide a building floor shall be measured and recorded while the HVAC systems serving the floor's smoke zones are operating in their normal (non-smoke control) mode and while all smoke barrier doors that separate the floor zones are closed.

8.4.6.4.3 Smoke Control Mode for Each Smoke Control Zone.

8.4.6.4.3.1 Each separate smoke control zone shall be activated by a simulated fire alarm input.

8.4.6.4.3.2 The pressure difference across all smoke barriers that separate the smoke zone from adjacent zones shall be measured and recorded.

8.4.6.4.3.3 The measurements shall be made while all smoke barrier doors that separate the smoke zone from the other zones are fully closed.

8.4.6.4.3.4 One measurement shall be made across each smoke barrier or set of doors, and the data shall clearly indicate the higher and lower pressure sides of the doors or barriers.

8.4.6.4.3.5 Doors that have a tendency to open slightly due to the pressure difference shall have one pressure measurement made while held closed and another made while not held closed.

8.4.6.4.3.6* Testing, as described in 8.4.6.4.3.1, shall continue until all fire alarm inputs have been activated.

8.4.6.5* Elevator Smoke Control Systems.

8.4.6.5.1 Elevator Hoistway Pressurization Systems.

8.4.6.5.1.1 General.

(A) The requirements in 8.4.6.5.1 shall apply where elevator hoistway pressurization is the only smoke control system in the building.

(B) Where elevator hoistway pressurization is used in combination with zoned smoke control, the requirements of 8.4.6.7.3 shall apply.

8.4.6.5.1.2 Pressure Testing.

(A) With the elevator pressurization system activated, the pressure difference across each elevator door with all elevator doors closed shall be measured and recorded.

(B) If the elevator door on the recall floor would normally be open during system pressurization, it shall be open during testing.

(C) The HVAC system shall be off unless the normal mode is to leave the HVAC system on during smoke control operations.

(D) If the elevator pressurization system has been designed to operate during elevator movement, the tests in 8.4.6.5.1.2(A) through 8.4.6.5.1.2(C) shall be repeated under these conditions.

8.4.6.5.2 Lobby Pressurization Systems.

8.4.6.5.2.1 General.

(A) The requirements in 8.4.6.5.2 shall apply where enclosed elevator lobby pressurization is the only smoke control system in the building.

(B) Where elevator lobby pressurization is used in combination with zoned smoke control, the requirements of 8.4.6.7.3 shall apply.

(C)* Where enclosed elevator lobbies are pressurized by an elevator lobby pressurization system, or where enclosed elevator lobbies receive secondary pressurization from the elevator hoistway, the requirements of 8.4.6.7.3 shall apply.

8.4.6.6 Smoke Refuge Area.

8.4.6.6.1 A smoke refuge area shall be treated as a zone in a zoned smoke control system.

8.4.6.6.2 The tests outlined in 8.4.6.4 shall be conducted.

8.4.6.7 Combination of Smoke Control Systems.

8.4.6.7.1* Stairwell and Zoned Smoke Control System.

8.4.6.7.1.1 The stairwell pressurization system shall be considered as one zone in a zoned smoke control system.

8.4.6.7.1.2 The tests outlined in 8.4.6.1, 8.4.6.2, and 8.4.6.4 shall be conducted.

8.4.6.7.1.3 All tests shall be conducted with both systems operating in response to a simulated fire alarm input.

8.4.6.7.2 Smoke Refuge Area and Zoned Smoke Control System.

8.4.6.7.2.1 A smoke refuge area shall be treated as a separate zone in a zoned smoke control system.

8.4.6.7.2.2 The tests outlined 8.4.6.4 shall be conducted.

8.4.6.7.3 Elevator Pressurization and Zoned Smoke Control System.

8.4.6.7.3.1 The elevator pressurization system shall be considered as one zone in a zoned smoke control system.

8.4.6.7.3.2 Each elevator lobby in an enclosed elevator lobby pressurization system shall be considered as one zone in a zoned smoke control system.

8.4.6.7.3.3 The tests outlined in 8.4.6.4 shall be conducted.

8.4.6.7.3.4 The tests outlined in 8.4.6.5.1 shall be conducted if a hoistway pressurization system is present.

8.4.6.7.3.5 The tests outlined in 8.4.6.5.2 shall be conducted if a lobby pressurization system is present.

8.4.6.7.3.6 The tests outlined in both 8.4.6.5.1 and 8.4.6.5.2 shall be conducted if both systems are present.

8.4.7 Tests of Fire Fighter's Smoke Control Station.

8.4.7.1 All inputs to and outputs from the FSCS shall be tested.

8.4.7.2 Tests shall include manual override of normal and automatic smoke control modes.

8.5 Testing Documentation.

8.5.1* Upon completion of acceptance testing, a copy of all operational testing documentation shall be provided to the owner and to the authority having jurisdiction.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

8.5.2 Owner's manuals containing complete data on the smoke control system and instructions for operating and maintaining the system shall be provided to the owner.

8.6 Periodic Testing.

8.6.1* Proper maintenance of the system shall, as a minimum, include the periodic testing of all equipment, such as initiating devices, fans, dampers, controls, doors, and windows.

8.6.2 The equipment shall be maintained in accordance with the manufacturer's recommendations.

8.6.3 The periodic tests shall determine the airflow quantities and the pressure differences at the following locations:

(1) Across smoke barrier openings
(2) At the air makeup supplies
(3) At smoke exhaust equipment

8.6.4 All data points shall coincide with the acceptance test location to facilitate comparison measurements.

8.6.5 The system shall be tested by persons who are thoroughly knowledgeable in the operation, testing, and maintenance of the systems.

8.6.5.1 The results of the tests shall be documented in the operations and maintenance log and made available for inspection.

8.6.5.2 The smoke control system shall be operated for each sequence in the current design criteria.

8.6.5.3 The operation of the correct outputs for each given input shall be observed.

8.6.5.4 Tests shall also be conducted under standby power if applicable.

8.6.6 Special arrangements shall be considered for the introduction of large quantities of outside air into occupied areas or sensitive equipment spaces when outside temperature and humidity conditions are extreme and when such unconditioned air could damage contents.

8.6.7 Dedicated systems shall be tested at least semiannually.

8.6.8 Nondedicated systems shall be tested at least annually.

8.7 Modifications.

8.7.1* All operational and acceptance testing shall be performed on the applicable part of the system whenever the system is changed or modified.

8.7.2 If the smoke control system or the zone boundaries have been modified since the last test, acceptance testing shall be conducted on the portion modified.

8.7.3 Documentation shall be updated to reflect these changes or modifications.

Annex A Explanatory Material

Annex A is not a part of the requirements of this NFPA document but is included for informational purposes only. This annex contains explanatory material, numbered to correspond with the applicable text paragraphs.

A.1.1 This standard incorporates methods for applying engineering calculations and reference models to provide a designer with the tools to develop smoke control system designs. The designs are based on select design objectives presented in Section 4.1.

This standard addresses the following topics:

(1) Basic physics of smoke movement in indoor spaces
(2) Methods of smoke control
(3) Supporting data and technology
(4) Building equipment and controls applicable to smoke control systems
(5) Approaches to testing and maintenance methods

This standard does not address the interaction of sprinklers and smoke control systems. The cooling effect of sprinklers can result in some of the smoke losing buoyancy and migrating downward below the design smoke layer interface. This standard also does not provide methodologies to assess the effects of smoke exposure on people, property, or mission continuity.

A.3.2.1 Approved. The National Fire Protection Association does not approve, inspect, or certify any installations, procedures, equipment, or materials; nor does it approve or evaluate testing laboratories. In determining the acceptability of installations, procedures, equipment, or materials, the authority having jurisdiction may base acceptance on compliance with NFPA or other appropriate standards. In the absence of such standards, said authority may require evidence of proper installation, procedure, or use. The authority having jurisdiction may also refer to the listings or labeling practices of an organization that is concerned with product evaluations and is thus in a position to determine compliance with appropriate standards for the current production of listed items.

A.3.2.2 Authority Having Jurisdiction (AHJ). The phrase "authority having jurisdiction," or its acronym AHJ, is used in NFPA documents in a broad manner, since jurisdictions and approval agencies vary, as do their responsibilities. Where public safety is primary, the authority having jurisdiction may be a federal, state, local, or other regional department or individual such as a fire chief; fire marshal; chief of a fire prevention bureau, labor department, or health department; building official; electrical inspector; or others having statutory authority. For insurance purposes, an insurance inspection department, rating bureau, or other insurance company representative may be the authority having jurisdiction. In many circumstances, the property owner or his or her designated agent assumes the role of the authority having jurisdiction; at government installations, the commanding officer or departmental official may be the authority having jurisdiction.

A.3.2.4 Listed. Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or service meets appropriate designated standards or has been tested and found suitable for a specified purpose.

A.3.3.2 Ceiling Jet. Normally, the temperature of the ceiling jet is greater than the adjacent smoke layer.

A.3.3.4 Design Pressure Difference. Protected spaces include the nonsmoke zones in a zoned smoke control system, the stairwells in a stairwell pressurization system, a smoke refuge area, and the elevator shaft in an elevator hoistway system.

A.3.3.8 Fire Fighters' Smoke Control Station (FSCS). Other fire fighters' systems (such as voice alarm, public address, fire

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

department communication, and elevator status and controls) are not covered in this document.

A.3.3.11 Plume. A plume entrains air as it rises so that the mass flow of the plume increases with height and the temperature and other smoke properties of the plume decrease with height.

A.3.3.11.1 Axisymmetric Plume. Strictly speaking, an axisymmetric plume applies only to round fires, but it is a useful idealization for fires of many other shapes. When the largest dimension of a fire is much less than the height of the plume, the plume mass flow and temperature can be approximated by those characteristics of an axisymmetric plume.

An axisymmetric plume *(see Figure A.3.3.11.1)* is expected for a fire originating on the atrium floor, removed from any walls. In that case, air is entrained from all sides along the entire height of the plume until the plume becomes submerged in the smoke layer.



FIGURE A.3.3.11.1 Approximation of an Axisymmetric Plume.

A.3.3.11.2 Balcony Spill Plume. A balcony spill plume is one that flows under and around a balcony before rising, giving the impression of spilling from the balcony, from an inverted perspective, as illustrated in Figure A.3.3.11.2.

A.3.3.11.3 Window Plume. Plumes issuing from wall openings, such as doors and windows of an adjacent compartment, into a large-volume open space are referred to as window plumes *(see Figure A.3.3.11.3)*. Window plumes usually occur when the adjacent compartment is fully involved in a fire typically after the compartment has reached flashover.

A.3.3.13.1 First Indication of Smoke. See Figure A.3.3.13.1. For design evaluations using the algebraic approach outlined in Chapter 5, the first indication of smoke can be determined using Equations 5.4.2.1(a) and (b) and Equations 5.4.2.2(a) and (b).

For design evaluations using physical or computational fluid dynamics (CFD) modeling, a method to define the smoke interface height and the first indication of smoke using a limited number of point measurements over the height of the atrium is required. One approach (Cooper et al. [4]; Madrzykowski and Vettori [29]) uses linear interpolation of the point measurements. Using temperature data, the interfaces are at the heights at which the temperature is as follows:

$$T_n = C_n\left(T_{\max} - T_b\right) + T_b \qquad \textbf{(A.3.3.13.1)}$$

where:

T_n = temperature at the interface height
C_n = interpolation constant with values of 0.1–0.2 for the first indication of smoke and 0.8–0.9 for the smoke layer interface, respectively
$T_{\max}$ = temperature in the smoke layer
T_b = temperature in the cold lower layer

A.3.3.14 Smoke Barrier. A smoke barrier might or might not have a fire resistance rating. Such barriers might have protected openings. Smoke barriers as used with smoke control or smoke management systems described in this standard could have openings protected either by physical opening protectives or by pressure differences created by the smoke control or smoke management system. Smoke barriers described in some other codes and standards might require that the openings be protected by physical opening protectives.

A.3.3.15 Smoke Containment. Smoke containment can be achieved by using smoke barriers alone. This standard deals with active mechanical systems. Passive smoke containment achieved by construction features are outside the scope of this document. For further information on the use of smoke barriers, see the requirements in NFPA *101, Life Safety Code®*, and *NFPA 5000, Building Construction and Safety Code®*.



FIGURE A.3.3.11.2 Approximation of a Balcony Spill Plume.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.



FIGURE A.3.3.11.3 Approximation of a Window Plume.



FIGURE A.3.3.13.1 First Indication of Smoke.

A.3.3.17.3 Communicating Space. Communicating spaces can open directly into the large-volume space or connect through open passageways.

A.3.3.18.2 Dedicated Smoke Control System. Dedicated smoke-control systems are separate systems of air-moving and distribution equipment that do not function under normal building operating conditions.

Advantages of dedicated systems include the following:

(1) Modification of system controls after installation is less likely.
(2) Operation and control of the system is generally simpler.
(3) Reliance on or impact by other building systems is limited.

Disadvantages of dedicated systems include the following:

(1) System impairments might go undiscovered between periodic tests or maintenance activities.
(2) Systems can require more physical space.

A.3.3.18.3 Nondedicated Smoke Control Systems. Advantages of nondedicated systems include the following:

(1) Impairments to shared equipment required for normal building operation are likely to be corrected promptly.
(2) Limited additional space for smoke-control equipment is necessary.

Disadvantages of nondedicated systems include the following:

(1) System control might become elaborate.
(2) Modification of shared equipment or controls can impair smoke-control functionality.

A.3.3.18.6 Smoke Exhaust System. Maintenance of a tenable environment in the smoke zone is not within the capability of these systems.

A.3.3.20 Smoke Layer. The smoke layer includes a transition zone that is nonhomogeneous and separates the hot upper layer from the smoke-free air. The smoke layer is not a homogeneous mixture, nor does it have a uniform temperature. The calculation methods presented in this standard can assume homogeneous conditions.

A.3.3.21 Smoke Layer Interface. In practice, the smoke layer interface *(see Figure A.3.3.13.1)* is an effective boundary within a transition buffer zone, which can be several feet (meters) thick. Below this effective boundary, the smoke density in the transition zone decreases to zero. This height is used in the application of the equations in 5.5.3.1, 5.5.3.2, 5.5.4.1, and Section 5.7.

A.3.3.25 Tenable Environment. It is not expected that a tenable environment will be completely free of smoke.

A.3.3.26.3 Transition Zone. See Figure A.3.3.13.1 for further details.

A.4.1.1 For the purposes of this document, all systems used to address the impact of smoke from a fire are termed *smoke control systems*. Past editions of both NFPA 92A and NFPA 92B attempted to draw a distinction between types of systems, referring to the pressurization systems (covered by NFPA 92A) as *smoke control systems* and the systems used to mitigate smoke in large-volume spaces (covered by NFPA 92B) as *smoke management systems*. The distinction between *smoke control* and *smoke management* had the potential to cause confusion, particularly when building codes and standards labeled all systems *smoke control systems*. This document follows the convention of using *smoke control* as the general classification, with *smoke containment systems* being adopted for the subclassification of pressurization systems and *smoke management systems* being adopted for the subclassification of systems for large-volume spaces.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Passive smoke control is a smoke containment method used in areas of a building to prevent smoke from migrating outside the smoke zone. It is a method recognized by model building codes; however, this standard covers only pressurization systems for containment. If a passive system is used, the following design parameters should be considered as a minimum: stack effect, wind effect, operation of the HVAC equipment, leakage of boundary elements, and whether the space is sprinklered.

A.4.1.2 In addition to the design objectives listed, smoke control systems can be used for the following objectives:

(1) Allowing fire department personnel sufficient visibility to approach, locate, and extinguish a fire
(2) Limiting the spread of toxic gases that can affect building occupants
(3) Limiting the spread of products of combustion to provide protection for building contents

(See Annex G for additional information about objectives for smoke management systems.)

A.4.2.1 The performance objective of automatic sprinklers installed in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, is to provide fire control, which is defined as follows: limiting the size of a fire by distribution of water so as to decrease the heat release rate and pre-wet adjacent combustibles while controlling ceiling gas temperatures to avoid structural damage. A limited number of investigations have been undertaken involving full-scale fire tests in which the sprinkler system was challenged but provided the expected level of performance (Madrzykowski and Vettori [29]; Lougheed, Mawhinney, and O'Neill [26]). These investigations indicate that, for a fire control situation, although the heat release rate is limited, smoke can continue to be produced. However, the temperature of the smoke is reduced, and the pressure differences provided in this document for smoke control systems in fully sprinklered buildings are conservative. In addition, with the reduced smoke temperatures, the temperature requirement for smoke control components in contact with exhaust gases can be limited.

A.4.3.2 The design approaches are intended either to prevent people from coming into contact with smoke or to maintain a tenable environment when people do come into contact with smoke. The smoke development analysis in each of the design approaches listed should be justified using algebraic calculations, CFD models, compartment fire models, scale modeling, or zone models.

A.4.3.2(2) An equilibrium position for the smoke layer interface can be achieved by exhausting smoke at the same rate it is supplied to the smoke layer.

A.4.3.2(6) Opposed airflow can have applications beyond large-volume spaces and communicating spaces, but this document does not provide design guidance for those other applications.

A.4.4.1 The temperature differences between the exterior and the interior of the building cause stack effect and determine the stack effect's direction and magnitude. The stack effect must be considered when selecting exhaust fans. The effect of temperature and wind velocity varies with building height, configuration, leakage, and openings in wall and floor construction. One source of weather data is the ASHRAE *Handbook of Fundamentals*, Chapter 26, Climatic Design Information. It is suggested that the 99.6 percent heating dry bulb (DB) temperature and the 0.4 percent cooling DB temperature be used as the winter and summer design conditions, respectively. It is also suggested that the 1 percent extreme wind velocity be used as the design condition. If available, more site-specific wind data should be consulted.

A.4.4.2.1.1 A smoke control system designed to provide smoke containment should be designed to maintain the minimum design pressure differences under likely conditions of stack effect or wind. Pressure differences produced by smoke control systems tend to fluctuate due to the wind, fan pulsations, doors opening, doors closing, and other factors. Short-term deviations from the suggested minimum design pressure difference might not have a serious effect on the protection provided by a smoke control system. There is no clear-cut allowable value for this deviation. It depends on the tightness of doors, the tightness of construction, the toxicity of the smoke, airflow rates, and the volumes of spaces. Intermittent deviations up to 50 percent of the suggested minimum design pressure difference are considered tolerable in most cases.

The minimum design pressure differences in Table 4.4.2.1.1 for nonsprinklered spaces are values that will not be overcome by buoyancy forces of hot gases. The method used to obtain the values in Table 4.4.2.1.1 for nonsprinklered spaces follows. This method can be used to calculate pressure differences for gas temperatures other than 1700°F (927°C).

The pressure difference due to buoyancy of hot gases is calculated by the following equations:

$$\Delta P = 7.64\left[\frac{1}{T_O} - \frac{1}{T_F}\right]h$$

where:
ΔP = pressure difference due to buoyancy of hot gases (in. w.g.)
T_o = absolute temperature of surroundings (R)
T_F = absolute temperature of hot gases (R)
h = distance above neutral plane (ft)

$$\Delta P = 3460\left[\frac{1}{T_O} - \frac{1}{T_F}\right]h$$

where:
ΔP = pressure difference due to buoyancy of hot gases (Pa)
T_o = absolute temperature of surroundings (K)
T_F = absolute temperature of hot gases (K)
h = distance above neutral plane (m)

The neutral plane is a horizontal plane between the fire space and a surrounding space at which the pressure difference between the fire space and the surrounding space is zero. For Table 4.4.2.1.1, h was conservatively selected at two-thirds of the floor-to-ceiling height, the temperature of the surroundings was selected at 70°F (20°C), the temperature of the hot gases was selected at 1700°F (927°C), and a safety factor of 0.03 in. w.g. (7.5 Pa) was used.

For example, the minimum design pressure difference for a ceiling height of 12 ft should be calculated as follows:

$$T_O = 530 \text{ R} = 293 \text{ K}$$
$$T_F = 2160 \text{ R} = 1200 \text{ K}$$
$$h = (12)\left(\frac{2}{3}\right) = 8 \text{ ft} = 2.44 \text{ m}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

From the first equation, $\Delta P = 0.087$ in. w.g. Adding the safety factor and rounding off, the minimum design pressure difference is 0.12 in. w.g.

A.4.4.2.2 The forces on a door in a smoke control system are illustrated in Figure A.4.4.2.2. The force required to open a door in a smoke control system is as follows:

$$F = F_r + \frac{5.2(WA)\Delta P}{2(W-d)}$$

where:

F = total door-opening force (lb)
F_r = force to overcome the door closer and other friction (lb)
W = door width (ft)
A = door area (ft^2)
ΔP = pressure difference across the door (in. w.g.)
d = distance from the doorknob to the knob side of the door (ft)



FIGURE A.4.4.2.2 Forces on a Door in a Smoke Control System.

When the maximum door-opening force is specified at 30 lbf, Table A.4.4.2.2 can be used to determine the maximum pressure difference across the door.

A.4.4.4.1 Makeup air has to be provided to ensure that the exhaust fans are able to move the design air quantities and to ensure that door-opening force requirements are not exceeded. The large openings to the outside can consist of open doors, open windows, and open vents. The large openings to the outside do not include cracks in the construction, gaps around closed doors, gaps around closed windows, and other small paths. It is recommended that makeup air be designed at 85 percent to 95 percent of the exhaust, not including the leakage through small paths. This is based on experience that the remaining air (5 percent to 15 percent) to be exhausted will enter the large-volume space as leakage through the small paths. The reason that less makeup air is supplied than is being exhausted is to avoid positively pressurizing the large-volume space.

A.4.4.4.1.4 The maximum value of 200 ft/min (1.02 m/sec) for makeup air is to prevent significant plume deflection and disruption of the smoke interface. An engineering analysis of the effect of a higher makeup air velocity can be done by comparison with full-scale experimental data, scale modeling, or CFD modeling. The maximum makeup air velocity is based on flame deflection data (Mudan and Croce [36]). Where maintaining a smoke layer height is not a design goal, plume disruption due to supply velocity might not be detrimental. When the exhaust is provided by natural venting, makeup air should also be supplied by natural venting to avoid pressurizing the space.

Table A.4.4.2.2 Maximum Pressure Differences Across Doors

Door-Closer Force* (lbf)	Door Width (in. w.g.)†				
	32 in.	36 in.	40 in.	44 in.	48 in.
6	0.45	0.40	0.37	0.34	0.31
8	0.41	0.37	0.34	0.31	0.28
10	0.37	0.34	0.30	0.28	0.26
12	0.34	0.30	0.27	0.25	0.23
14	0.30	0.27	0.24	0.22	0.21

For SI units, 1 lbf = 4.4 N; 1 in. = 25.4 mm; 0.1 in. w.g. = 25 Pa.

Notes:

(1) Total door-opening force is 30 lbf.

(2) Door height is 7 ft.

(3) The distance from the doorknob to the knob side of the door is 3 in.

(4) For other door-opening forces, other door sizes, or hardware other than a knob (e.g., panic hardware), the calculation procedure provided in ASHRAE/SFPE *Principles of Smoke Management* should be used.

*Many door closers require less force in the initial portion of the opening cycle than that required to bring the door to the fully open position. The combined impact of the door closer and the imposed pressure combine only until the door is opened enough to allow air to pass freely through the opening. The force imposed by a closing device to close the door is often different from that imposed on opening.

†Door widths apply only if the door is hinged at one end; otherwise, the calculation procedure provided in ASHRAE/SFPE *Principles of Smoke Management* should be used.

A.4.4.4.2.2 Fires in communicating spaces can produce buoyant gases that spill into the large space. The design for this case is analogous to the design for a fire in the large space. However, the design has to consider the difference in entrainment behavior between an axisysmmetric plume and a spill plume. If communicating open spaces are protected by automatic sprinklers, the calculations set forth in this standard might show that no additional venting is required. Alternatively, whether or not communicating spaces are sprinklered, smoke can be prevented from spilling into the large space if the communicating space is exhausted at a rate to cause a sufficient inflow velocity across the interface to the large space.

A.4.4.4.3 In the design of smoke control systems, airflow paths must be identified and evaluated. Some leakage paths are obvious, such as gaps around closed doors, open doors, elevator doors, windows, and air transfer grilles. Construction cracks in building walls and floors are less obvious but no less important. The flow area of most large openings can be calculated easily. The flow area of construction cracks is dependent on workmanship, for example, how well a door is fitted or how well weather stripping is installed. Typical leakage areas of construction cracks in walls and floors of commercial buildings are listed in Table A.4.4.4.3. Doors open for short periods of time result in a transition condition that is necessary to provide egress from or access to the smoke zone.

A.4.4.5 In the event that the smoke control and the suppression systems are activated concurrently, the smoke control system might dilute the gaseous agent in the space. Because gaseous suppression systems commonly provide only one application of the agent, the potential arises for renewed growth of the fire.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table A.4.4.4.3 Typical Leakage Areas for Walls and Floors of Commercial Buildings

Construction Element	Tightness	Area Ratio[a]
Exterior building walls (includes construction cracks and cracks around windows and doors)	Tight[b]	0.50×10^{-4}
	Average[b]	0.17×10^{-3}
	Loose[b]	0.35×10^{-3}
	Very loose[b]	0.12×10^{-2}
Stairwell walls (includes construction cracks but not cracks around windows and doors)	Tight[c]	0.14×10^{-4}
	Average[c]	0.11×10^{-3}
	Loose[c]	0.35×10^{-3}
Elevator shaft walls (includes construction cracks but not cracks and gaps around doors)	Tight[c]	0.18×10^{-3}
	Average[c]	0.84×10^{-3}
	Loose[c]	0.18×10^{-2}
Floors (includes construction cracks and gaps around penetrations)	Tight[d]	0.66×10^{-5}
	Average[e]	0.52×10^{-4}
	Loose[d]	0.17×10^{-3}

[a]For a wall, the area ratio is the area of the leakage through the wall divided by the total wall area. For a floor, the area ratio is the area of the leakage through the floor divided by the total area of the floor.

[b]Values based on measurements of Tamura and Shaw [50]; Tamura and Wilson [53]; and Shaw, Reardon, and Cheung [45].

[c]Values based on measurements of Tamura and Wilson [53] and Tamura and Shaw [51].

[d]Values extrapolated from average floor tightness based on range of tightness of other construction elements.

[e]Values based on measurements of Tamura and Shaw [52].

A.4.5 The following factors should be considered in determining the ability of the system to remain effective for the time period necessary:

(1) Reliability of power source(s)
(2) Arrangement of power distribution
(3) Method and protection of controls and system monitoring
(4) Equipment materials and construction
(5) Building occupancy

A.4.5.1.1 Tenability analysis is outside the scope of this document. However, other references are available that present analytical methods for use in tenability analysis. The SFPE *Engineering Guide to Performance-Based Fire Protection Analysis and Design of Buildings* describes a process of establishing tenability limits.

The SFPE guide references D. A. Purser, "Toxicity Assessment of Combustion Products," Chapter 2/6, SFPE *Handbook of Fire Protection Engineering* [42], which describes a fractional effective dose (FED) calculation approach, which is also contained in NFPA 269, *Standard Test Method for Developing Toxic Potency Data for Use in Fire Hazard Modeling*. The FED addresses the effects of carbon monoxide, hydrogen cyanide, carbon dioxide, hydrogen chloride, hydrogen bromide, and anoxia. It is possible to use the test data, combined with laboratory experience, to estimate the FED value that leads to the survival of virtually all people. This value is about 0.8.

A.4.5.1.2 Timed egress analysis is outside the scope of this document. However, other references are available that present analytical methods for use in egress analysis, for example, ASHRAE/SFPE *Principles of Smoke Management* [21].

A.4.5.1.3 The depth of the smoke layer depends on many factors and generally ranges from 10 percent to 20 percent of the floor to ceiling height. An engineering analysis of the depth of the smoke layer can be done by comparison with full scale experimental data, scale modeling, or CFD modeling.

A.4.6.1 This number depends largely on the building occupancy and the type of smoke control system. In some systems, doors most likely are open for only short periods of time and smoke leakage is negligible. In other systems, frequent egress from the smoke zone could cause at least one door to be open most of the time.

Where the building egress strategy anticipates multiple floors to be evacuated simultaneously or the design for the stairwell pressurization system assumes the exit door is open, the stairwell pressurization system should be designed to accommodate more than one door open, at least one of which should be the discharge door from the stairwell.

The effect of opening a door to the outside is usually much greater than that of opening interior doors. The importance of the exterior stairwell door can be explained by considering the conservation of mass of the pressurization air. This air comes from the outside and must eventually flow back to the outside. For an open interior door, the rest of the building on that floor acts as flow resistance to the air flowing out the open doorway. When the exterior door is open, there is no other flow resistance, and the flow can be 10 to 30 times more than through an open interior door. *(See Annex F for information on types of stairwell pressurization systems.)* This separation should be as great as is practicable. Because hot smoke rises, consideration should be given to locating supply air intakes below such critical openings. However, outdoor smoke movement that might result in smoke feedback depends on the location of the fire, the location of points of smoke leakage from the building, the wind speed and direction, and the temperature difference between the smoke and the outside air.

A.4.6.3.1 Simple single-point injection systems such as that illustrated in Figure A.4.6.3.1 can use roof or exterior wall-mounted propeller fans. The use of propeller fans without windshields is not permitted because of the extreme effect wind can have on the performance of such fans.



FIGURE A.4.6.3.1 Stairwell Pressurization by Roof-Mounted Propeller Fan.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

One major advantage of using propeller fans for stairwell pressurization is that they have a relatively flat pressure response curve with respect to varying flow. Therefore, as doors are opened and closed, propeller fans quickly respond to airflow changes in the stairwell without major pressure fluctuations. A second advantage of using propeller fans is that they are less costly than other types of fans and can provide adequate smoke control with lower installed costs.

A disadvantage of using propeller fans is that they often require windshields at the intake because they operate at low pressures and are readily affected by wind pressure on the building. This is less critical on roofs, where the fans are often protected by parapets and where the direction of the wind is at right angles to the axis of the fan.

Propeller fans mounted on walls pose the greatest susceptibility to the adverse effects of wind pressures. The adverse effect is at a maximum when wind direction is in direct opposition to the fan airflow, resulting in a lower intake pressure and thus significantly reducing fan effectiveness. Winds that are variable in intensity and direction also pose a threat to the ability of the system to maintain control over the stairwell static pressure.

A.4.6.4 Figure A.4.6.4(a) and Figure A.4.6.4(b) are two examples of the many possible multiple-injection systems that can be used to overcome the limitations of single-injection systems. The pressurization fans can be located at ground level, at roof level, or at any location in between.



FIGURE A.4.6.4(a) Stairwell Pressurization by Multiple Injection with the Fan Located at Ground Level.

In Figure A.4.6.4(a)and Figure A.4.6.4(b), the supply duct is shown in a separate shaft. However, systems have been built that have eliminated the expense of a separate duct shaft by locating the supply duct in the stair enclosure itself. Care should be taken so that the duct does not reduce the required exit width or become an obstruction to orderly building evacuation.

A.4.6.4.1.1 The most common injection point is at the top of the stairwell, as illustrated in Figure A.4.6.4.1.1.

A.4.6.4.1.2 Single-injection systems can fail when a few doors are open near the air supply injection point. All the pressurization air can be lost through these open doors, at which time the system will fail to maintain positive pressures across doors farther from the injection point.

Because a ground-level stairwell door is likely to be in the open position much of the time, a single-bottom-injection system is especially prone to failure. Careful design analysis is needed for all single-bottom-injection systems and for all other single-injection systems for stairwells in excess of 100 ft (30.5 m) in height to ensure proper pressurization throughout the stairwell.

A.4.6.4.2 Many multiple-injection systems have been built with supply air injection points on each floor. These systems represent the ultimate in preventing loss of pressurization air through a few open doors; however, that many injection points might not be necessary. For system designs with injection points more than three stories apart, the designer should use a computer analysis such as the one in ASHRAE/SFPE *Principles of Smoke Management* [21]. The purpose of this analysis is to ensure that loss of pressurization air through a few open doors does not lead to substantial loss of stairwell pressurization.

A.4.7 If elevators are intended to be used for evacuation during a fire, the elevator pressurization system should be protected against heat, flame, smoke, loss of electrical power, loss of elevator machine room cooling, water intrusion, and inadvertent activation of controls.

Historically, elevator hoistways have proved to be a readily available conduit for the movement of smoke throughout buildings. The reason is that elevator doors have not been tight-fitting and elevator hoistways have been provided with



FIGURE A.4.6.4(b) Stairwell Pressurization by Multiple Injection with Roof-Mounted Fan.



FIGURE A.4.6.4.1.1 Stairwell Pressurization by Top Injection.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

openings in their tops. The building stack effect has provided the driving force that has readily moved smoke into and out of the loosely constructed elevator hoistways. Several methods of correcting this problem have been proposed and investigated. These methods include the following:

(1) Exhaust of the fire floor
(2) Pressurization of enclosed elevator lobbies
(3) Construction of smoke-tight elevator lobbies
(4) Pressurization of the elevator hoistway
(5) Closing of elevator doors after automatic recall

(Note: Rule 211.3a, Phase I Emergency Recall Operations, of ASME/ANSI A17.1, *Safety Code for Elevators and Escalators*, requires that elevator doors open and remain open after the elevators are recalled. This results in large openings into the elevator hoistways, which can greatly increase the airflow required for pressurization. NFPA 80, *Standard for Fire Doors and Other Opening Protectives*, permits closing of elevator doors after a predetermined time when required by the authority having jurisdiction. Local requirements on operation of elevator doors should be determined and incorporated into the system design.)

The methods listed in A.4.7(1) through A.4.7(5) have been employed either singly or in combination. However, their application to a particular project, including the effect of any vents in the elevator hoistway, should be closely evaluated. The open vent at the top of the elevator hoistway could have an undesirable effect on elevator smoke control systems.

The following references discuss research concerning elevator use during fire situations: Klote and Braun [17]; Klote [15]; Klote, Levin, and Groner [20]; Klote, Levin, and Groner [19]; Klote [13]; Klote et al. [18]; and Klote et al. [16].

If it is intended to open the elevator doors during operation of the smoke control system, the maximum pressure difference across the elevator doors that allows the elevator doors to operate should be established.

A.4.8 The pressurized stairwells discussed in Section 4.6 are intended to control smoke to the extent that they inhibit smoke infiltration into the stairwell. However, in a building with a pressurized stairwell as the sole means of smoke control, smoke can flow through cracks in floors and partitions and through other shafts and threaten life and damage property at locations remote from the fire. The concept of zoned smoke control discussed in this section is intended to limit this type of smoke movement within a building.

Limiting fire size (mass burning rate) increases the reliability and viability of smoke control systems. Fire size can be limited by fuel control, compartmentation, or automatic sprinklers. It is possible to provide smoke control in buildings not having fire-limiting features, but in those instances careful consideration must be given to fire pressure, high temperatures, mass burning rates, accumulation of unburned fuels, and other outputs resulting from uncontrolled fires.

A.4.8.1.1.1 Arrangements of some smoke control zones are illustrated in Figure A.4.8.1.1.1.

In Figure A.4.8.1.1.1, the smoke zone is indicated by a minus sign and pressurized spaces are indicated by plus signs. Each floor can be a smoke control zone, as in (a) and (b), or a smoke zone can consist of more than one floor, as in (c) and (d). A smoke zone can also be limited to a part of a floor, as in (e).

When a fire occurs, all the non–smoke zones in the building can be pressurized as shown in Figure A.4.8.1.1.1, parts (a), (c), and (e). This system requires large quantities of outside air. The comments concerning location of supply air inlets of pressurized stairwells also apply to the supply air inlets for non–smoke zones.



FIGURE A.4.8.1.1.1 Arrangements of Smoke Control Zones.

In cold climates, the introduction of large quantities of outside air can cause serious damage to building systems. Therefore, serious consideration should be given to emergency preheat systems that temper the incoming air and help to avoid or limit damage. Alternatively, pressurizing only those zones immediately adjacent to the smoke zones could limit the quantity of outside air required, as in Figure A.4.8.1.1.1, parts (b) and (d). However, the disadvantage of this limited approach is that it is possible to have smoke flow through shafts past the pressurized zone and into unpressurized spaces. When this alternative is considered, a careful examination of the potential smoke flows involved should be accomplished and a determination of acceptability made.

Smoke zones should be kept as small as practicable so that evacuation from these zones can be readily achieved and so that the quantity of air required to pressurize the surrounding spaces can be kept to a manageable level. However, these zones should be large enough so that heat buildup from the fire will be sufficiently diluted with surrounding air so as to prevent failure of major components of the smoke control system. Design guidance on dilution temperature is provided in ASHRAE/SFPE *Principles of Smoke Management.*

A.4.8.3 Methods of design for smoke refuge areas are presented in Klote [14].

A.4.9 Examples of smoke control systems that can interact when operating simultaneously include the following:

(1) Pressurized stairwells that connect to floor areas that are part of a zoned smoke control system

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

(2) Elevator hoistways that are part of an elevator smoke control system that connects to floor areas that are part of a zoned smoke control system
(3) Elevator smoke control systems that are connected to areas of refuge that are in turn connected with floor areas that are part of a zoned smoke control system
(4) Pressurized stairwells that are also connected to a smoke refuge area

Often smoke control systems are designed independently to operate under the dynamic forces they are expected to encounter (e.g., buoyancy, stack effect, wind). Once the design is completed, it is necessary to study the impact the smoke control systems will have on one another. For example, an exhausted smoke zone operating in conjunction with a stairwell pressurization system can tend to improve the performance of the stairwell pressurization system. At the same time, it could increase the pressure difference across the door, causing difficulty in opening the door into the stairwell. For complex systems, it is recommended that a computer network model be used for the analysis.

Unless venting or exhaust is provided in the fire zones, the required pressure differences might not be developed. Eventually pressure equalization between the fire zone and the unaffected zones will become established, and there will be nothing to inhibit smoke spread into all other zones.

A.4.10.1 Stairwells that do not have vestibules can be pressurized using systems currently available. Some buildings are constructed with vestibules because of building code requirements.

A.4.10.2 *Nonpressurized Vestibules.* Stairwells that have nonpressurized vestibules can have applications in existing buildings. With both vestibule doors open, the two doors in series provide an increased resistance to airflow compared to a single door. This increased resistance will reduce the required airflow so as to produce a given pressure in the stairwell. This subject is discussed in detail in ASHRAE/SFPE *Principles of Smoke Management*.

In buildings with low occupant loads, it is possible that one of the two vestibule doors might be closed or at least partially closed during the evacuation period. This will further reduce the required airflow to produce a given pressure.

Pressurized Vestibules. Closing both doors to a vestibule can limit the smoke entering a vestibule and provide a tenable environment as a smoke refuge area. The adjacent stairwell is indirectly pressurized by airflow from the pressurized vestibule. However, this pressurization can be lost if the exterior door is open. Also, smoke can flow into the stairwell through any leakage openings in the stairwell walls adjacent to the floor space. Such walls should be constructed to minimize leakages for a stairwell protected by a pressurized vestibule system.

Pressurized Vestibules and Stairwells. To minimize the amount of smoke entering a vestibule and a stairwell, both the vestibule and the stairwell can be pressurized. The combined system will enhance the effectiveness of the stairwell pressurization system. Also, the pressurized vestibule can provide a temporary smoke refuge area.

Purged or Vented Vestibules. Purged or vented vestibule systems fall outside the scope of this document. A hazard analysis would be required using the procedures provided in the SFPE *Handbook of Fire Protection Engineering*. An engineering analysis should be performed to determine the benefits, if any, of pressurizing, purging, or exhausting vestibules on the stairwell.

A.4.11 For a stairwell pressurization system that has not been designed to accommodate the opening of doors, pressurization will drop when any doors open, and smoke can then infiltrate the stairwell. For a building of low occupant density, the opening and closing of a few doors during evacuation has little effect on the system. For a building with a high occupant density and total building evacuation, it can be expected that most of the doors will be open at some time during evacuation. The methods provided in ASHRAE/SFPE *Principles of Smoke Management* can be used to design systems to accommodate anywhere from a few open doors to almost all the doors being open.

During the time that occupants of the smoke zone are exiting the area, the conditions in the smoke zone are still tenable. Although opening the stairwell door on the fire floor during this time might release some smoke into the stairwell, it will not create untenable conditions there. Once conditions in the smoke zone become untenable, it is unlikely that the door to the fire floor would be opened by occupants of that floor. For this reason, designing for an open stairwell door on the fire floor is normally not required. Doors blocked open in violation of applicable codes are beyond the capability of the system.

A.5.1 Scale modeling uses a reduced-scale physical model following established scaling laws, whereby small-scale tests are conducted to determine the requirements and capabilities of the modeled smoke management system.

Algebraic, closed-form equations are derived primarily from the correlation of large- and small-scale experimental results.

Compartment fire models use both theory and empirically derived values to estimate conditions in a space.

Each approach has advantages and disadvantages. Although the results obtained from the different approaches normally should be similar, they usually are not identical. The state of the art, while advanced, is empirically based, and a final theory provable in fundamental physics has not yet been developed. The core of each calculation method is based on the entrainment of air (or other surrounding gases) into the rising fire-driven plume. A variation of approximately 20 percent in entrainment occurs between the empirically derived entrainment equations commonly used, such as those indicated in Chapter 5, or in zone fire models. Users can add an appropriate safety factor to exhaust capacities to account for this uncertainty.

A.5.1.1 The equations presented in Chapter 5 are considered to be the most accurate, simplest algebraic expressions available for the proposed purposes. In general, they are limited to cases involving fires that burn at a constant rate of heat release ("steady fires") or fires that increase in rate of heat release as a function of the square of time ("unsteady fires"). The equations are not appropriate for other fire conditions or for a condition that initially grows as a function of time but then, after reaching its maximum growth, burns at a steady state. In most cases, judicious use of the equations can reasonably overcome this limitation. Each of the equations has been derived from experimental data. In some cases, the test data are limited or have been collected within a limited set of fire sizes, space dimensions, or points of measurement. Where possible, comments are included on the range of data used in deriving the equations presented. It is important to consider these limits.

Caution should be exercised in using the equations to solve the variables other than the ones presented in the list of variables, unless it is clear how sensitive the result is to minor changes in any of the variables involved. If these restrictions

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

present a limit that obstructs the users' needs, consideration should be given to combining the use of equations with either scale or compartment fire models. Users of the equations should appreciate the sensitivity of changes in the variables being solved.

A.5.1.2 Scale modeling is especially desirable where the space being evaluated has projections or other unusual arrangements that prevent a free-rising plume. This approach is expensive, time-consuming, and valid only within the range of tests conducted. Because this approach is usually reserved for complex structures, it is important that the test series cover all the potential variations in factors, such as position and size of fire, location and capacity of exhaust and intake flows, variations in internal temperature (stratification or floor-ceiling temperature gradients), and other variables. It is likely that detection will not be appraisable using scale models.

A.5.1.3 Computer capabilities sufficient to execute some of the family of compartment fire models are widely available. All compartment fire models solve the conservation equations for distinct regions (control volumes). Compartment fire models can be classified as zone fire models or CFD models.

Verifying computer fire model results is important because it is sometimes easier to obtain results than to determine their accuracy. Computer fire model results have been verified over a limited range of experimental conditions (Emmons [5]; Klote [14]; Soderbom [46]); review of these results should provide the user with a level of confidence. However, because the very nature of a fire model's utility is to serve as a tool for investigating unknown conditions, there will be conditions for which any model has yet to be verified. It is for those conditions that the user should have some assistance in judging the model's accuracy.

There are three areas of understanding that greatly aid accurate fire modeling of unverified conditions. The first area involves understanding what items are being modeled. The second area involves appropriately translating the real-world items into fire model input. The third area involves understanding the model conversion of input to output.

A.5.2.1 A design fire size of approximately 5000 Btu/sec (5275 kW) for mercantile occupancies is often referenced (Morgan [33]). This is primarily based on a statistical distribution of fire sizes in shops (retail stores) in the United Kingdom that included sprinkler protection. Less than 5 percent of fires in this category exceeded 5000 Btu/sec. Geometrically, a 5000 Btu/sec (5275 kW) fire in a shop has been described as a 10 ft × 10 ft (3.1 m × 3.1 m) area resulting in an approximate heat release rate per unit area of 50 Btu/ft^2 · s (568 kW/m^2).

Automatic suppression systems are designed to limit the mass burning rate of a fire and will, therefore, limit smoke generation. Fires in sprinklered spaces adjacent to atria and covered mall pedestrian areas can also be effectively limited to reduce the effect on atrium spaces or covered mall pedestrian areas and thus increase the viability of a smoke management system.

The likelihood of sprinkler activation is dependent on many factors, including heat release rate of the fire and the ceiling height. Thus, for modest fire sizes, sprinkler operation is most likely to occur in a reasonable time in spaces with lower ceiling heights, such as 8 ft (2.4 m) to 25 ft (7.6 m). Activation of sprinklers near a fire causes smoke to cool, resulting in reduced buoyancy. This reduced buoyancy can cause smoke to descend and visibility to be reduced. Equations 5.4.2.1 and 5.4.2.2 for smoke filling and Equations 5.5.1.1a, 5.5.1.1b, 5.5.1.1c, and 5.5.3.2 for smoke production do not apply if a loss of buoyancy due to sprinkler operation has occurred.

Sprinkler activation in spaces adjacent to an atrium results in cooling of the smoke. For fires with a low heat release rate, the temperature of the smoke leaving the compartment is near ambient, and the smoke will be dispersed over the height of the opening. For fires with a high heat release rate, the smoke temperature will be above ambient, and the smoke entering the atrium will be buoyant.

The performance objective of automatic sprinklers installed in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, is to provide fire control, which is defined as follows: Limiting the size of a fire by distribution of water so as to decrease the heat release rate and pre-wet adjacent combustibles, while controlling ceiling gas temperatures to avoid structural damage. A limited number of investigations have been undertaken in which full-scale fire tests were conducted in which the sprinkler system was challenged but provided the expected level of performance. These investigations indicate that, for a fire control situation, the heat release rate is limited but smoke can continue to be produced. However, the temperature of the smoke is reduced.

Full-scale sprinklered fire tests were conducted for open-plan office scenarios (Lougheed [23]; Madrzykowski [29]). These tests indicate that there is an exponential decay in the heat release rate for the sprinklered fires after the sprinklers are activated and achieve control. The results of these tests also indicate that a design fire with a steady-state heat release rate of 474 Btu/sec (500 kW) provides a conservative estimate for a sprinklered open-plan office.

Limited full-scale test data are available for use in determining design fire size for other sprinklered occupancies. Hansell and Morgan [7] provide conservative estimates for the convective heat release rate based on UK fire statistics: 1 MW for a sprinklered office, 0.5–1.0 MW for a sprinklered hotel bedroom, and 5 MW for a sprinklered retail occupancy. These steady-state design fires assume the area is fitted with standard response sprinklers.

Full-scale fire tests for retail occupancies were conducted in Australia (Bennetts et al. [1]). These tests indicated that for some common retail outlets (clothing and book stores) the fire is controlled and eventually extinguished with a single sprinkler. These tests also indicated that the sprinklers might have difficulty suppressing a fire in a shop with a high fuel load, such as a toy store.

Full-scale fire tests were conducted for a variety of occupancies (retail stores, cellular offices, and libraries) in the United Kingdom (Heskestad [11]). Full-scale fire tests were conducted for compact mobile storage systems used for document storage. Information on tests conducted in 1979 on behalf of the Library of Congress is provided in Annex H of NFPA 909, *Code for the Protection of Cultural Resource Properties — Museums, Libraries, and Places of Worship*. Subsequent full-scale fire tests conducted for the Library of Congress Archives II and the National Library of Canada showed that fires in compact mobile storage systems are difficult to extinguish (Lougheed, Mawhinney, and O'Neill [26]).

During the initial active phase of the fire with the sprinklers operating, the smoke layer remains stratified under the ceiling (Heskestad [10]). Near the sprinklers, smoke is pulled into the cold lower layer by the water droplets and returns to the smoke layer due to buoyancy. Once the sprinklers gain control and begin to suppress the fire, the gas temperature in

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

the smoke layer falls rapidly and the smoke is dispersed throughout the volume as buoyancy decays.

The temperature of smoke produced in a sprinklered fire depends on factors such as the heat release rate of the fire, the number of sprinklers operating, and sprinkler application density. Full-scale fire tests with the water temperature at 50°F (10°C) indicate that, for four operating sprinklers, the smoke temperature is cooled to near or below ambient if the heat release rate is <190 Btu/sec (<200 kW) at an application density of 0.1 gpm/ft^2 (4.1 L/m^2) and <474 Btu/sec (<500 kW) at an application density of 0.2 gpm/ft^2 (8.15 L/m^2). For higher heat release rates, the smoke temperature is above ambient and is buoyant as it leaves the sprinklered area.

For low heat release rate sprinklered fires, the smoke is mixed over the height of the compartment. The smoke flow through large openings into an atrium has a constant temperature with height.

With higher heat release rates, a hot upper layer is formed. The temperature of the upper layer will be between the ambient temperature and the operating temperature of the sprinkler. If the smoke is hotter than the sprinkler operating temperature, further sprinklers will be activated and the smoke will be cooled. For design purposes, a smoke temperature equivalent to the operating temperature of the sprinklers can be assumed.

A.5.2.4.4 Full-scale fire tests for open-plan offices (Lougheed [23]; Madrzykowski [29]) have shown that, once the sprinklers gain control of the fire but are not immediately able to extinguish it due to the fuel configuration, the heat release rate decreases exponentially as follows:

$$Q(t) = Q_{act} e^{-kt} \qquad \textbf{(A.5.2.4.4)}$$

where:

$Q(t)$ = heat release rate at time t after sprinkler activation (Btu/sec or kW)
Q_{act} = heat release rate at sprinkler activation (Btu/sec or kW)
k = decay constant (sec^{-1})
t = time after sprinkler activation (sec)

Estimates for the decay constant for office occupancies protected with a discharge density of 0.1 gpm/ft^2 (4.1 L/m^2) are 0.0023 for situations with light fuel loads in shielded areas (Madrzykowski [29]) and 0.00155 sec^{-1} for situations with heavy loads (Lougheed [23]).

A.5.2.5 The entire floor area covered or included between commodities should be considered in the calculations. Figure A.5.2.5(a) and Figure A.5.2.5(b) illustrate the concepts of separation distance.



FIGURE A.5.2.5(a) Separation Distance, R.



FIGURE A.5.2.5(b) Fuel Items.

A.5.4.1 The relations address the following three situations:

(1) No smoke exhaust is operating (see 5.4.2.1 and 5.4.2.2).
(2) The mass rate of smoke exhaust equals the mass rate of smoke supplied from the plume to the smoke layer.
(3) The mass rate of smoke exhaust is less than the rate of smoke supplied from the plume to the smoke layer.

The height of the smoke layer interface can be maintained at a constant level by exhausting the same mass flow rate from the layer as is supplied by the plume. The rate of mass supplied by the plume depends on the configuration of the smoke plume. Three smoke plume configurations are addressed in this standard.

The following provides a basic description of the position of smoke layer interface with smoke exhaust operating:

(1) *Mass Rate of Smoke Exhaust Equal to Mass Rate of Smoke Supplied.* After the smoke exhaust system has operated for a sufficient period of time, an equilibrium position of the smoke layer interface is achieved if the mass rate of smoke exhaust is equal to the mass rate of smoke supplied by the plume to the base of the smoke layer. Once achieved, this position should be maintained as long as the mass rates remain equal. See Section 5.5 for the mass rate of smoke supplied to the base of the smoke layer for different plume configurations.
(2) *Mass Rate of Smoke Exhaust Not Equal to Mass Rate of Smoke Supplied.* With a greater rate of mass supply than exhaust, an equilibrium position of the smoke layer interface will not be achieved. The smoke layer interface can be expected to descend, but at a slower rate than if no exhaust were provided (*see 5.4.2*). Table A.5.4.1 includes information on the smoke layer position as a function of time for axisymmetric plumes of steady fires, given the inequality of the mass rates. For other plume configurations, a computer analysis is required.

A.5.4.2.1 The equations in 5.4.2.1 are for use with the worst-case condition, a fire away from any walls. The equations provide a conservative estimate of hazard because z relates to the height where there is a first indication of smoke, rather than the smoke layer interface position. Calculation results yielding $z/H > 1.0$ indicate that the smoke layer has not yet begun to descend.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table A.5.4.1 Increase in Time for Smoke Layer Interface to Reach Selected Position for Axisymmetric Plumes

		t/t_0					
z/H	m/m_e =	0.25	0.35	0.5	0.7	0.85	0.95
0.2		1.12	1.19	1.3	1.55	1.89	2.49
0.3		1.14	1.21	1.35	1.63	2.05	2.78
0.4		1.16	1.24	1.4	1.72	2.24	3.15
0.5		1.17	1.28	1.45	1.84	2.48	3.57
0.6		1.20	1.32	1.52	2.00	2.78	4.11
0.7		1.23	1.36	1.61	2.20	3.17	4.98
0.8		1.26	1.41	1.71	2.46	3.71	6.25

where:
t = time for smoke layer interface to descend to z
t_0 = value of t in absence of smoke exhaust *(see Equation 5.4.2.1)*
z = design height of smoke layer interface above base of the fire
H = ceiling height above fire source
m = mass flow rate of smoke exhaust (minus any mass flow rate into smoke layer from sources other than the plume)
m_e = value of m required to maintain smoke layer interface indefinitely at z *(see Equation 5.5.1.1b)*

The equations are based on limited experimental data (Cooper et al. [4]; Hagglund, Jansson, and Nireus [6]; Heskestad and Delichatsios [12]; Mulholland et al. [38]; Nowler [40]) from investigations using the following:

(1) Uniform cross-sectional areas with respect to height
(2) A/H^2 ratios ranging from 0.9 to 14
(3) $z/H \geq 0.2$

A.5.4.2.2 See Annex I for additional information on unsteady fires.

A.5.5.1.1 The mass rate of smoke production is calculated based on the rate of entrained air, because the mass rate of combustion products generated from the fire is generally much less than the rate of air entrained in the plume.

Several entrainment relations for axisymmetric fire plumes have been proposed. Those recommended here were first derived in conjunction with the 1982 edition of NFPA 204, *Standard for Smoke and Heat Venting*. The relations were later slightly modified by the incorporation of a virtual origin and were also compared against other entrainment relations. For more information about fire plumes, see Heskestad [9] and Beyler [2].

The entrainment relations for axisymmetric fire plumes in this standard are essentially those presented in the 1982 edition of NFPA 204. Effects of virtual origin are ignored, because they generally would be small in the current application.

The base of the fire has to be the lowest point of the fuel array. The mass flow rate in the plume depends on whether locations above or below the mean flame height are considered (i.e., whether the flames are below the smoke layer interface or reach into the smoke layer).

The rate of mass supplied by the plume to the smoke layer is obtained from Equation 5.5.1.1c for clear heights less than the flame height (see Equation 5.5.1.1a and otherwise from Equation 5.5.1.1b). The clear height is selected as the design height of the smoke layer interface above the fire source.

It should be noted that Equations 5.5.1.1b and 5.5.1.1c do not explicitly address the types of materials involved in the fire, other than through the rate of heat release. This is due to the mass rate of air entrained being much greater than the mass rate of combustion products generated and to the amount of air entrained only being a function of the strength (i.e., rate of heat release of the fire).

Fires can be located near the edge or a corner of the open space. In this case, entrainment might not be from all sides of the plume, resulting in a lesser smoke production rate than where entrainment can occur from all sides. Thus, conservative design calculations should be conducted based on the assumption that entrainment occurs from all sides.

Physical model tests (Lougheed [24]; Lougheed [25]) with steady-state fires have shown that Equation 5.5.1.1b provides a good estimate of the plume mass flow rate for an atrium smoke management system operating under equilibrium conditions *(see 5.5.1.1)*. The results also showed that the smoke layer was well mixed. The average temperature in the smoke layer can be approximated using the adiabatic estimate for the plume temperature at the height of the smoke layer interface (see Equation 5.5.5).

At equilibrium, the height z in Equation 5.5.1.1b is the location of the smoke layer interface above the base of fuel (see Figure A.3.3.13.1). For an efficient smoke management system, the depth of the transition zone is approximately 10 percent of the atrium height. In the transition zone, the temperature and other smoke parameters decrease linearly with height between the smoke layer interface height and the lower edge of the transition zone.

Plume contact with the walls can be of concern for cases where the plume diameter increases (see 5.5.4) to contact multiple walls of the atrium below the intended design smoke layer interface. The effective smoke layer interface will occur at or below the height where the plume is in contact with all the walls.

In situations where the flame height as calculated from Equation 5.5.1.1a is greater than 50 percent of the ceiling height or in a condition of dispersed fuel packages *(see 5.2.5)* that can be burning simultaneously, the application of the virtual origin concept can make a difference in the mass flow calculation. Equations that include the virtual origin and revised flame height calculation can be found in NFPA 204, *Standard for Smoke and Heat Venting*, 9.2.3, Mass Flow Rate in Plume.

A.5.5.2.1 Equation 5.5.2.1 is based on Law's interpretation [22] of small-scale experiments by Morgan and Marshall [35]. Scenarios with balcony spill plumes involve smoke rising above a fire, reaching a ceiling, balcony, or other significant horizontal projection, then traveling horizontally toward the edge of the "balcony." Characteristics of the resulting balcony spill plume depend on characteristics of the fire, width of the spill plume, and height of the ceiling above the fire. In addition, the path of horizontal travel from the plume centerline to the balcony edge is significant.

Agreement of the predictions from Equation 5.5.2.1 with those from small-scale experimental efforts is presented in Figure A.5.5.2.1. Whereas the agreement is quite good, the results are from only two small-scale experimental programs.

The results of full-scale tests conducted as part of a joint research project involving the American Society for Heating, Refrigerating and Air-Conditioning Engineers and the National Research Council (Lougheed [27]; Lougheed [28]) indicate that the balcony spill plume equation developed by Law provides a reasonable but conservative estimate for smoke layer interface heights up to 50 ft (15 m).

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

The full-scale tests as well as research conducted at Building Research Establishment (BRE) using scale physical models (Marshall and Harrison [30]) indicate that higher smoke production rates than predicted by spill plume equations can be produced in a small atrium of 10 m × 10 m × 19 m in height. The additional smoke production has been attributed to the recirculation of the ceiling jet produced by the spill plume in the atrium space resulting in additional air entrainment. This additional smoke production is more likely to occur for scenarios with narrow openings (7.5 m) and with draft curtains. For a small atrium, it is recommended that the final design be supported by a modeling study.



FIGURE A.5.5.2.1 Agreement Between Predictions and Experimental Values (Morgan and Marshall [35]; Mulholland [37]).

A.5.5.2.5 Visual observations of the width of the balcony spill plume at the balcony edge were made in a set of small-scale experiments by Morgan and Marshall [35] and analyzed by Law [22]. In those experiments, the fire was in a communicating space immediately adjacent to the atrium. An equivalent width can be defined by equating the entrainment from an unconfined balcony spill plume to that from a confined balcony spill plume.

The results of full-scale tests conducted as part of a joint research project involving the American Society for Heating, Refrigerating and Air-Conditioning Engineers and the National Research Council (Lougheed [27]; Lougheed [28]) indicate that the equation for the width of the unconfined spill plume is valid for spill plumes from compartments with opening widths of 16 ft (5 m) to 46 ft (14 m).

A.5.5.2.6 Equations 5.5.2.6a and 5.5.2.6b are based on a parametric study using CFD model simulations (Lougheed [28]; McCartney, Lougheed, and Weckman [31]) to determine the best fit for the parameters to determine smoke production rates in a high atrium. The virtual origin term for the equation was determined such that Equation 5.5.2.6a or 5.5.2.6b provides the same estimate for the mass flow rate for a smoke layer interface height at 50 ft (15 m) as Equation 5.5.2.1a or 5.5.2.1b. For narrow spill plumes, the initially rectangular plume will evolve to an axisymmetric plume as it rises, resulting in a higher smoke production rate than that predicted by Equation 5.5.2.7a or 5.5.2.7b. It is recommended that the final design be supported by a CFD modeling study.

A.5.5.2.7 Equations 5.5.2.7a and 5.5.2.7b are similar to the algebraic equation used to determine smoke production by a line plume originating in the large-volume space (CIBSE [3]). The equations are also comparable to the algebraic equations determined for a spill plume based on an infinite line plume approximation (Morgan et al. [34]). The virtual origin term for the equations was determined such that Equation 5.5.2.7a or 5.5.2.7b provides the same estimate for the mass flow rate for a smoke layer interface height at 50 ft (15 m) as Equation 5.5.2.1a or 5.5.2.1b. It is recommended that the final design be supported by a CFD modeling study.

A.5.5.2.8 For high smoke layer interface heights, a fire in an atrium can result in a higher smoke production rate than a balcony spill plume.

Figure A.5.5.2.8 compares the mass flow rates in the spill plume estimated using Figure Equation 61 (Equation 5.5.2.1a or 5.5.2.1b), Figure Equation 63 (Equation 5.5.2.7a or 5.5.2.7b), and Figure Equation 64 (Equation 5.5.2.6a or 5.5.2.6b) for a design fire with a convective heat release rate of 1000 kW and a balcony height of 16 ft (5 m) and spill widths of 16 ft (5 m) and 33 ft (10 m). The estimated mass flow rates are the same at the 50 ft (15 m) height above the balcony. Also, Figure Equations 63 and 64 provide comparable results for the case with the 33 ft (10 m) spill width.



FIGURE A.5.5.2.8 Estimated Mass Flow Rates.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

A.5.5.3 Window plumes are not expected for sprinkler-controlled fires.

A.5.5.3.1 Equation 5.5.3.1a or 5.5.3.1b is appropriate when the heat release rate is limited by the air supply to the compartment, the fuel generation is limited by the air supply, and excess fuel burns outside the compartment using air entrained outside the compartment. The methods in 5.5.3.1 are also valid only for compartments having a single ventilation opening.

Equations 5.5.3.1a and 5.5.3.1b are for a ventilation-controlled fire where the heat release rate can be related to the characteristics of the ventilation opening. These equations are based on experimental data for wood and polyurethane by Modak and Alpert [32] and Tewarson [54].

A.5.5.3.2 The air entrained into the window plume can be determined by analogy with the axisymmetric plume. This is accomplished by determining the entrainment rate at the tip of the flames issuing from the window and determining the height in an axisymmetric plume that would yield the same amount of entrainment. The mass entrainment for window plumes is given as follows:

$$m = \left[0.022 Q_c^{1/3} \left(z_w + a\right)^{5/3}\right] + 0.0042 Q_c$$

Substituting Equation 5.5.3.1 into this mass flow rate and using $Q_c = 0.7j$ results in Equation 5.5.3.2.

The virtual source height is determined as the height of a fire source in the open that gives the same entrainments as the window plume at the window plume flame tip. Further entrainment above the flame tip is assumed to be the same as for a fire in the open. Although this development is a reasonably formulated model for window plume entrainment, no data are available to validate its use. As such, the accuracy of the model is unknown.

A.5.5.4 As a plume rises, it entrains air and widens. The required values of K_d will result in conservative calculations.

A.5.5.5 The mass flow rate of the plume can be calculated from Equation 5.5.1.1b, 5.5.1.1c, 5.5.2.1, or 5.5.3.2, which were developed for strongly buoyant plumes; for small temperature differences between the plume and ambient, errors due to low buoyancy could be significant. This topic needs further study; in the absence of better data, it is recommended that the plume equations not be used when this temperature difference is small [<4°F (<2.2°C)].

The temperature from Equation 5.5.5 is a mass flow average, but the temperature varies over the plume cross section. The plume temperature is greatest at the centerline of the plume; the centerline temperature is of interest when atria are tested by real fires.

The plume's centerline temperature should not be confused with the average plume temperature. The centerline temperature of an axisymmetric plume should be determined using Equation A.5.5.5a as follows:

For U.S. units,

$$T_{cp} = T_o + 9.1\left(\frac{T_o}{g C_p^2 \rho_o^2}\right)^{1/3} \frac{Q^{2/3}}{z^{5/3}} \qquad \textbf{(A.5.5.5a)}$$

where:

T_{cp} = absolute centerline plume temperature of an axisymmetric plume at elevation z (R)
T_o = absolute ambient temperature (R)
g = acceleration of gravity (32.2 ft/sec^2)
C_p = specific heat of air (0.24 Btu/lb-R)
ρ_o = density of ambient air (lb/ft^3)
Q = convective heat release rate of the fire (Btu/sec)
z = height above base of fuel (ft)

For SI units,

T_{cp} = absolute centerline plume temperature of an axisymmetric plume at elevation z (K)
T_o = absolute ambient temperature (K)
g = acceleration of gravity (9.81 m/sec^2)
C_p = specific heat of air (1.0 kJ/kg-K)
ρ_o = density of ambient air (kg/m^3)
Q = convective heat release rate of the fire (kW)
z = height above base of fuel (m)

Based on the first law of thermodynamics, the average temperature of the plume above the flame should be determined using Equation A.5.5.5b, as follows:

$$T_p - T_o + \frac{Q_c}{m C_p} \qquad \textbf{(A.5.5.5b)}$$

where:

T_p = average plume temperature at elevation z (°F or °C)
T_o = ambient temperature (°F or °C)
Q_c = convective portion of heat release (Btu/sec or kW)
m = mass flow rate of the plume at elevation z (lb/sec or kg/sec)
C_p = specific heat of plume gases (0.24 Btu/lb-°F or 1.0 kJ/kg-°C)

A.5.6 The sizing and spacing of exhaust fan intakes should balance the following concerns:

(1) The exhaust intakes need to be sufficiently close to one another to prevent the smoke from cooling to the point that it loses buoyancy as it travels along the underside of the ceiling to an intake and descends from the ceiling. This is particularly important for spaces where the length is greater than the height, such as shopping malls.
(2) The exhaust intakes need to be sized and distributed in the space to minimize the likelihood of air beneath the smoke layer from being drawn through the layer. This phenomenon is called plugholing.

The objective of distributing fan inlets is to establish a gentle and generally uniform rate over the entire smoke layer. To accomplish this, the velocity of the exhaust inlet should not exceed the value determined from Equation 5.6.3a or 5.6.3b.

A.5.6.3 The plugholing equations in this paragraph are consistent with and derived from the scale model studies of Spratt and Heselden [47]. These equations are also consistent with the recent study of Nii et al. [39].

A.5.6.4 The γ factor of 1.0 applies to ceiling vents remote from a wall. *Remote* is regarded as a separation greater than two times the depth of the smoke layer below the lower point of the exhaust opening.

A.5.6.5 The γ factor of 0.5 is based on potential flow considerations for a ceiling vent adjacent to a wall. While γ should vary smoothly from 0.5 for a vent directly adjacent to a wall to 1.0 for a ceiling vent remote from a wall, the available data do not support this level of detail in the requirements of the standard.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

A.5.6.6 The γ factor of 0.5 is used for all wall vents. Because no data exist for wall exhausts, a value of γ greater than 0.5 could not be justified.

A.5.6.7 Noise due to exhaust fan operation or to velocity at the exhaust inlet should be limited to allow the fire alarm signal to be heard.

A.5.7 For smoke management purposes, the density of smoke can be considered the same as the density of air. Equations 5.8a and 5.8b apply to both smoke and air. Designers should use the atmospheric pressure for a specific location. Standard atmospheric pressure is 14.696 psi (101,325 Pa).

A.5.8 For smoke management purposes, the density of smoke can be considered the same as the density of air. Equations 5.8a and 5.8b apply to both smoke and air. Designers should use the atmospheric pressure for a specific location. Standard atmospheric pressure is 14.696 psi (101,325 Pa).

A.5.9 The algebraic equations in Chapter 5 and many of the compartment fire models are only for spaces of uniform cross-sectional area. In practice, it is recognized that spaces being evaluated will not always exhibit a simple uniform geometry. The descent of the first indication of smoke in varying cross sections or complex geometric spaces can be affected by conditions such as sloped ceilings, variations in cross-sectional areas of the space, and projections into the rising plume. Methods of analysis that can be used to deal with complex and nonuniform geometries are as follows:

(1) Scale models *(See 5.1.2, Section 5.6, and A.5.6.)*
(2) CFD models *(See 5.1.3 and Annex F.)*
(3) Zone model adaptation *(See Annex C.)*
(4) Bounding analysis *(See Annex C.)*

A.5.11 In this standard, scale modeling pertains to the movement of hot gas through building configurations due to fire. A fire needs to be specified in terms of a steady or unsteady heat release rate.

For the zone modeling of this standard, combustion and flame radiation phenomena are ignored. Fire growth is not modeled.

A more complete review of scaling techniques and examples can be found in the referenced literature (Quintiere [43]). Smoke flow studies have been made by Heskestad [8] and by Quintiere, McCaffrey, and Kashiwagi [44]. Analog techniques using a water and saltwater system are also available (Steckler, Baum, and Quintiere [48]). Smoke flow modeling for buildings is based on maintaining a balance between the buoyancy and convective "forces" while ignoring viscous and heat conduction effects. Neglecting these terms is not valid near solid boundaries. Some compensation can be made in the scale model by selecting different materials of construction.

Dimensionless groups can be formulated for a situation involving a heat source representing a fire along with exhaust and makeup air supply fans of a given volumetric flow rate. The solution of the gas temperature *(T)*, velocity *(v)*, pressure *(p)*, and surface temperature *(T_s)* expressed in dimensionless terms and as a function of *x*, *y*, *z*, and time *(t)* are as follows:

$$\left\{ \frac{T}{T_o},\ \frac{v}{\sqrt{gl}},\ \frac{\rho}{\rho_o gl},\ \frac{T_s}{T_o} \right\} = f\left(\frac{x}{l}, \frac{y}{l}, \frac{z}{\sqrt{l/g}}, \pi_1, \pi_2, \pi_3 \right) \qquad \textbf{(A.5.11a)}$$

where:
T_o = ambient temperature
g = gravitational acceleration
l = characteristic length
ρ_o = ambient density

π_1, π_2, and π_3 are dimensionless groups arising from the energy release of the fire, fan flows, and wall heat transfer as follows:

$$\pi_1 = \frac{Q}{\rho_o c_o \sqrt{gl}^{5/2}} \sim \frac{\text{fire energy}}{\text{flow energy}} \qquad \textbf{(A.5.11b)}$$

where:
Q = energy release rate of the fire
c_o = specific heat of the ambient air

$$\pi_2 = \frac{V_{fan}}{\sqrt{gl}^{5/2}} \sim \frac{\text{fan flow}}{\text{buoyant flow}} \qquad \textbf{(A.5.11c)}$$

where:
V_{fan} = volumetric flow rate of the exhaust fan

$$\pi_3 = \frac{1}{(k\rho c)_w} \left(\frac{\rho_o}{\mu} \right)^{1.6} g^{0.3} k^2 l^{0.9} \sim \frac{\text{convection heat transfer}}{\text{wall heat transfer}} \qquad \textbf{(A.5.11d)}$$

where:
$(k\rho c)_w$ = thermal properties (conductivity, density, and specific heat) of the wall
μ = gas viscosity
k = gas thermal conductivity

The expression of π_3 is applicable to a thermally thick construction material. Additionally, more than one dimensionless π will be needed if wall thickness and radiation effects are significant. π_3 attempts to correct for heat loss at the boundary by permitting a different construction material in the scale model in order to maintain a balance for the heat losses.

The scaling expression for the fire heat release rate follows from preserving π_1. Similarly, expressions for the volumetric exhaust rate and wall thermal properties are obtained from preserving π_2 and π_3.

The wall properties condition is easily met by selecting a construction material that is noncombustible and approximately matches $(k\rho c)_w$ with a material of sufficient thickness to maintain the thermally thick condition. The thermal properties of enclosure can be scaled as follows:

$$(k\rho c)_{w,m} = (k\rho c)_{m,F} \left(\frac{l_m}{l_F} \right)^{0.9} \qquad \textbf{(A.5.11e)}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

where:

$(k\rho c)_{w,m}$ = thermal properties of the wall of the model
$(k\rho c)_{w,F}$ = thermal properties of the wall of the full-scale facility
c = specific heat of enclosure materials (wall, ceiling)
k = thermal conductivity of enclosure materials (wall, ceiling)
ρ = density of enclosure materials (wall, ceiling)

The following examples are included to provide insight into the way that the Froude modeling scaling relations are used.

Example 1. What scale model should be used for a mall where the smallest area of interest at 3 m is the floor-to-ceiling height on the balconies?

Note that it is essential that the flow in the model is fully developed turbulent flow; to achieve this, it is suggested that areas of interest in the scale model be at least 0.3 m. The corresponding floor-to-ceiling height of the model should be at least 0.3 m. Set $l_m = 0.3$ m, and $lF = 3$ m, then $l_m/l_F = 0.1$.

Example 2. The design fire for a specific facility is a constant fire of 5000 kW. What size fire will be needed for a one-tenth scale model?

$$\frac{l_m}{l_F} = 0.1 \qquad \textbf{(A.5.11f)}$$

$$Q_m = Q_F\left(\frac{l_m}{l_F}\right)^{5/2} = 5000(0.1)^{5/2} = 15.8 \text{ kW} \qquad \textbf{(A.5.11g)}$$

Example 3. For a full-scale facility with a smoke exhaust rate of 250 m^3/sec, what is the smoke exhaust rate for a one-tenth scale model?

$$V_{fan,m} = V_{fan,F}\left(\frac{l_m}{l_F}\right)^{5/2} = 250(0.1)^{5/2} = 7.9 \text{ m}^3/\text{sec} \qquad \textbf{(A.5.11h)}$$

Example 4. The walls of a full-scale facility are made of concrete. What is the impact of constructing the walls of a one-tenth scale model of gypsum board? The $k\rho c$ of brick is 1.7 $kW^2/m^{-4} \cdot K^{-2} \cdot s$. The ideal thermal properties of the model can be calculated as follows:

$$(k\rho c)_{w,m} = (k\rho c)_{w,F}\left(\frac{l_m}{l_F}\right)^{0.9} = (1.7)(0.1)^{0.9} = 0.21\left(\text{kW}^2/\text{m}^{-4} \cdot \text{sec}\right) \qquad \textbf{(A.5.11i)}$$

The value for gypsum board is 0.18 $kW^2/m^{-4} \cdot K^{-2} \cdot s$, which is close to the ideal value above, so that the gypsum board is a good match. It should be noted that using glass windows for video and photographs would be more important than scaling of thermal properties.

Example 5. In a one-tenth scale model, the following clear heights were observed: 2.5 m at 26 seconds, 1.5 m at 85 seconds, and 1.0 m at 152 seconds. What are the corresponding clear heights for the full-scale facility? For the first clear height and time pair of $z_m = 2.5$ m at $t_m = 26$ seconds:

$$z_F = z_m\left(\frac{l_F}{l_m}\right) = 2.5(10/1) = 25 \text{ m} \qquad \textbf{(A.5.11j)}$$

and

$$t_F = t_m\left(\frac{l_F}{l_m}\right)^{1/2} = 26(10/1)^{1/2} = 82 \text{ sec} \qquad \textbf{(A.5.11k)}$$

The other clear height and time pairs are calculated in the same manner and are listed in Table A.5.11(a) and Table A.5.11(b).

Table A.5.11(a) Scale Model Observation Clear Height

Clear Height (m)	Time (sec)
2.5	26
1.5	85
1.0	152

Table A.5.11(b) Full-Scale Facility Prediction

Clear Height (m)	Time (sec)
25	82
15	269
10	480

A.6.2 See Annex G for information on types of HVAC air-handling systems.

A.6.2.4 Exhaust fans should be operated prior to the operation of the makeup air supply. The simplest method of introducing makeup air into the space is through direct openings to the outside, such as through doors and louvers, which can be opened upon system activation. Such openings can be coordinated with the architectural design and be located as required below the design smoke layer. For locations where such openings are impractical, a mechanical supply system can be considered. This system could be an adaptation of the building's HVAC system if capacities, outlet grille locations, and velocities are suitable. For those locations where climates are such that damage to the space or contents could be extensive during testing or frequent inadvertent operation of the system, consideration should be given to heating the makeup air.

A.6.4 Related systems can include fire protection signaling systems, sprinkler systems, and HVAC systems, among others. Simplicity should be the goal of each control system. Complex systems should be avoided. Such systems tend to confuse, might not be installed correctly, might not be properly tested, might have a low level of reliability, and might not be maintained.

A.6.4.3 Various types of control systems are commonly used for HVAC systems. These control systems utilize pneumatic, electric, electronic, and programmable logic-based control units. All these control systems can be adapted to provide the necessary logic and control sequences to configure HVAC systems for smoke control functions. Programmable electronic logic-based (i.e., microprocessor-based) control units, which control and monitor HVAC systems as well as provide other building control and monitoring functions, are readily applicable for providing the necessary logic and control sequences for an HVAC system's smoke control mode of operation.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

The control system should be designed as simply as possible to attain the required functionality. Complex controls, if not properly designed and tested, can have a low level of reliability and can be difficult to maintain.

A.6.4.4.1.1 For purposes of automatic activation, fire detection devices include automatic devices such as smoke detectors, waterflow switches, and heat detectors.

A.6.4.4.1.2 During a fire, it is likely that enough smoke to activate a smoke detector might travel to other zones and subsequently cause alarm inputs for other zones. Systems activated by smoke detectors should continue to operate according to the first alarm input received rather than divert controls to respond to any subsequent alarm input(s).

A.6.4.4.1.3 Systems initiated by heat-activated devices and designed with sufficient capacity to exhaust multiple zones can expand the number of zones being exhausted to include the original zone and subsequent additional zones, up to the limit of the mechanical system's ability to maintain the design pressure difference. Exceeding the design capacity likely will result in the system's failing to adequately exhaust the fire zone or to achieve the desired pressure differences. If the number of zones that can be exhausted while still maintaining the design pressure is not known, that number should be assumed to be one.

A.6.4.4.1.4 Documentation of the equipment to be operated for each automatically activated smoke control system configuration includes, but is not limited to, the following parameters:

(1) Fire zone in which a smoke control system automatically activates.
(2) Type of signal that activates a smoke control system, such as sprinkler waterflow or smoke detector.
(3) Smoke zone(s) where maximum mechanical exhaust to the outside is implemented and no supply air is provided.
(4) Positive pressure smoke control zone(s) where maximum air supply is implemented and no exhaust to the outside is provided.
(5) Fan(s) ON as required to implement the smoke control system. Multiple-speed fans should be further noted as FAST or MAX. VOLUME to ensure that the intended control configuration is achieved.
(6) Fan(s) OFF as required to implement the smoke control system.
(7) Damper(s) OPEN where maximum airflow must be achieved.
(8) Damper(s) CLOSED where no airflow should take place.
(9) Auxiliary functions might be required to achieve the smoke control system configuration or might be desirable in addition to smoke control. Changes or override of normal operation static pressure control set points should also be indicated if applicable.
(10) Damper position at fan failure.

Examples of auxiliary functions that can be useful, but that are not required, are the opening and closing of terminal boxes while pressurizing or exhausting a smoke zone. These functions are considered auxiliary if the desired state is achieved without the functions, but the functions help to achieve the desired state more readily.

A.6.4.4.1.5 See Annex E for additional information on the stratification of smoke.

A.6.4.4.1.5(1) The purpose of using an upward beam to detect the smoke layer is to quickly detect the development of a smoke layer at whatever temperature condition exists. One or more beams should be aimed at an upward angle to intersect the smoke layer regardless of the level of smoke stratification. More than one beam smoke detector should be used. The manufacturers' recommendations should be reviewed when using these devices for this application. Devices installed in this manner can require additional maintenance activity.

A.6.4.4.1.5(2) The purpose of using horizontal beams to detect the smoke layer at various levels is to quickly detect the development of a smoke layer at whatever temperature condition exists. One or more beam detectors are located at the ceiling. Additional detectors are located at other levels lower in the volume. The exact positioning of the beams is a function of the specific design but should include beams at the bottom of any identified unconditioned (dead-air) spaces and at or near the design smoke level with intermediate beam positions at other levels.

A.6.4.4.1.5(3) The purpose of using horizontal beams to detect the smoke plume is to detect the rising plume rather than the smoke layer. For this approach, an arrangement of beams close enough to each other to ensure intersection of the plume is installed at a level below the lowest expected stratification level. The spacing between beams has to be based on the narrowest potential width of the plume at the level of detection.

A.6.4.4.2.1 Authorized users possess keys, passwords, or other devices that limit unauthorized users from operating the smoke control equipment.

A.6.4.4.2.2 Manual pull stations are not used to activate smoke control strategies that require information on the location of the fire because of the likelihood of a person signaling an alarm from a station outside the zone of fire origin.

A.6.4.4.2.3 Generally, stairwell pressurization systems can be activated from a manual pull station, provided the response is common for all zones. Other systems that respond identically for all zone alarms can also be activated from a manual pull station. An active-tracking stairwell pressurization system that provides control based on the pressure measured at the fire floor should not be activated from a manual pull station.

A.6.4.4.2.5 Manual controls exclusively for other building-control purposes, such as hand-off-auto switches located on a thermostat, are not considered to be manual controls in the context of smoke control. Manual activation and deactivation for smoke control purposes should override manual controls for other purposes.

A.6.4.5.2.1.2 This equipment includes air supply/return fans and dampers subject to automatic control according to building occupancy schedules, energy management, or other purposes.

A.6.4.5.3.2 To prevent damage to equipment, it might be necessary to delay activation of certain equipment until other equipment has achieved a prerequisite state (i.e., delay starting a fan until its associated damper is partially or fully open).

A.6.4.5.3.3 The times given for components to achieve their desired state are measured from the time each component is activated.

A.6.4.5.3.4 Refer to 4.5.3 for additional information regarding calculation of time required for the system to become fully operational.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

A.6.4.5.4 See Annex H for additional considerations for a fire fighters' smoke control station.

A.6.4.5.4.3 For complex control and containment system designs, status indication, fault indication, or manual control can be provided for groups of components or by smoke control zone.

A.6.4.5.4.7 Indirect indication of fan status, such as motor current measurement or motor starter contact position, may not be positive proof of airflow.

A.6.4.6.1.1 In limited instances, it can be desirable to pressurize only some stairwells due to fastidious building configurations and conditions.

A.6.4.7.2.1 If fire alarm zones and smoke control zones do not coincide, there is a possibility that the wrong smoke control system(s) can be activated.

A.6.4.7.3 Manual pull stations are not used to activate zoned smoke containment strategies because these types of system require information on the location of the fire, and there is no assurance that the pull station that was activated is located in the smoke zone.

A.6.4.8 The means and frequency of verification methods will vary according to the complexity and importance of the system as follows:

(1) Positive confirmation of fan activation should be by means of duct pressure, airflow, or equivalent sensors that respond to loss of operating power, problems in the power or control circuit wiring, airflow restrictions, and failure of the belt, the shaft coupling, or the motor itself.
(2) Positive confirmation of damper operation should be by contact, proximity, or equivalent sensors that respond to loss of operating power or compressed air; problems in the power, control circuit, or pneumatic lines; and failure of the damper actuator, the linkage, or the damper itself.
(3) Other devices, methods, or combinations of methods as approved by the authority having jurisdiction might also be used.

Items A.6.4.8(1) through A.6.4.8(3) describe multiple methods that can be used, either singly or in combination, to verify that all portions of the controls and equipment are operational. For example, conventional (electrical) supervision might be used to verify the integrity of portions of the circuit used to send an activation signal from a fire alarm system control unit to the relay contact within 3 ft (1 m) of the smoke-control system input *(see 6.4.8.4)*, and end-to-end verification might be used to verify operation from the smoke-control system input to the desired end result. If different systems are used to verify different portions of the control circuit, controlled equipment, or both, then each system would be responsible for indicating off-normal conditions on its respective segment.

End-to-end verification, as defined in 3.3.6, monitors both the electrical and mechanical components of a smoke control system. End-to-end verification provides positive confirmation that the desired result has been achieved during the time that a controlled device is activated. The intent of end-to-end verification goes beyond determining whether a circuit fault exists, but instead ascertains whether the desired end result (e.g., airflow or damper position) is achieved. True end-to-end verification, therefore, requires a comparison of the desired operation to the actual end result.

An open control circuit, failure of a fan belt, disconnection of a shaft coupling, blockage of an air filter, failure of a motor, or other abnormal condition that could prevent proper operation is not expected to result in an off-normal indication when the controlled device is not activated, since the measured result at that time matches the expected result. If a condition that prevents proper operation persists during the next attempted activation of the device, an off-normal indication should be displayed.

A.6.6.3 Temperatures within the smoke layer and the fire plume can be determined using methods outlined in this standard. Where flashover in the room of fire origin is a concern, the design temperature should be 1700°F (927°C).

A.7.3 The building owner can pass on the owner responsibilities identified in 7.3.3 and 7.3.4 to the occupant, management firm, or managing individual through specific provisions in the lease, written use agreement, or management contract. Where this is done, the building owner should provide a copy of the operations and maintenance manual, including testing results, to all responsible parties.

A.8.1 Some smoke control systems are designed to limit smoke migration at the boundaries of a smoke control area using pressure differences. A stairwell pressurization system is used to limit smoke movement from the floor area into the stairwell and thus provide a tenable environment during egress. For zoned smoke control, pressure differences are used to contain smoke within the smoke zone and limit the migration of smoke and fire gases to other parts of the building. Testing appropriate to the objective of the system consists of measuring the pressure difference between the smoke zone and the adjacent zones. The testing procedures provided in Section 8.4 are based on the measurement of pressure differences and door-opening forces under the design conditions agreed on with the authority having jurisdiction.

An understanding with the authority having jurisdiction on the expected performance of the system and the acceptance test procedures should be established early in the design. (Detailed engineering design information is contained in ASHRAE/SFPE *Principles of Smoke Management* [21] and the NFPA publication *Smoke Movement and Control in High-Rise Buildings* [49]).

Absence of a consensus agreement for a testing procedure and acceptance criteria historically has created numerous problems at the time of system acceptance, including delays in obtaining a certificate of occupancy.

It is recommended that the building owner, the designer, and the authority having jurisdiction meet during the planning stage of the project to share their thoughts and objectives concerning the smoke control system and agree on the design criteria and the pass/fail performance tests for the systems. Such an agreement helps to overcome the numerous problems that occur during final acceptance testing and facilitates obtaining the certificate of occupancy.

A.8.1.4 The intent is that all parties — designers, installers, owners, and authorities having jurisdiction — have a clear understanding of the system objectives and the testing procedure.

A.8.3 The intent of component system testing is to establish that the final installation complies with the specified design, is functioning properly, and is ready for acceptance testing. Operational testing of system components should be completed during construction. These operational tests normally are performed by various trades before interconnection is made to integrate the overall smoke control system. It should be documented in writing that each individual system component's installation is complete and the component is functional. Each component test, including items such as speed, volume, sensitivity calibration, voltage, and amperage, should be individually documented.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

A.8.3.3 Systems that could affect or be affected by the operation of the smoke control system include the following:

(1) Fire alarm system *(see NFPA 72, National Fire Alarm and Signaling Code)*
(2) Energy management system
(3) Building management system
(4) Heating, ventilating, and air-conditioning (HVAC) equipment
(5) Electrical equipment
(6) Temperature control system
(7) Power sources
(8) Standby power
(9) Automatic suppression systems
(10) Automatic operating doors and closures
(11) Other smoke control systems
(12) Emergency elevator operation
(13) Dampers
(14) Fire fighters' control station (FFCS)

A.8.4.1 Representatives of one or more of the following should be present during acceptance testing to grant acceptance:

(1) Authority having jurisdiction
(2) Owner
(3) Designer
(4) Subsystem contractors

A.8.4.2 Parameters that should be tested during the acceptance testing include the following:

(1) Total volumetric flow rate
(2) Airflow velocities
(3) Airflow direction
(4) Door-opening forces
(5) Pressure differences
(6) Ambient indoor and outdoor temperatures
(7) Wind speed and direction

The following equipment might be needed to perform acceptance testing:

(1) Differential pressure gauges, inclined water manometers, or electronic manometer [instrument ranges 0–0.25 in. w.g. (0–62.5 Pa) and 0–0.50 in. w.g. (0–125 Pa) with a sufficient length of tubing], including traversing equipment
(2) Scale suitable for measuring door-opening force
(3) Anemometer
(4) Ammeter and voltmeter
(5) Door wedges
(6) Tissue paper roll or other convenient device for indicating direction of airflow
(7) Signs indicating that a test of the smoke control system is in progress and that doors should not be opened
(8) Several walkie-talkie radios (useful to help coordinate equipment operation and data recording)
(9) Psychrometer
(10) Flow measuring hood (optional)

Other Test Methods. Much can be accomplished to demonstrate smoke control system operation without resorting to demonstrations that use smoke or products that simulate smoke.

The test methods previously described should provide an adequate means to evaluate the smoke control system's performance. Other test methods have been used historically in instances where the authority having jurisdiction requires additional testing. These test methods have limited value in evaluating certain system performance, and their validity as a method of testing a smoke control system is questionable.

As covered in the preceding chapters, the dynamics of the fire plume, buoyancy forces, and stratification are all major critical elements in the design of the smoke control system. Therefore, to test the system properly, a real fire condition would be the most appropriate and meaningful test. However, there are many valid reasons why such a fire is not practical in a completed building. Open flame/actual fire testing might be dangerous and normally should not be attempted. Any other test is a compromise. If a test of the smoke control system for building acceptance is mandated by the authority having jurisdiction, such a test condition would become the basis of design and might not in any way simulate any real fire condition. More important, it could be a deception and provide a false sense of security that the smoke control system would perform adequately in a real fire emergency.

Smoke bomb tests do not provide the heat, buoyancy, and entrainment of a real fire and are not useful in evaluating the real performance of the system. A system designed in accordance with this document and capable of providing the intended smoke control might not pass smoke bomb tests. Conversely, it is possible for a system that is incapable of providing the intended smoke control to pass smoke bomb tests. Because of the impracticality of conducting real fire tests, the acceptance tests described in this document are directed to those aspects of smoke control systems that can be verified.

It is an understatement to say that acceptance testing involving a real fire has obvious danger to life and property because of the heat generated and the toxicity of the smoke.

A.8.4.3 Guidance on test procedures can be found in the publications of organizations such as the Associated Air Balance Council (AABC); the National Environmental Balancing Bureau (NEBB); the American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE); and the Sheet Metal and Air Conditioning Contractors National Association (SMACNA).

A.8.4.4.1 Building mechanical equipment that is not typically used to implement smoke control includes but is not limited to toilet exhaust, elevator shaft vents, elevator machine room fans, and elevator and kitchen hoods.

A.8.4.4.2 The normal building power should be disconnected at the main service disconnect to simulate true operating conditions in standby power mode.

A.8.4.4.4(2) One or more device circuits on the fire alarm system can initiate a single input signal to the smoke control system. Therefore, consideration should be given to establishing the appropriate number of initiating devices and initiating device circuits to be operated to demonstrate the smoke control system operation.

A.8.4.5 Large-volume spaces come in many configurations, each with its own peculiarities. They can be tall and thin or short and wide, have balconies and interconnecting floors, be open or closed to adjacent floors, have corridors and stairs for use in evacuation, have only exposed walls and windows (sterile tube), or be a portion of a hotel, hospital, shopping center, or arena. Specific smoke control criteria have to be developed for each unique situation.

A.8.4.6.1.4 The local code and contract documents' requirements should be followed regarding the number and location of all doors that need to be opened for this test.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

In lieu of specific direction in the local code or contract documents, choose the doors to be opened as follows in order to produce the most severe conditions:

(1) For the differential pressure test, the open doors should include those for which the highest pressure difference was measured in the tests with all doors closed *(see 8.4.6.1)*. When measured with the stairwell as the reference, these doors have the greatest negative values.
(2) When systems are designed for open stairwell doors and total building evacuation, the number of open doors should include the exterior stairwell door.
(3) Because the pressure in the stairwell must be greater than the pressure in the occupied areas, it is not necessary to repeat the door-opening force tests with open doors. Opening any door would decrease the pressure in the stairwell and thereby decrease the door-opening force on the remaining doors.

A.8.4.6.2 Door-opening forces include frictional forces, the forces produced by the door hardware, and the forces produced by the smoke control system. In cases where frictional forces are excessive, the door should be repaired. *(See Annex I for information on testing for leakage between smoke zones.)*

A.8.4.6.4 The exact location of each smoke control zone and the door openings in the perimeter of each zone should be verified. If the plans do not specifically identify these zones and doors, the fire alarm system in those zones might have to be activated so that any doors magnetically held open will close and identify the zone boundaries. *(See Annex I for information on testing for leakage between smoke zones.)*

A.8.4.6.4.3.6 After a smoke zone's smoke control systems have been tested, it should be ensured that the systems are properly deactivated and the HVAC systems involved are returned to their normal operating modes prior to activation of another zone's smoke control system. It should be also ensured that all controls necessary to prevent excessive pressure differences are functional so as to prevent damage to ducts and related building equipment.

A.8.4.6.5 A consistent procedure should be established for recording data throughout the entire test, such that the shaft side of the doors is always considered as the reference point [0 in. w.g. (0 Pa)] and the floor side of the doors always has the pressure difference value (positive if higher than the shaft and negative if less than the shaft).

Because the hoistway pressurization system is intended to produce a positive pressure within the hoistway, all negative pressure values recorded on the floor side of the doors are indicative of a potential airflow from the shaft to the floor.

A.8.4.6.5.2.1(C) Where enclosed elevator lobbies are pressurized by an elevator lobby pressurization system, or where enclosed elevator lobbies receive secondary pressurization from the elevator hoistway, they should be treated as a zone in a zoned smoke control system.

A.8.4.6.7.1 When testing the combination of zoned smoke control systems and stairwell pressurization systems, the tests applicable to each stand-alone system should be conducted. Differential pressure tests are specified in both 8.4.6.3 and 8.4.6.4. When the two systems are used in combination, the stairwell should be treated as a zone in a zoned smoke control system. The minimum design pressures specified in Table 4.4.2.1.1 apply only to the differential pressure tests specified in 8.4.6.4.

Differential pressure tests conducted as directed in 8.4.6.1 are used to determine the doors that should be opened during the tests specified in 8.4.6.2. It is not expected that these values will comply with the minimum design pressures specified in Table 4.4.2.1.1, except at the fire floor.

In lieu of specific direction in the local code or contract documents, choose the doors to be opened as follows in order to produce the most severe conditions:

(1) For the differential pressure test, the open doors should include those for which the highest pressure difference was measured in the tests with all doors closed *(see 8.4.6.2)*, excluding the door on the fire floor. When measured with the stairwell as the reference, these doors have the greatest negative values.
(2) When systems are designed for open stairwell doors and total building evacuation, the number of open doors should include the exterior stairwell door.
(3) For the door-opening force test, the open doors should include any doors (up to the specified number) found in the tests with all doors closed *(see 8.4.6.2)* to have pressure in the occupied area greater than the pressure in the stairwell. Opening these doors adds pressure to the stairwell, thereby increasing door-opening forces on the remaining doors. When measured with the stairwell as the reference, these doors have the greatest positive values. If no doors meet these criteria, it is not necessary to repeat the door-opening force tests with open doors, since opening any door would decrease the pressure in the stairwell and thereby decrease the door-opening force on the remaining doors.

A.8.5.1 This documentation should include results from the preliminary building inspection, component testing, and acceptance testing.

A.8.6.1 During the life of the building, maintenance is essential to ensure that the smoke control system will perform its intended function under fire conditions. Proper maintenance of the system should, as a minimum, include periodic testing of all equipment such as initiating devices, fans, dampers, controls, doors, and windows. The equipment should be maintained in accordance with the manufacturer's recommendations. *(See* NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems.)*

Special arrangements might have to be made for the introduction of large quantities of outside air into occupied areas or computer centers when outside temperature and humidity conditions are extreme. Because smoke control systems override limit controls, such as freezestats, tests should be conducted when outside air conditions will not cause damage to equipment and systems.

A.8.7.1 Documentation should be updated to reflect changes or modifications.

Annex B Predicting the Rate of Heat Release of Fires

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

B.1 Introduction. This annex presents techniques for estimating the heat release rate of various fuel arrays likely to be present in buildings where smoke venting is a potential fire safety provision. It primarily addresses the estimation of fuel concentrations found in retail shops, stadiums, offices, and similar locations that might involve large areas addressed by

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

this standard. Conversely, NFPA 204, *Standard for Smoke and Heat Venting*, addresses the types of fuel arrays more common to storage and manufacturing locations and other types of building situations covered by that standard. This standard is applicable to situations where the hot layer does not enhance the burning rate. The methods provided in this annex for estimating the rate of heat release, therefore, are based on "free burning" conditions in which no ceiling or hot gas layer effects are involved. It is assumed that the burning rate is relatively unaffected by the hot layer.

Limited heat release rate data for some fuel commodities have been reported (Babrauskas and Krasny [56]; Babrauskas [55]; Klote and Milke [21]). However, furniture construction details and materials are known to substantially influence the peak heat release rate, such that heat release rate data are not available for all furniture items or for generic furniture items.

B.2 Sources of Data. The following sources of data appear in their approximate order of priority, given equal quality of data acquisition:

(1) Actual tests of the array involved
(2) Actual tests of similar arrays
(3) Algorithms derived from tests of arrays having similar fuels and dimensional characteristics
(4) Calculations based on tested properties and materials and expected flame flux
(5) Mathematical models of fire spread and development

B.3 Actual Tests of the Array Involved. Where an actual calorific test of the specific array under consideration has been conducted and the data are in a form that can be expressed as rate of heat release, the data can then be used as input for the methods in this standard. Since actual test data seldom produce the steady state assumed for a limited-growth fire or the square of time growth assumed for a continuous growth (*t*-squared) fire, engineering judgment is usually needed to derive the actual input necessary if either of these approaches is used. *(See Section B.7 for further details relevant to t-squared fires.)* If a computer model that is able to respond to a rate of heat release versus time curve is used, the data can be used directly. Currently there is no established catalog of tests of specific arrays. Some test data can be found in technical reports. Alternatively, individual tests can be conducted.

Many fire tests do not include a direct measurement of rate of heat release. In some cases, it can be derived based on measurement of mass loss rate using the following equation:

$$Q = \dot{m} h_c \qquad \textbf{(B.3a)}$$

where:
Q = rate of heat release (kW)
$\dot{m}$ = mass loss rate (kg/sec)
h_c = heat of combustion (kJ/kg)

In other cases, the rate of heat release can be derived based on measurement of flame height as follows:

$$Q = 37\left(L + 1.02D\right)^{5/2} \qquad \textbf{(B.3b)}$$

where:
Q = rate of heat release (kW)
L = flame height (m)
D = fire diameter (m)

B.4 Actual Tests of Arrays Similar to That Involved. Where an actual calorific test of the specific array under consideration cannot be found, it can be possible to find data on one or more tests that are similar to the fuel of concern in important matters such as type of fuel, arrangement, or ignition scenario.

The more the actual tests are similar to the fuel of concern, the higher the confidence that can be placed in the derived rate of heat release. The addition of engineering judgment, however, might be needed to adjust the test data to those approximating the fuel of concern. If rate of heat release has not been directly measured, it can be estimated using the method described for estimating burning rate from flame height in Section B.3.

B.5 Algorithms Derived from Tests of Arrays Having Similar Fuels and Dimensional Characteristics.

B.5.1 Pool Fires. In many cases, the rate of heat release of a tested array has been divided by a common dimension, such as occupied floor area, to derive a normalized rate of heat release per unit area. The rate of heat release of pool fires is the best documented and accepted algorithm in this class.

An equation for the mass release rate from a pool fire is as follows (Babrauskas [55]):

$$m'' = m''_o\left(1 - e^{-kBD}\right) \qquad \textbf{(B.5.1)}$$

The variables for Equation B.5.1 are as shown in Table B.5.1.

The mass rates derived from Equation B.5.1 are converted to rates of heat release using Equation B.3a and the heat of combustion from Table B.5.1. The rate of heat release per unit area times the area of the pool yields heat release data for the anticipated fire.

B.5.2 Other Normalized Data. Other data based on burning rate per unit area in tests have been developed. Table B.5.2(a) and Table B.5.2(b) list the most available of these data.

B.5.3 Other Useful Data. Other data that are not normalized might be useful in developing the rate of heat release curve. Examples are included in Table B.5.3(a) through Table B.5.3(h).

B.6 Calculated Fire Description Based on Tested Properties.

B.6.1 Background. It is possible to make general estimates of the rate of heat release of burning materials based on the fire properties of that material. The fire properties involved can be determined by small-scale tests. The most important of these tests are calorimeter tests involving both oxygen depletion calorimetry and the application of external heat flux to the sample while determining time to ignition, rate of mass release, and rate of heat release for the specific applied flux.

Most prominent of the current test apparatus are the cone calorimeter *(see ASTM E 1354, Standard Test Method for Heat and Visible Smoke Release Rates for Materials and Products Using an Oxygen Consumption Calorimeter)* and the Factory Mutual calorimeter (Tewarson [54]). In addition to these directly measured properties, it is possible to derive ignition temperature, critical ignition flux, effective thermal inertia ($k\rho c$), heat of combustion, and heat of gasification based on results from these calorimeters. Properties not derivable from these calorimeters and essential to determining flame spread in directions not concurrent with the flow of the flame can be obtained from the lateral ignition and flame travel (LIFT) apparatus *(see ASTM E 1321, Standard Test Method for Determining Material Ignition and Flame Spread Properties)*. This section presents a concept of the use of fire property test data as the basis of an analytical evaluation of the rate of heat release involved in the use of a tested material.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.1 Data for Large Pool Burning Rate Estimates

Material	Density		h_c		$\dot{m}_b$		kb	
	lb/ft^3	kg/m^3	Btu/lb	mJ/kg	lb/ft^2·s	kg/m^2·s	ft^{-1}	m^{-1}
Cryogenics[a]								
Liquid H_2	4.4	70	55,500	120	0.0035	0.017	1.9	6.1
LNG (mostly CH_4)	26	415	21,500	50.0	0.016	0.078	0.33	1.1
LPG (mostly C_3H_8)	37	585	20,000	46.0	0.02	0.099	0.43	1.4
Alcohols								
Methanol (CH_3OH)	50	796	8,500	20.0	0.0035	—	[b]	—
Ethanol (C_2H_5OH)	50	794	11,500	26.8	0.0031	—	[b]	—
Simple organic fuels								
Butane (C_4H_{10})	36	573	20,000	45.7	0.016	0.078	0.82	2.7
Benzene (C_5H_6)	53	874	17,000	40.1	0.017	0.085	0.82	2.7
Hexane (C_6H_{14})	41	650	19,000	44.7	0.015	0.074	0.58	1.9
Heptane (C_7H_{16})	42	875	19,000	44.6	0.021	0.101	0.34	1.1
Xylene (C_8H_{10})	54	870	17,500	40.8	0.018	0.090	0.42	1.4
Acetone (C_3H_6O)	49	791	11,000	25.8	0.0084	0.041	0.58	1.9
Dioxane ($C_4H_8O_2$)	65	1035	11,000	26.2	0.0037[c]	0.018	1.6[c]	5.4
Diethyl ether ($C_4H_{10}O$)	45	714	14,500	34.2	0.017	0.085	0.21	0.7
Petroleum products								
Benzene	46	740	19,000	44.7	0.0098	0.048	1.1	3.6
Gasoline	46	740	19,000	43.7	0.011	0.055	0.64	2.1
Kerosene	51	820	18,500	43.2	0.008	0.039	1.1	3.5
JP-4	47	760	18,500	43.5	0.01	0.051	1.1	3.6
JP-5	51	810	18,500	43.0	0.011	0.054	0.49	1.6
Transformer oil, hydrocarbon	47	760	20,000	46.4	0.008[c]	0.039	0.21[c]	0.7
Fuel oil, heavy	59–62	940–1000	17,000	39.7	0.0072	0.035	0.52	1.7
Crude oil	52–55	830–880	18,000	42.5–42.7	0.0045–0.0092	0.022–0.045	0.85	2.8
Solids								
Polymethylmethacrylate $(C_5H_8O_2)_n$	74	1184	10,000	24.9	0.0041	0.022	1.0	3.2
Polypropylene $(C_3H_6)_n$	56	905	18,500	43.2	0.0037	—	—	—
Polystyrene $(C_8H_8)_n$	66	1050	17,000	39.7	0.007	—	—	—

[a]For pools on dry land, not over water.
[b]Value independent of diameter in turbulent regime.
[c]Estimate uncertain, since only two data points available.

The approach outlined in this section is based on that presented by Nelson and Forssell [57].

B.6.2 Discussion of Measured Properties. Table B.6.2(a) lists the type of fire properties obtainable from the cone or Factory Mutual calorimeters and similar instruments.

In Table B.6.2(a), the rate of heat release (RHR), mass loss, and time to ignition are functions of the externally applied incident radiant heat flux imposed on the tested sample. The purpose of the externally applied flux is to simulate the fire environment surrounding a burning item. In general, it can be estimated that a free-burning fuel package (i.e., one that burns in the open and is not affected by energy feedback from a hot gas layer of a heat source other than its own flame) is impacted by a flux in the range of 25 kW/m^2 to 50 kW/m^2. If the fire is in a space and conditions are approaching flashover, this can increase to the range of 50 kW/m^2 to 75 kW/m^2. In fully developed, post-flashover fires, a range of 75 kW/m^2 to over 100 kW/m^2 can be expected. The following is a discussion of the individual properties measured or derived and the usual form used to report the property.

Rate of Heat Release. Rate of heat release is determined by oxygen depletion calorimetry. Each test is run at a user-specific incident flux and either for a predetermined period of time or until the sample is consumed. The complete results are presented in the form of a plot of rate of heat release against time, with the level of applied flux noted. In some cases, the rate of heat release for several tests of the same material at different levels of applied flux is plotted on a single curve for comparison. Figure B.6.2 is an example of such a plotting.

Often only the peak rate of heat release at a specific flux is reported. Table B.6.2(b) is an example.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.2(a) Unit Heat Release Rate for Commodities

Commodity	Btu/sec · ft² of Floor Area	kW/m² of Floor Area
Wood pallets, stacked 1½ ft high (6–12% moisture)	125	1,420
Wood pallets, stacked 5 ft high (6–12% moisture)	350	4,000
Wood pallets, stacked 10 ft high (6–12% moisture)	600	6,800
Wood pallets, stacked 16 ft high (6–12% moisture)	900	10,200
Mail bags, filled, stored 5 ft high	35	400
Cartons, compartmented, stacked 15 ft high	150	1,700
PE letter trays, filled, stacked 5 ft high on cart	750	8,500
PE trash barrels in cartons, stacked 15 ft high	175	2,000
PE fiberglass shower stalls in cartons, stacked 15 ft high	125	1,400
PE bottles packed in compartmented cartons	550	6,200
PE bottles in cartons, stacked 15 ft high	175	2,000
PU insulation board, rigid foam, stacked 15 ft high	170	1,900
PS jars packed in compartmented cartons	1,250	14,200
PS tubs nested in cartons, stacked 14 ft high	475	5,400
PS toy parts in cartons, stacked 15 ft high	180	2,000
PS insulation board, rigid foam, stacked 14 ft high	290	3,300
PVC bottles packed in compartmented cartons	300	3,400
PP tubs packed in compartmented cartons	390	4,400
PP & PE film in rolls, stacked 14 ft high	550	6,200
Methyl alcohol	65	740
Gasoline	200	2,300
Kerosene	200	2,300
Diesel oil	175	2,040

For SI units, 1 ft = 0.305 m.

PE: Polyethylene. PP: Polypropylene. PS: Polystyrene. PU: Polyurethane. PV: Polyvinyl chloride.

Note: Heat release rate per unit floor area of fully involved combustibles, based on negligible radiative feedback from the surroundings and 100 percent combustion efficiency.

Mass Loss Rate (m). Mass loss rate is determined by a load cell. The method of reporting is identical to that for rate of heat release. In the typical situation where the material has a consistent heat of combustion, the curves for mass loss rate and rate of heat release are similar in shape.

Time to Ignition (q_i). Time to ignition is reported for each individual test and applied flux level conducted.

Effective Thermal Inertia (kDc). Effective thermal inertia is a measurement of the heat rise response of the tested material to the heat flux imposed on the sample. It is derived at the time of ignition and is based on the ratio of the actual incident flux to the critical ignition flux and the time to ignition. A series of tests at different levels of applied flux is necessary to derive the effective thermal inertia. Effective thermal inertia derived in this manner can differ from and be preferable to that derived using handbook data for the values of *k, D,* and *c* derived without a fire.

Heat of Combustion (H_c). Heat of combustion is derived by dividing the measured rate of heat release by the measured mass loss rate. It is normally reported as a single value, unless the sample is a composite material and the rates of heat release and mass loss vary significantly with time and exposure.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.2(b) Maximum Heat Release Rates

Warehouse Materials	Growth Time (sec)	Heat Release Density (q)	Classification
Wood pallets, stacked 1½ ft high (6–12% moisture)	150–310	110	M–F
Wood pallets, stacked 5 ft high (6–12% moisture)	90–190	330	F
Wood pallets, stacked 10 ft high (6–12% moisture)	80–110	600	F
Wood pallets, stacked 16 ft high (6–12% moisture)	75–105	900	F
Mail bags, filled, stored 5 ft high	190	35	F
Cartons, compartmented, stacked 15 ft high	60	200	*
Paper, vertical rolls, stacked 20 ft high	15–28	—	*
Cotton (also PE, PE/Cot, Acrylic/Nylon/PE), garments in 12 ft high rack	20–42	—	*
Cartons on pallets, rack storage, 15–30 ft high	40–280	—	M–F
Paper products, densely packed in cartons, rack storage, 20 ft high	470	—	M–S
PE letter trays, filled, stacked 5 ft high on cart	190	750	F
PE trash barrels in cartons stacked 15 ft high	55	250	*
FRP shower stalls in cartons, stacked 15 ft high	85	110	*
PE bottles packed in compartmented cartons	85	550	*
PE bottles in cartons, stacked 15 ft high	75	170	*
PE pallets, stacked 3 ft high	130	—	F
PE pallets, stacked 6–8 ft high	30–55	—	*
PU mattress, single, horizontal	110	—	F
PF insulation, board, rigid foam, stacked 15 ft high	8	170	*
PS jars packed in compartmented cartons	55	1200	*
PS tubs nested in cartons, stacked 14 ft high	105	450	F
PS toy parts in cartons, stacked 15 ft high	110	180	F
PS insulation board, rigid, stacked 14 ft high	7	290	*
PVC bottles packed in compartmented cartons	9	300	*
PP tubs packed in compartmented cartons	10	390	*
PP and PE film in rolls, stacked 14 ft high	40	350	*
Distilled spirits in barrels, stacked 20 ft high	23–40	—	*
Methyl alcohol	—	65	—
Gasoline	—	200	—
Kerosene	—	200	—
Diesel oil	—	180	—

For SI units, 1 ft = 0.305 m.

S: Slow. M: Medium. F: Fast.

FRP: Fiberglass-reinforced polyester. PE: Polyethylene. PP: Polypropylene. PS: Polystyrene. PU: Polyurethane. PVC: Polyvinyl chloride.

Notes:

(1) $Qm = qA$, where Qm = maximum heat release rate (Btu/sec), q = heat release density (Btu/sec · ft^2), and A = floor area (ft^2).

(2) The heat release rates per unit floor area are for fully involved combustibles, assuming 100 percent efficiency. The growth times shown are those required to exceed 1000 Btu/sec heat release rate for developing fires, assuming 100 percent combustion efficiency.

*Fire growth rate exceeds classification criteria.

Heat of Gasification (h_g). Heat of gasification is the flux needed to pyrolyze a unit mass of fuel. It is derived as a heat balance and is usually reported as a single value in terms of the amount of energy per unit mass of material released (e.g., kJ/g).

Critical Ignition Flux (q_{cr}). Critical ignition flux is the minimum level of incident flux on the sample needed to ignite the sample, given an unlimited time of application. At incident flux levels less than the critical ignition flux, ignition does not take place.

Ignition Temperature (T_i). Ignition temperature is the surface temperature of a sample at which flame occurs. This is a sample material value that is independent of the incident flux. It is derivable from the calorimeter tests, the LIFT apparatus test, and other tests. It is derived from the time to ignite in a given test, the applied flux in that test, and the effective thermal inertia of the sample. It is reported at a single temperature.

If the test includes a pilot flame or spark, the reported temperature is for piloted ignition; if there is no pilot present, the temperature is for autoignition. Most available data are for piloted ignition.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.3(a) Maximum Heat Release Rates from Fire Detection Institute Analysis

Commodity	Approximate Values (Btu/sec)
Medium wastebasket with milk cartons	100
Large barrel with milk cartons	140
Upholstered chair with polyurethane foam	350
Latex foam mattress (heat at room door)	1200
Furnished living room (heat at open door)	4000–8000

For SI units, 1 Btu/sec = 1.055 W.

Table B.5.3(b) Characteristics of Ignition Sources (Babrauskas and Krasny [56])

Ignition Source	Typical Heat Output (W)	Burn Time[a] (sec)	Maximum Flame Height (mm)	Flame Width (mm)	Maximum Heat Flux (kW/m^2)
Cigarette 1.1 g (not puffed, laid on solid surface), bone dry					
Conditioned to 50%	5	1,200	—	—	42
Relative humidity	5	1,200	—	—	35
Methenamine pill, 0.15 g	45	90	—	—	4
Match, wooden (laid on solid surface)	80	20–30	30	14	18–20
Wood cribs, BS 5852 Part 2					
No. 4 crib, 8.5 g	1,000	190	—	—	15[d]
No. 5 crib, 17 g	1,900	200	—	—	17[d]
No. 6 crib, 60 g	2,600	190	—	—	20[d]
No. 7 crib, 126 g	6,400	350	—	—	25[d]
Crumpled brown lunch bag, 6 g	1,200	80	—	—	—
Crumpled wax paper, 4.5 g (tight)	1,800	25	—	—	—
Crumpled wax paper, 4.5 g (loose)	5,300	20	—	—	—
Folded double-sheet newspaper, 22 g (bottom ignition)	4,000	100	—	—	—
Crumpled double-sheet newspaper, 22 g (top ignition)	7,400	40	—	—	—
Crumpled double-sheet newspaper, 22 g (bottom ignition)	17,000	20	—	—	—
Polyethylene wastebasket, 285 g, filled with 12 milk cartons (390 g)	50,000	200[b]	550	200	35[c]
Plastic trash bags, filled with cellulosic trash (1.2–14 kg)[e]	120,000–350,000	200[b]	—	—	—

For U.S. units, 1 in. = 25.4 mm; 1 Btu/sec = 1.055 W; 1 oz = 0.02835 kg = 28.35 g; 1 Btu/ft^2-sec = 11.35 kW/m^2.

[a]Time duration of significant flaming.

[b]Total burn time in excess of 1800 seconds.

[c]As measured on simulation burner.

[d]Measured from 25 mm away.

[e]Results vary greatly with packing density.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.3(c) Characteristics of Typical Furnishings as Ignition Sources (Babrauskas and Krasny [56])

Furnishings	Total Mass (kg)	Total Heat Content (mJ)	Maximum Rate of Heat Release (kW)	Maximum Thermal Radiation to Center of Floor* (kW/m^2)
Wastepaper baskets	0.73–1.04	0.7–7.3	4–18	0.1
Curtains, velvet, cotton	1.9	24	160–240	1.3–3.4
Curtains, acrylic/cotton	1.4	15–16	130–150	0.9–1.2
TV sets	27–33	145–150	120–290	0.3–2.6
Chair mockup	1.36	21–22	63–66	0.4–0.5
Sofa mockup	2.8	42	130	0.9
Arm chair	26	18	160	1.2
Christmas trees, dry	6.5–7.4	11–41	500–650	3.4–14

For U.S. units, 1 lb = 0.4536 kg = 453.6 g; 1 Btu = 1.055×10^{-3} mJ; 1 Btu/sec = 1.055 kW; 1 Btu/ft^2 · sec = 11.35 kW/m^2.

*Measured at approximately 2 m away from the burning object.

Table B.5.3(d) Heat Release Rates of Chairs (Babrauskas and Krasny [56])

Specimen	kg	Mass Combustible (kg)	Style	Frame	Padding	Fabric	Interliner	Peak *m* (g/sec)	Peak *q* (kW)
C12	17.9	17.0	Traditional easy chair	Wood	Cotton	Nylon	—	19.0	290[a]
F22	31.9	—	Traditional easy chair	Wood	Cotton (FR)	Cotton	—	25.0	370
F23	31.2	—	Traditional easy chair	Wood	Cotton (FR)	Olefin	—	42.0	700
F27	29.0	—	Traditional easy chair	Wood	Mixed	Cotton	—	58.0	920
F28	29.2	—	Traditional easy chair	Wood	Mixed	Cotton	—	42.0	730
CO2	13.1	12.2	Traditional easy chair	Wood	Cotton, PU	Olefin	—	13.2	800[b]
CO3	13.6	12.7	Traditional easy chair	Wood	Cotton, PU	Cotton	—	17.5	460[a]
CO1	12.6	11.7	Traditional easy chair	Wood	Cotton, PU	Cotton	—	17.5	260[a]
CO4	12.2	11.3	Traditional easy chair	Wood	PU	Nylon	—	75.7	1350[b]
C16	19.1	18.2	Traditional easy chair	Wood	PU	Nylon	Neoprene	NA	180
F25	27.8	—	Traditional easy chair	Wood	PU	Olefin	—	80.0	1990
T66	23.0	—	Traditional easy chair	Wood	PU, polyester	Cotton	—	27.7	640
F21	28.3	—	Traditional easy chair	Wood	PU (FR)	Olefin	—	83.0	1970
F24	28.3	—	Traditional easy chair	Wood	PU (FR)	Cotton	—	46.0	700
C13	19.1	18.2	Traditional easy chair	Wood	PU	Nylon	Neoprene	15.0	230[a]
C14	21.8	20.9	Traditional easy chair	Wood	PU	Olefin	Neoprene	13.7	220[a]
C15	21.8	20.9	Traditional easy chair	Wood	PU	Olefin	Neoprene	13.1	210[b]
T49	15.7	—	Easy chair	Wood	PU	Cotton	—	14.3	210
F26	19.2	—	Thinner easy chair	Wood	PU (FR)	Olefin	—	61.0	810
F33	39.2	—	Traditional loveseat	Wood	Mixed	Cotton	—	75.0	940

(continues)

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.3(d) *(Continued)*

Specimen	kg	Mass Combustible (kg)	Style	Frame	Padding	Fabric	Interliner	Peak m (g/sec)	Peak q (kW)
F31	40.0	—	Traditional loveseat	Wood	PU (FR)	Olefin	—	130.0	2890
F32	51.5	—	Traditional sofa	Wood	PU (FR)	Olefin	—	145.0	3120
T57	54.6	—	Loveseat	Wood	PU, cotton	PVC	—	61.9	1100
T56	11.2	—	Office chair	Wood	Latex	PVC	—	3.1	80
CO9/T64	16.6	16.2	Foam block chair	Wood (part)	PU, polyester	PU	—	19.9	460
CO7/T48	11.4	11.2	Modern easy chair	PS foam	PU	PU	—	38.0	960
C10	12.1	8.6	Pedestal chair	Rigid PU foam	PU	PU	—	15.2	240[a]
C11	14.3	14.3	Foam block chair	—	PU	Nylon	—	NA	810[b]
F29	14.0	—	Traditional easy chair	PP foam	PU	Olefin	—	72.0	1950
F30	25.2	—	Traditional easy chair	Rigid PU foam	PU	Olefin	—	41.0	1060
CO8	16.3	15.4	Pedestal swivel chair	Molded PE	PU	PVC	—	112.0	830[b]
CO5	7.3	7.3	Bean bag chair	—	Polystyrene	PVC	—	22.2	370[a]
CO6	20.4	20.4	Frameless foam back chair	—	PU	Acrylic	—	151.0	2480[b]
T50	16.5	—	Waiting room chair	Metal	Cotton	PVC	—	NA	<10
T53	15.5	1.9	Waiting room chair	Metal	PU	PVC	—	13.1	270
T54	27.3	5.8	Metal frame loveseat	Metal	PU	PVC	—	19.9	370
T75/F20	7.5(×4)	2.6	Stacking chairs (4)	Metal	PU	PVC	—	7.2	160

For U.S. units, 1 lb/sec = 0.4536 kg/sec = 453.6 g/sec; 1 lb = 0.4536 kg; 1 Btu/sec = 1.055 kW.
[a]Estimated from mass loss records and assumed Wh_c.
[b]Estimated from doorway gas concentrations.

Table B.5.3(e) Effect of Fabric Type on Heat Release Rate in Table B.5.3(a) (Within Each Group All Other Construction Features Kept Constant) (Babrauskas and Krasny [56])

Specimen	Full-Scale Peak q (kW)	Padding	Fabric
	Group 1		
F24	700	Cotton (750 g/m^2)	FR PU foam
F21	1970	Polyolefin (560 g/m^2)	FR PU foam
	Group 2		
F22	370	Cotton (750 g/m^2)	Cotton batting
F23	700	Polyolefin (560 g/m^2)	Cotton batting
	Group 3		
28	760	None	FR PU foam
17	530	Cotton (650 g/m^2)	FR PU foam
21	900	Cotton (110 g/m^2)	FR PU foam
14	1020	Polyolefin (650 g/m^2)	FR PU foam
7, 19	1340	Polyolefin (360 g/m^2)	FR PU foam

For U.S. units, 1 lb/ft^2 = 48.83 g/m^2; 1 oz/ft^2 = 305 g/m^2; 1 Btu/sec = 1.055 kW.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.5.3(f) Effect of Padding Type on Maximum Heat Release Rate in Table B.5.3(d) (Within Each Group All Other Construction Features Kept Constant) (Babrauskas and Krasny [56])

Specimen	Full-Scale Peak q (kW)	Padding	Fabric
	Group 1		
F21	1970	FR PU foam	Polyolefin (560 g/m^2)
F23	1990	NFR PU foam	Polyolefin (560 g/m^2)
	Group 2		
F21	1970	FR PU foam	Polyolefin (560 g/m^2)
F23	700	Cotton batting	Polyolefin (560 g/m^2)
	Group 3		
F24	700	FR PU foam	Cotton (750 g/m^2)
F22	370	Cotton batting	Cotton (750 g/m^2)
	Group 4		
12, 27	1460	NFR PU foam	Polyolefin (360 g/m^2)
7, 19	1340	FR PU foam	Polyolefin (360 g/m^2)
15	120	Neoprene foam	Polyolefin (360 g/m^2)
	Group 5		
20	430	NFR PU foam	Cotton (650 g/m^2)
17	530	FR PU foam	Cotton (650 g/m^2)
22	0	Neoprene foam	Cotton (650 g/m^2)

For U.S. units, 1 lb/ft^2 = 48.83 g/m^2; 1 oz/ft^2 = 305 g/m^2; 1 Btu/sec = 1.055 kW.

Table B.5.3(g) Effect of Frame Material for Specimens with NFR PU Padding and Polyolefin Fabrics (Babrauskas and Krasny [56])

Specimen	Mass (kg)	Peak q (kW)	Frame
F25	27.8	1990	Wood
F30	25.2	1060	Polyurethane
F29	14.0	1950	Polypropylene

For U.S. units, 1 lb = 0.4536 kg; 1 Btu/sec = 1.055 kW.

B.6.3 Ignition. Equations for time to ignition, t_{ig}, are given for both thermally thin and thermally thick materials, as defined in B.6.3.1 and B.6.3.2. For materials of intermediate depth, estimates for t_{ig} necessitate considerations beyond the scope of this presentation (Quintiere [44]; Hirsch [58]).

Table B.5.3(h) Considerations for Selecting Heat Release Rates for Design

Constant Heat Release Rate Fires	Heat Release Rate
Theobald (industrial)	260 kW/m^2 (approx. 26 Btu/sec-ft^2)
Law [22] (offices)	290 kW/m^2 (approx. 29 Btu/sec-ft^2)
Hansell & Morgan [7] (hotel rooms)	249 kW/m^2 (approx. 25 Btu/sec-ft^2)
Variable Heat Release Rate Fires	
NBSIR 88-3695	**Fire Growth Rate**
Fuel Configuration	
Computer workstation	
Free burn	Slow to fast
Compartment	Very slow
Shelf storage	
Free burn	Medium up to 200 sec, fast after 200 sec
Office module	Very slow to medium
NISTIR 483	**Peak Heat**
Fuel commodity:	**Release Rate (kW)**
Computer workstation	1000–1300
NBS Monograph 173	
Fuel commodity:	
Chairs	80–2480 (<10, metal frame)
Loveseats	940–2890 (370, metal frame)
Sofa	3120

For U.S. units, 1 Btu/sec = 1.055 kW.

Table B.6.2(a) Relation of Calorimeter-Measured Properties to Fire Analysis

Property	Ignition	Flame Spread	Fire Size (Energy)
Rate of heat release*		X	X
Mass loss*			X
Time to ignition*	X	X	
Effective thermal properties†	X	X	
Heat of combustion†		X	X
Heat of gasification†			X
Critical ignition flux†	X	X	
Ignition temp.†	X	X	

*Property is a function of the externally applied incident flux.
†Derived properties from calorimeter measurements.

B.6.3.1 Thermally Thin Materials. Relative to ignition from a constant incident heat flux, q_i, at the exposed surface and with relatively small heat transfer losses at the unexposed surface, a thermally thin material is a material whose temperature is relatively uniform throughout its entire thickness, l, at $t = t_{ig}$. For example, at $t = t_{ig\alpha}$:

$$T_{unexposed}BT_o < 0.1\left(T_{exposed}BT_o\right) = 0.1\left(T_{ig}BT_o\right) \quad \textbf{(B.6.3.1a)}$$

Equation B.6.3.1a can be used to show that a material is thermally thin (Hirsch [58]) if:

$$1 < 0.6\left(t''_{ig}\right)^{1/2} \quad \textbf{(B.6.3.1b)}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table B.6.2(b) Average Maximum Heat Release Rates (kW/m^2)

Material	Orientation	2.2 Btu/sec/ft² (25 kW/m²) Exposing Flux	4.4 Btu/sec/ft² (50 kW/m²) Exposing Flux	6.6 Btu/sec/ft² (75 kW/m²) Exposing Flux
PMMA	Horizontal	57	79	114
	Vertical	49	63	114
Pine	Horizontal	12	21	23
	Vertical	11	15	56
Sample A	Horizontal	11	18	22
	Vertical	8	11	19
Sample B	Horizontal	12	15	21
	Vertical	5.3	18	29
Sample C	Horizontal	—	19	22
	Vertical	—	15	15
Sample D	Horizontal	6.2	13	13
	Vertical	—	11	11



FIGURE B.6.2 Typical Graphic Output of Cone Calorimeter Test.

For example, for sheets of maple or oak wood (where the thermal diffusivity = 1.28 × 10-7 m^2/sec; Sako and Hasemi [59]), if t_{ig} = 35 seconds is measured in a piloted ignition test, then, according to Equation B.6.3.1b, if the sample thickness is less than approximately 0.0013 m, the unexposed surface of the sample can be expected to be relatively close to T_{ig} at the time of ignition, and the sample is considered to be thermally thin.

The time to ignition of a thermally thin material subjected to incident flux above a critical incident flux is as follows:

$$t_{ig} = \rho c l \frac{\left(T_{ig} - T_o\right)}{\dot{q}_i''} \qquad \textbf{(B.6.3.1c)}$$

B.6.3.2 Thermally Thick Materials. Relative to the type of ignition test described in B.6.3.1, a sample of a material of a thickness, l, is considered to be thermally thick if the increase in temperature of the unexposed surface is relatively small compared to that of the exposed surface at $t = t_{ig}$. For example, at $t = t_{ig}$:

$$t_{ig} = \rho c l \frac{\left(T_{ig} - T_o\right)}{\dot{q}_i''} \qquad \textbf{(B.6.3.2a)}$$

Equation B.6.3.2a can be used to show that a material is thermally thick (Carslaw and Jaeger [60]) if

$$T_{unexposed} BT_o < 0.1\left(T_{exposed} BT_o\right) = 0.1\left(T_{ig} BT_o\right) \qquad \textbf{(B.6.3.2b)}$$

For example, according to Equation B.6.3.2b, in the case of an ignition test on a sheet of maple or oak wood, if t_{ig} = 35 seconds is measured in a piloted ignition test, then, if the sample thickness is greater than approximately 0.0042 m, the unexposed surface of the sample can be expected to be relatively close to T_o at $t = t_{ig}$ and the sample is considered to be thermally thick.

Time to ignition of a thermally thick material subjected to incident flux above a critical incident flux is as follows:

$$l > 2\left(t_{ig} 10\right)^{1/2} \qquad \textbf{(B.6.3.2c)}$$

It should be noted that a particular material is not intrinsically thermally thin or thick (i.e., the characteristic of being thermally thin or thick is not a material characteristic or property) but also depends on the thickness of the particular sample (i.e., a particular material can be implemented in either a thermally thick or thermally thin configuration).

B.6.3.3 Propagation Between Separate Fuel Packages. Where the concern is for propagation between individual separated fuel packages, incident flux can be calculated using traditional radiation heat transfer procedures (Tien, Lee, and Stretton [61]).

The rate of radiation heat transfer from a flaming fuel package of total energy release rate, Q, to a facing surface element of an exposed fuel package can be estimated from the following:

$$q''_{inc} = \frac{X_r Q}{4\pi r^2} \qquad \textbf{(B.6.3.3)}$$

where:
q''_{inc} = incident flux on exposed fuel
X_r = radiant fraction of exposing fire
Q = rate of heat release of exposing fire
r = radial distance from center of exposing fire to exposed fuel

B.6.4 Estimating Rate of Heat Release. As discussed in B.6.2, tests have demonstrated that the energy feedback from a burning fuel package ranges from approximately 25 kW/m^2 to 50 kW/m^2. For a reasonable conservative analysis, it is recommended that test data developed with an incident flux of 50 kW/m^2 be used. For a first-order approximation, it should be assumed that all the surfaces that can be simultaneously involved in burning are releasing energy at a rate equal to that determined by testing the material in a fire properties calorimeter with an incident flux of 50 kW/m^2 for a free-burning material and 75 kW/m^2 to 100 kW/m^2 for post-flashover conditions.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

In making this estimate, it is necessary to assume that all surfaces that can "see" an exposing flame (or superheated gas, in the post-flashover condition) are burning and releasing energy and mass at the tested rate. If sufficient air is present, the rate of heat release estimate is then calculated as the product of the exposed area and the rate of heat release per unit area as determined in the test calorimeter. Where there are test data taken at the incident flux of the exposing flame, the tested rate of heat release should be used. Where the test data are for a different incident flux, the burning rate should be estimated using the heat of gasification as expressed in Equation B.6.4a to calculate the mass burning rate per unit area:

$$\dot{m}'' = \frac{\dot{q}_i''}{h_c} \qquad \textbf{(B.6.4a)}$$

The resulting mass loss rate is then multiplied by the derived effective heat of combustion and the burning area exposed to the incident flux to produce the estimated rate of heat release as follows:

$$\dot{Q}_i'' = \dot{m}'' h_c A \qquad \textbf{(B.6.4b)}$$

B.6.5 Flame Spread. If it is desired to predict the growth of fire as it propagates over combustible surfaces, it is necessary to estimate flame spread. The computation of flame spread rates is an emerging technology still in an embryonic stage. Predictions should be considered as order-of-magnitude estimates.

Flame spread is the movement of the flame front across the surface of a material that is burning (or exposed to an ignition flame) where the exposed surface is not yet fully involved.

Physically, flame spread can be treated as a succession of ignitions resulting from the heat energy produced by the burning portion of a material, its flame, and any other incident heat energy imposed upon the unburned surface. Other sources of incident energy include another burning object, high temperature gases that can accumulate in the upper portion of an enclosed space, and the radiant heat sources used in a test apparatus such as the cone calorimeter or the LIFT mechanism. For analysis purposes, flame spread can be divided into two categories: that which moves in the same direction as the flame (concurrent or wind-aided flame spread) and that which moves in any other direction (lateral or opposed flame spread). Concurrent flame spread is assisted by the incident heat flux from the flame to unignited portions of the burning material. Lateral flame spread is not so assisted and tends to be much slower in progression unless an external source of heat flux is present. Concurrent flame spread can be expressed as follows:

$$V = \frac{\dot{q}_i'' L}{k\rho c\left(T_{ig} - T_s\right)^2} \qquad \textbf{(B.6.5)}$$

The values for $k\rho c$ and ignition temperature are calculated from the cone calorimeter as previously discussed. For this equation, the flame length (L) is measured from the leading edge of the burning region.

B.7 *t*-Squared Fires.

B.7.1 Over the past decade, persons interested in developing generic descriptions of the rate of heat release of accidental open flaming fires have used a "*t*-squared" approximation for this purpose. A *t*-squared fire is one in which the burning rate varies proportionally to the square of time. Frequently, *t*-squared fires are classed by speed of growth, labeled fast, medium, and slow (and occasionally ultra-fast). Where these classes are used, they are defined on the basis of the time required for the fire to grow to a rate of heat release of 1000 Btu/sec. The times related to each of these classes are as shown in Table B.7.1.

Table B.7.1 Time for the Fire Growth Rate to Reach 1000 Btu/sec

Class	Time (sec)
Ultra-fast	75
Fast	150
Medium	300
Slow	600

The general equation is as follows:

$$q = at^2$$

where:
q = rate of heat release (normally in Btu/sec or kW)
a = constant governing the speed of growth
t = time (normally in sec)

B.7.2 Relevance of *t*-Squared Approximation to Real Fires. A *t*-squared fire can be viewed as one in which the rate of heat release per unit area is constant over the entire ignited surface and the fire is spreading as a circle with a steadily increasing radius. In such cases, the burning area increases as the square of the steadily increasing fire radius. Of course, other fires that do not have such a conveniently regular fuel array and consistent burning rate might or might not actually produce a *t*-squared curve. The tacit assumption is that the *t*-squared approximation is close enough for reasonable design decisions.

Figure B.7.2(a) is extracted from NFPA 204, *Standard for Smoke and Heat Venting*. It is presented to demonstrate that most fires have an incubation period in which the fire does not conform to



FIGURE B.7.2(a) Conceptual Illustration of Continuous Fire Growth. [204:Figure 8.3.1]

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

a *t*-squared approximation. In some cases this incubation period can be a serious detriment to the use of the *t*-squared approximation. In most instances, this is not a serious concern in atria and other large spaces covered by this standard. It is expected that the rate of heat release during the incubation period usually would not be sufficient to cause activation of the smoke detection system. In any case, where such activation happens or human observation results in earlier activation of the smoke management system, a fortuitous safeguard would result.

Figure B.7.2(b), extracted from Nelson [62], compares rate of heat release curves developed by the aforementioned classes of *t*-squared fires and two test fires commonly used for test purposes. The test fires are shown as dashed lines labeled "Furniture" and "6 ft storage." The dashed curves farther from the origin show the actual rates of heat release of the test fires used in the development of the residential sprinkler and a standard 6 ft high array of test cartons containing foam plastic pails also frequently used as a standard test fire.

The other set of dashed lines in Figure B.7.2(b) shows these same fire curves relocated to the origin of the graph. This is a more appropriate comparison with the generic curves. As can be seen, the rate of growth in these fires is actually faster than that prescribed for an ultra-fast fire. Such is appropriate for a test fire designed to challenge the fire suppression system being tested.

Figure B.7.2(c) relates the classes of *t*-squared fire growth curves to a selection of actual fuel arrays from NFPA 204. The individual arrays are also described in Annex B.



FIGURE B.7.2(b) Rates of Energy Release in a *t*-Squared Fire. (Source: Nelson [62])



Note: For SI units, 1 ft = 0.3048 m; 1 Btu/sec = 1055 J/sec.

FIGURE B.7.2(c) Relation of *t*-Squared Fire to Some Fire Tests.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Annex C Computer-Based Models for Atria and Malls

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

C.1 Zone Fire Models

C.1.1 Overview. Smoke produced from a fire in a large, open space is assumed to be buoyant, rising in a plume above the fire and striking the ceiling or stratifying due to temperature inversion. After the smoke either strikes the ceiling or stratifies, the space can be expected to begin to fill with smoke, with the smoke layer interface descending. The descent rate of the smoke layer interface depends on the rate at which smoke is supplied to the smoke layer from the plume. Such smoke filling is represented by a two-zone model in which there is a the ambient air. For engineering purposes, the smoke supply rate from the plume can be estimated to be the air entrainment rate into the plume below the smoke layer interface.

Sprinklers can reduce the heat release rate and the air entrainment rate into the plume.

As a result of the zone model approach, the model assumes uniform properties (smoke concentration and temperature) from the point of interface through the ceiling and horizontally throughout the entire smoke layer.

For general information about fire plumes and ceiling jets, see Beyler [2].

C.1.2 Simplifications of Zone Fire Models. Zone models are simple models and can usually be run on personal computers. Zone models divide the space into two zones, an upper zone, which contains the smoke and hot gases produced by the fire, and a lower zone, which is the source of entrainment air. The sizes of the two zones vary during the course of a fire, depending on the rate of flow from the lower to the upper zone, the rate of exhaust of the upper zone, and the temperature of the smoke and gases in the upper zone. Because of the small number of zones, zone models use engineering equations for heat and mass transfer to evaluate the transfer of mass and energy from the lower zone to the upper zone, the heat and mass losses from the upper zone, and other features. Generally, the equations assume that conditions are uniform in each zone.

In zone models, the source of the flow into the upper zone is the fire plume. All zone models have a plume equation. A few models allow the user to select among several plume equations.

Most current zone models are based on an axisymmetric plume.

Because zone models assume that there is no pre-existing temperature variation in the space, they cannot directly handle stratification. Zone models also assume that the ceiling smoke layer forms instantly and evenly from wall to wall, which fails to account for the initial lateral flow of smoke across the ceiling. The resulting error can be significant in spaces having large ceiling areas. Zone models can, however, calculate many important factors in the course of events (e.g., smoke level, temperature, composition, and rate of descent) from any fire that the user can describe. Most zone models will calculate the extent of heat loss to the space boundaries. Several models calculate the impact of vents or mechanical exhaust, and some predict the response of heat- or smoke-actuated detection systems.

Common simplifications of zone models are listed as follows:

(1) Fuel
   (a) Heat release rate is not accelerated by heat feedback from smoke layer.
   (b) Post-flashover heat release rate is weakly understood, and its unique simulation is attempted by only a few models.
   (c) CO production is simulated, but its mechanism is not fully understood through the flashover transition.
   (d) Some models do not consider burning of excess pyrolyzate on exit from a vent.

(2) Plumes
   (a) Plume mass entrainment is ±20 percent and not well verified in tall compartments.
   (b) There is no transport time from the fire elevation to the position of interest in the plume and ceiling jet.
   (c) Spill plume models are not well developed.
   (d) Not all plume models consider the fuel area geometry.
   (e) Entrainment along stairwells is not simulated.
   (f) Entrainment from horizontal vents is not simulated by all models.

(3) Layers
   (a) Hot stagnation layers at the ceiling are not simulated.
   (b) There is uniformity in temperature.

(4) Heat transfer
   (a) Some models do not distinguish between thermally thin and thermally thick walls.
   (b) There is no heat transfer via barriers from room to room.
   (c) Momentum effects are neglected.

(5) Ventilation: Mixing at vents is correlationally determined.

C.1.3 Nonuniform Spaces.

C.1.3.1 Sensitivity Analysis. In the absence of an analysis using scale models, field models, or zone model adaptation, a sensitivity analysis should be considered. A sensitivity analysis can provide important information to assist in engineering judgments regarding the use of Equations 5.4.2.1 and 5.4.2.2 for complex and nonuniform geometries. An example of a sensitivity analysis for a large space having a nonflat ceiling geometry follows.

The first step of the analysis would be to convert a nonuniform geometry to a similar or volume-equivalent uniform geometry.

In the case of the geometry shown in Figure C.1.3.1(a), this would be done as follows:

(1) Convert the actual nonrectangular vertical cross-sectional area to a rectangular vertical cross section of equal area.
(2) The height dimension corresponding to the equivalent rectangular cross section would then be used as a substitute height factor H_{sub} in Equation 5.4.2.2.

Results of Equation 5.4.2.2 should be compared with other minimum and maximum conditions as indicated by Figure C.1.3.1(b).

An appropriate method of comparison could be a graph of Equation 5.4.2.2 as shown in Figure C.1.3.1(c). Assume that the building in question can be evacuated in 3 minutes and that the design criteria require the smoke layer to remain available 10 ft above the floor at this time. A review of the curves would indicate that the smoke layer heights as calculated for the substitute case are appropriate. This conclusion can be drawn by noting that neither the extreme minimum height case (H = 30 ft, W = 60 ft) nor the maximum height case (H = 60 ft) offers an expected answer, but the results for two cases (H = 41.6 ft, W = 60 ft; and H = 30 ft, W = 83.3 ft) can be judged to reasonably approximate the behavior of the nonuniform space. It might otherwise be unreasonable to expect the behavior indicated by the maximum or minimum cases.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.





$A = W \times H$
$700 = 60 \times H$
$H = 11.66$
$H_{sub} = 30 + 11.66 = 41.7$

Note: For SI units, 1 ft = 0.3048 m; 1 ft² = 0.0929 m².

FIGURE C.1.3.1(a) Large Space with Nonflat Ceiling.



Note: For SI units, 1 ft = 0.3048 m.

FIGURE C.1.3.1(b) Other Nonuniform Geometry Considerations.



Note: For SI units, 1 ft = 0.3048 m.

FIGURE C.1.3.1(c) Comparison Data for Guidance on Nonrectangular Geometries — Growing Fire.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

C.1.3.2 Zone Model Adaptation. A zone model predicated on smoke filling a uniform cross-sectional geometry is modified to recognize the changing cross-sectional areas of a space. The entrainment source can be modified to account for expected increases or decreases in entrainment due to geometric considerations, such as projections.

C.1.3.3 Bounding Analysis. An irregular space is evaluated using maximum height and minimum height identifiable from the geometry of the space using equivalent height or volume considerations.

C.1.4 Zone Fire Model Using Algebraic Equations. A computer model (written in a programming language or using a spreadsheet) can be constructed using the algebraic equations contained in Chapter 5 to calculate the position of a smoke layer interface over time, with and without smoke exhaust. This approach involves the calculation of the mass flow rate of smoke entering the smoke layer, the temperature of the smoke entering the layer, and the mass flow rate of smoke removed from the smoke layer by mechanical or gravity venting. The steps to calculate the position of the smoke layer interface are as follows:

(1) Select the time interval for the calculation, Δt. *(See Table C.1.4.)*
(2) Determine the design fire (e.g., steady fire, growing fire, growing fire with steady maximum, or other description of heat release rate as a function of time). *(See Section 5.2 for a discussion of design fires.)*

Table C.1.4 The Effect of Time Interval on the Accuracy of Smoke Filling Simulations

Atrium Height, *H*		Cross-Sectional Area, *A*			Steady Fire[a]		Fast *t*-Squared Fire[b]	
ft	m	ft^2	m^2	Time Interval, Δt (s)	Simulation Time (sec)	Error[c] (%)	Simulation Time (sec)	Error[c] (%)
				Small Atrium				
30	9.14	1,000	93	0.005	30	0.0	90	0.0
				0.01	30	0.0	90	0.0
				0.05	30	0.2	90	0.1
				0.20	30	1.2	90	0.2
				0.50	30	3.7	90	0.6
				1.00	30	7.7	90	1.2
				5.00	30	65.0	90	6.1
				Small Spread-Out Atrium				
30	9.14	12,000	1,110	0.01	240	0.0	300	0.0
				0.05	240	0.0	300	0.0
				0.20	240	0.1	300	0.1
				0.50	240	0.1	300	0.1
				1.00	240	0.3	300	0.3
				5.00	240	1.5	300	1.5
				20.00	240	6.3	300	6.4
				Large Atrium				
150	45.7	25,000	2,320	0.01	480	0.0	300	0.0
				0.05	480	0.0	300	0.0
				0.20	480	0.0	300	0.1
				0.50	480	0.1	300	0.1
				1.00	480	0.3	300	0.3
				5.00	480	1.4	300	1.4
				20.00	480	6.0	300	5.8
				Large Spread-Out Atrium				
150	44.7	300,000	27,900	0.01	1200	0.0	600	0.0
				0.05	1200	0.0	600	0.0
				0.20	1200	0.0	600	0.0
				0.50	1200	0.0	600	0.0
				1.00	1200	0.0	600	0.0
				5.00	1200	0.1	600	0.2
				20.00	1200	0.2	600	0.7

Note: Calculations were done with AZONE with the following conditions: (1) ambient temperature of 70°F (21°C); (2) constant cross-sectional area; (3) no smoke exhaust; (4) top of fuel at floor level; (5) wall heat transfer fraction of 0.3.

[a]The steady fire was 5000 Btu/sec (5275 kW).

[b]For the *t*-squared fire, the growth time was 150 sec.

[c]The error, δ, is the error of the smoke layer height, z, using the equation $\delta = 100(z_m - z)/z$, where z_m is the value of z at the smallest time interval listed in the table for that atrium size.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

(3) For an unsteady fire, calculate or specify the heat release rate, Q, of the design fire at the midpoint of the current time interval. Calculate the convective portion of the heat release rate, Q_c, at the midpoint of the current time interval.

(4) Calculate the mass flow rate of smoke entering the smoke layer during the current time interval. For an axisymmetric plume, the plume mass flow rate should be calculated using either Equation 5.5.1.1b or 5.5.1.1c, depending on the position of the smoke layer at the end of the previous time interval relative to the flame height of the design fire. For a balcony spill plume, the plume mass flow rate should be calculated using Equation 5.5.2.1. For a window plume, the plume mass flow rate should be calculated using Equation 5.5.3.2.

(5) Calculate the temperature of the smoke entering the smoke layer using Equation 5.5.5.

(6) Calculate the mass of smoke in the smoke layer at the end of this time interval as follows:

$$M_2 = M_1 + \left(m_p - m_e\right)\Delta t \qquad \textbf{(C.1.4a)}$$

where:

M_2 = mass of smoke in the smoke layer at the end of current time interval (kg)
M_1 = mass of smoke in the smoke layer at the start of current time interval (kg)
m_p = mass flow rate of plume (kg/sec)
m_e = mass flow rate of exhaust (kg/sec)
Δt = time interval (sec)

When there is more than one exhaust point from the smoke layer, the mass flow rate of exhaust, m_e, is the total of the flows from all the exhaust points.

(7) Calculate the energy of the smoke layer as follows:

$$E_2 = E_1 + C_p\left[m_p T_p - m_e T_{s,1} - \eta m_p\left(T_p - T_o\right)\right]\Delta t \qquad \textbf{(C.1.4b)}$$

where:

E_2 = energy of the smoke layer at the end of the time interval (kJ)
E_1 = energy of the smoke layer at the beginning of the time interval (kJ)
C_p = specific heat of the smoke (kJ/kg-K)
T_p = absolute temperature of plume (K)
$T_{s,1}$ = absolute temperature of the smoke layer at the start of current time interval (K)
η = heat loss factor (dimensionless)
T_o = absolute ambient temperature (K)

The heat loss factor is the fraction of the convective heat release rate that is transferred from the smoke layer to the ceiling and walls, and it has a maximum value of 1.0. The maximum temperature rise occurs where the heat loss factor is zero.

(8) Calculate the new temperature of the smoke layer as follows:

$$T_{s,2} = \frac{E_2}{C_p M_2} \qquad \textbf{(C.1.4c)}$$

where:

$T_{s,2}$ = the absolute temperature of the smoke layer at the end of current time interval (K)

(9) Calculate the density of the smoke layer:

$$\rho_s = \frac{P_o}{RT_{s,2}} \qquad \textbf{(C.1.4d)}$$

where:

ρ_s = density of the smoke layer at the end of the time interval (kg/m^3)
P_o = ambient pressure (Pa)
R = gas constant of smoke layer (287 J/kg-K)

(10) Calculate the volume of the smoke layer as follows:

$$V_2 = \frac{M_2}{\rho_s} \qquad \textbf{(C.1.4e)}$$

where:

V_2 = the volume of the smoke layer at the end of the time interval (m^3)

(11) Determine the new smoke layer interface position as a function of the upper layer volume and the geometry of the smoke reservoir. For constant cross-sectional areas, the smoke layer position is calculated as follows:

$$z_2 = H_{ceiling} - \frac{V_2}{A_{reservoir}} \qquad \textbf{(C.1.4f)}$$

where:

z_2 = smoke layer interface height above floor at the end of the time interval (m)
$H_{ceiling}$ = ceiling height above floor (m)
$A_{reservoir}$ = area of reservoir (m^2)

(12) Stop calculations if the maximum number of time intervals has been reached or if the smoke layer interface is at or below the top of the fuel.

(13) Return to interval (3) and use the newly calculated values for the calculations of the next time interval.

The Fortran computer program AZONE, provided with the smoke management book by Klote and Milke [21], is an example of the preceding routine. However, AZONE has a number of features not included in the routine. AZONE is capable of dealing with large spaces of variable cross-sectional area. It can also simulate the effect of plugholing on the exhaust flow rate.

C.2 Computational Fluid Dynamic (CFD) Models.

C.2.1 Overview. CFD models, also referred to as field models, usually require large-capacity computer workstations or mainframe computers and advanced expertise to operate and interpret.

CFD models, however, can potentially overcome the limitations of zone models and complement or supplant scale models. As with zone models, CFD models solve the fundamental conservation equations. In CFD models, the space is divided into many cells, and the governing equations are used to solve the movement of heat and mass between the cells. The governing equations include the equations of conservation of mass, momentum, and energy. These partial differential equations can be solved numerically by algorithms specifically developed for that purpose. For smoke management applications, the number of cells is generally in the range of tens of thousands to millions.

Because of the very large number of cells, CFD models avoid the more generalized engineering equations used in zone models. Through the use of small cells, CFD models can examine the

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

situation in much greater detail and account for the impact of irregular shapes and unusual air movements that cannot be addressed by either zone models or algebraic equations. The level of refinement exceeds that which can usually be observed or derived from scale models.

The conservation equations are generally expressed in either vector notation or tensor notation. For information about these mathematical forms of notation, see Borisenko and Tarapov [63] and Hay [64]. Information about the governing equations is provided in many fluid dynamics texts (Welty, Wicks, and Wilson [65]; Schetz [66]; Schlichting [67]; Sherman [68]). For a detailed derivation of the governing equations, see Aris [69]. For a general overview of CFD modeling, see Klote [22]. For more detailed information about CFD modeling, see Anderson, Tannehill, and Pletcher [70]; Abbott and Basco [71]; Hoffmann [72]; Markatos [73]; Hirsch [58, 74]; and Kumar [75].

C.2.2 General and Specific Application Models. Many computer CFD programs have been developed that are capable of simulation of fire-induced flows. Friedman [78] discusses 10 such codes. Several of these are general purpose codes that are commercially available. Some commercially available codes require that the user do computer programming in order to simulate fire-induced smoke transport.

The Fire Dynamics Simulator (FDS) model (McGrattan, et al. [76]; McGrattan and Forney [77]) was developed specifically for fire applications. FDS can be considered the product of decades of basic research in CFD modeling of fire and smoke transport conducted at the National Institute of Standards and Technology (NIST) in Gaithersburg, Maryland. FDS is in the public domain, and it can be obtained from NIST at no cost.

C.2.3 Simplifications of CFD Models. The items the modeler must accurately characterize are the fuel, the compartment, and the ambient conditions, as follows:

(1) Burning fuel description:
   (a) Heat release rate as it changes with time
   (b) Fire elevation
   (c) Radiation fraction
   (d) Species production rate
   (e) Area of fire (line, pool, or gaseous)
(2) Compartment description:
   (a) Height of ceiling
   (b) Size, location, and dynamic status (open or closed) of the vent (including leakage area)
   (c) Thermophysical properties of wall, ceiling, and floor material
   (d) Location, capacity, and status of mechanical ventilation
   (e) Presence of beams or trusses
   (f) Smoke transport time in the plume or ceiling jet
   (g) Structural failure
   (h) Initial temperature
(3) Ambient conditions description:
   (a) Elevation
   (b) Ambient pressure
   (c) Ambient temperature
   (d) Wind speed and direction
   (e) Relative humidity
   (f) Outside temperature

The fuel heat release rate is an important feature to describe. Many other details of the fuel also affect fire growth, such as species production, radiative heat loss fraction, fuel-to-air combustion ratio, and heat of combustion. However, the desired accuracy of these calculation results dictate which should be included and which can be ignored.

Compartment vent descriptions also must be properly evaluated. Often, leakage areas can account for substantial, unanticipated gas flows, especially in instances of extreme weather conditions with regard to temperature or wind.

Translating actual characteristics into a format recognizable as model input is the second major area of fire modeling. Some items simply do not merit attention because of their lower-order effects. Other items must be represented in ways that are altered somewhat. An example of the first case is excluding a mechanical ventilation duct when a large door to a room remains open. An example of the second case is a 5 ft vertical section of wall. The height of the fire is best described as the floor level, the lowest point where flames can entrain air.

The last area of understanding is perhaps the most difficult for the novice to master: understanding how the model converts input to output. It is not practical for the new user to grasp every detail of this transformation process, but it is possible for the novice to anticipate many results with a basic comprehension of fire dynamics (DiNenno [79]; Drysdale [80]) and working knowledge of the conservation equations. The conservation laws can be expressed with differential equations to reproduce the smooth, continuous changes exhibited by properties behaving in real fires. To the degree that the mathematics deviates from the differential representation of the conservation laws, the more uncertain the model accuracy becomes outside the range of verification. The potential for model inaccuracy is affected by the relative influence of the particular term in the equation. Terms having the greatest influence contain variables that are raised to exponential powers greater than 1.

Algebraic correlations, other fire models, scale models, and common sense can be used to verify model accuracy. The algebraic equations are only verified given the experimental conditions from which they were correlated. Projections beyond these experimental domains can be based on trends at the experimental endpoints. Using one model to verify another model ensures precision but not necessarily accuracy, unless the second model has been independently verified.

Annex D Additional Design Objectives

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

D.1 In addition to the design objectives listed in Section 1.2, smoke management systems can be used for the following objectives:

(1) Allowing fire department personnel sufficient visibility to approach, locate, and extinguish a fire
(2) Limiting the rise of the smoke layer temperature and toxic gas concentration and limiting the reduction of visibility

D.1.1 Egress Analysis. Timed egress analysis is outside the scope of this document. However, other references are available that present analytical methods for use in egress analysis (Klote and Milke [21]; Nelson and Mowrer [81]).

D.1.2 Tenability. Factors that should be considered in a tenability analysis include the following:

(1) Heat exposure
(2) Smoke toxicity
(3) Visibility

Other references are available that present analytical methods for tenability analyses (Purser [42]).

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

D.1.3 Equations to calculate the smoke layer depth, average temperature rise, optical density, and species concentrations during the smoke-filling stage and the quasi-steady vented stage are provided in Table D.1.3. These equations apply to fires with constant heat release rates and *t*-squared fires. These equations can also be used to calculate the conditions within the smoke layer once the vented conditions exist.

For design purposes, the topic of algebraic equations for gas concentrations and obscuration of visibility can be addressed for two limit cases:

(1) The smoke-filling scenario, where all products of combustion are assumed to accumulate in the descending smoke layer.
(2) The quasi-steady vented scenario, where a quasi-steady balance exists between the rates of inflow into and outflow from the smoke layer. Normally, the quasi-steady vented scenario is of interest for design purposes because this scenario represents the quasi-steady conditions that develop with a smoke extraction system operating. The smoke-filling scenario might be of interest to analyze the conditions that can develop before the smoke extraction system is actuated. A transient period exists between these two limit cases. During this transient intermediate period, the smoke layer is both filling and being exhausted.

Analysis of this transient period generally requires numerical computer-based approaches. From a design standpoint, this period should be of little consequence since it is not a limit case, so it is not addressed further.

Methods to analyze the gas composition and optical characteristics for the two limit cases can be addressed in terms of a number of algebraic equations. These algebraic equations are exact, but the data used in these equations are uncertain (Milke and Mowrer [82]). The user should be made aware of these uncertainties to the extent they are known.

D.2 Smoke-Filling Stage — Optical Properties Analysis. The average optical density (D) of the descending smoke layer can be estimated if the mass optical density of the fuel can be reasonably estimated. Equation D.2a is used to estimate the optical density as a function of the mass optical density, the mass of fuel consumed, and the volume of the smoke layer.

$$D = \frac{D_m m_f}{V_u} = \frac{D_m \int_0^t \dot{m}_f dt}{A z_u(t)} \qquad \textbf{(D.2a)}$$

where:
D_m = mass optical density [ft^2/lb (m^2/kg)]
m_f = total fuel mass consumed [lb (kg)]
$\dot{m}_f$ = burning rate of fuel [lb/sec (kg/sec)]
t = time
V_u = volume of upper layer [ft^3 (m^3)]
A = horizontal cross-sectional area of atrium [ft^2 (m^2)]
z_u = depth of upper layer [ft (m)]

Table D.1.3 Equations for Calculating Properties of Smoke Layer

Parameters	Unvented Fires: Steady Fires	Unvented Fires: *t*-Squared Fires	Vented Fires
ΔT	$T_o\{[\exp(Q_n/Q_o)] - 1\}$	$T_o\{[\exp(Q_n/Q_o)] - 1\}$	$[60(1-\chi_l)Q_c]/(\rho_o c_p V)$
D	$(D_m Q t)/[\chi_a \Delta H_c A(H-z)]$	$(D_m \alpha t^3)/[3\chi_a \Delta H_c A(H-z)]$	$(60 D_m Q)/(\chi_a \Delta H_c V)$
Y_i	$(f_i Q t)/[\rho_o \chi_a \Delta H_c A(H-z)]$	$(f_i \alpha t^3)/[3\rho_o \chi_a \Delta H_c A(H-z)]$	$(60 f_i Q)/(\rho_o \chi_a \Delta H_c V)$

where:
A = horizontal cross-sectional area of space (ft^2)
c_p = specific heat of ambient air (Btu/lb · °F)
$D = L^{-1} \log(I_o/I)$, optical density
D_m = mass optical density (ft^2/lb) measured in a test stream containing all the smoke from a material test sample
f_i = yield factor of species i (lb species i/lb fuel)
H = ceiling height (ft)
ΔH_c = heat of complete combustion (Btu/lb)
Q = heat release rate of fire (Btu/sec)
Q_c = convective portion of heat release rate (Btu/sec)
$Q_n = \zeta(1-\chi_l)\,Qdt$; for steady fires, $Q_n = (1-\chi_l)\,Qt$ (Btu); for *t*-squared fires, $Q_n = (1-\chi_l)\,\alpha t^3/3$ (Btu)
$Q_o = \rho_o c_p T_o A\,(H-z)$ (Btu)
t = time from ignition (sec)
T_o = absolute ambient temperature (R)
ΔT = temperature rise in smoke layer (°F)
V = volumetric venting rate (ft^3/min)
Y_i = mass fraction of species i (lb species i/lb of smoke)
z = height from top of fuel to smoke layer interface (ft)
α = *t*-squared fire growth coefficient (Btu/sec^3)
ρ_o = density of ambient air (lb/ft^3)
χ_a = combustion efficiency factor, maximum value of 1 (Hirsch [58])
χ_l = total heat loss factor from smoke layer to atrium boundaries, maximum value of 1; maximum temperature rise will occur if $\chi_l = 0$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

For the case of a flat ceiling, negligible plume area, and a fire with constant mass and heat release rates, Equation D.2a evaluates as follows:

$$D = \frac{D_m Q t}{\chi_a \Delta H_c A_u H}\left[1-\left(1+\frac{2t}{3\tau}\right)^{-3/2}\right]^{-1} \quad \textbf{(D.2b)}$$

$$\tau = \frac{V}{V_{ent}} = \frac{AH}{k_v Q^{1/3} H^{5/3}} = \frac{AH}{k_v\left(\alpha_n t^n\right)^{1/3} H^{5/3}} \quad \textbf{(D.2c)}$$

where:

Q = heat release rate from fire [Btu/sec (kW)]
χ_a = combustion efficiency
ΔH_c = heat of combustion [Btu/lb (kJ/kg)]
A_u = cross-sectional area of the smoke layer
H = height of ceiling above floor [ft (m)]
V = volume of atrium [ft^3 (m^3)]
V_{ent} = volumetric rate of air entrainment [ft^3/sec (m^3/sec)]
k_v = volumetric entrainment constant [0.32 ft$^{4/3}$/Btu$^{1/2}$sec$^{2/3}$ (0.064 m$^{4/3}$/kW$^{1/3}$sec)]
α = fire growth rate $1000/(t_g)^2$ (sec)

For the case of a flat ceiling, negligible plume area, and a *t*-squared fire, Equation D.2a evaluates as follows:

$$D = \frac{D_m \alpha t^3}{3\chi_a \Delta H_c A H}\left[1-\left(1+\frac{2k_v \alpha^{1/3} t^{5/3} H^{2/3}}{5A}\right)^{-3/2}\right]^{-1} \quad \textbf{(D.2d)}$$

where:

α = fire growth rate = $1000/(t_g)^2$ (sec)

For other scenarios, appropriate values must be substituted into Equation D.2a. For some scenarios, numerical integration might be necessary.

D.3 Smoke-Filling Stage — Layer Composition Analysis. Analysis of the composition of the smoke layer is analogous in many respects to the analysis of the optical density of the layer. To analyze the smoke layer composition as a function of time, a yield factor, f_i, must first be assigned for each species i of interest, as follows:

$$\dot{m}_i = f_i \dot{m}_f \quad \textbf{(D.3a)}$$

where:

f_i = yield factor (lb)

The mass fraction, Y_i, of each species in the smoke layer is as follows:

$$Y_i = \frac{m_i}{\sum_i m_i} \quad \textbf{(D.3b)}$$

where:

Y_i = mass fraction (lb)

The term in the numerator of Equation D.3b is calculated, similar to Equation D.2a, as follows:

$$m_i = \int_0^t \dot{m}_i \, dt = \int_0^t f_i \dot{m}_f \, dt = \int_0^t f_i \frac{Q}{\chi_a \Delta H_c} dt \quad \textbf{(D.3c)}$$

For the case of a constant yield factor and a *t*-squared fire growth rate, Equation D.3c evaluates as follows:

$$\dot{m}_i = f_i \int_0^t \frac{\alpha t^2}{\chi_a \Delta H_c} \, dt = \frac{f_i \alpha t^3}{3\chi_a \Delta H_c} \quad \textbf{(D.3d)}$$

For the case of a constant yield factor and a steady fire, Equation D.3c evaluates as follows:

$$m_i = \int_0^t f_i \frac{Q}{\chi_a \Delta H_c} \, dt = \frac{f_i Q t}{\chi_a \Delta H_c} \quad \textbf{(D.3e)}$$

The term in the denominator of Equation D.3b represents the total mass of the smoke layer. Typically, the mass of fuel released is negligible compared to the mass of air entrained into the smoke layer, so the total mass of the smoke layer can be approximated as follows:

$$\sum_i m_i = \bar{\rho} V_u \frac{\rho_o T_o V_u}{T} \quad \textbf{(D.3f)}$$

For the case where the temperature rise of the smoke layer is small relative to the ambient absolute temperature $(\bar{T}/T_0 \approx 1)$, Equation D.3f reduces to the following:

$$\sum_i m_i = \rho_o V_u \quad \textbf{(D.3g)}$$

Substituting Equations D.3d and D.3g into Equation D.3b yields, for the *t*-squared fire, as follows:

$$Y_i = \frac{f_i \alpha t^3}{3\rho_o V_u \chi_a \Delta H_c} \quad \textbf{(D.3h)}$$

Substituting Equations D.3e and D.3g into Equation D.3b yields, for the steady fire, as follows:

$$Y_i = \frac{f_i Q t}{\rho_o V_u \chi_a \Delta H_c} \quad \textbf{(D.3i)}$$

For a fire that grows as a *t*-squared fire from $Q = 0$ at time $t = 0$ to $Q = Q_{qs}$ at time $t = t_{qs}$, then continues to burn indefinitely at $Q = Q_{qs}$, Equations D.3h and D.3i can be combined to yield the following:

$$Y_i = \frac{f_i\left[\dfrac{\alpha t_{qs}^3}{3 + Q_{qs}\left(t - t_{qs}\right)}\right]}{\rho_o V_u \chi_a \Delta H_c} \quad \textbf{(D.3j)}$$

The volume of the smoke layer, V_u, in these equations is evaluated by the methods presented in Section 5.5 with $V_u = (H - z)$.

D.4 Quasi-Steady Ventilated Stage — Optical Properties Analysis. Under quasi-steady ventilated conditions, a balance exists between the rate of mass inflow into the smoke layer and the rate of mass outflow from the smoke layer. The average optical density of the smoke layer can be calculated on a rate basis as follows:

$$D = \frac{D_m Q}{V} = \frac{D_m Q}{\chi_a \Delta H_c V} \quad \textbf{(D.4a)}$$

Equation D.4a can be used to determine the average optical density of the smoke layer for a given exhaust rate. Alternatively, the required exhaust rate needed to produce a particular optical density, D, can be determined by rearranging Equation D.4a as follows:

$$V = \frac{D_m Q}{D \chi_a \Delta H_c} \quad \textbf{(D.4b)}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Use of Equations D.4a and D.4b requires knowledge of the mass optical density, D_m, of the smoke. Mass optical densities for a variety of fuels are reported by Tewarson [54] and Mulholland [37]. Values reported by those investigators are based on small-scale fire tests, generally conducted under well-ventilated conditions. It should be recognized that the optical properties of smoke can be affected by ventilation, so it is not clear how well these small-scale data correlate with large-scale behavior, particularly for scenarios where the large-scale conditions include underventilated fires. This topic requires further research.

D.5 Quasi-Steady Ventilated Stage — Layer Composition Analysis. The mass fraction of each species i in the smoke layer under quasi-steady flow conditions is given in general by the following:

$$Y_i = \frac{\dot{m}_i}{\sum_i \dot{m}_i} \qquad \textbf{(D.5a)}$$

Under quasi-steady flow conditions, the mass flow rate of each species is given as follows:

$$\dot{m}_i = f_i \dot{m}_f = f_i \frac{Q}{\chi_a \Delta H_c} \qquad \textbf{(D.5b)}$$

The total mass flow rate under quasi-steady conditions is given by the following:

$$\sum_i \dot{m}_i = \overline{\rho} V = \rho_o V_{ent} = \rho_o \left(V - V_{exp}\right) \qquad \textbf{(D.5c)}$$

Substituting Equations D.5b and D.5c into Equation D.5a permits calculation of the mass fraction for each species i of interest in terms of a known exhaust rate, as follows:

$$Y_i - Y_{i,o} = \frac{f_i Q}{\rho_o \chi_a \Delta H_c \left(V - V_{exp}\right)} \qquad \textbf{(D.5d)}$$

To determine the required volumetric exhaust rate needed to limit the mass fraction of some species i to a limit value, Y_i, Equation D.5e is arranged to the following:

$$V = V_{exp} + \frac{f_i Q}{\rho_o \chi_a \Delta H_c \left(Y_i - Y_{i,o}\right)} \qquad \textbf{(D.5e)}$$

The volumetric expansion rate, V_{exp}, is calculated as follows:

$$V_{exp} = \frac{Q_n}{\rho_o c_p T_o} = \frac{(1-\chi_i)Q}{\rho_o c_p T_o} \qquad \textbf{(D.5f)}$$

Annex E Stratification of Smoke

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

E.1 Introduction. When the temperature of the air in the upper portion of the large space is greater than that at lower levels, smoke can stratify under the hot layer of air and not reach ceiling-mounted smoke detectors.

The potential for stratification relates to the difference in temperature between the smoke and the surrounding air at any elevation, as explained by Morton, Taylor, and Turner [83].

The maximum height to which plume fluid (smoke) rises, especially early after ignition, depends on the convective heat release rate and the ambient temperature variation in the open space.

Of particular interest are those situations in which the temperature of the air in the upper portion of the large open space is greater than at lower levels before the fire. This can occur as a result of a solar load where the ceiling contains glazing materials. Computational methods are available to assess the potential for intermediate stratification.

One case of interest is depicted in Figure E.1. In this case, the temperature of the ambient air is relatively constant up to a height above which there is a layer of warm air at uniform temperature. This situation can occur if the upper portion of a mall, atrium, or other large space is unoccupied so that the air in that portion is left unconditioned. If the interior air has a discrete temperature change at some elevation above floor level, the potential for stratification can be assessed by applying the plume centerline temperature correlation. If the plume centerline temperature is equal to the ambient temperature, the plume is no longer buoyant, loses its ability to rise, and stratifies at that height. Once a smoke evacuation system has started in an atrium or other large space, the stratification condition will be eliminated by removal of the hot layer. The problem facing the designer is how to ensure that the presence of smoke is promptly detected through all potential pre-fire temperature profiles. Under some conditions, such as nights and cold days, it is probable that a stratification condition will not be present and any smoke plume will promptly rise to the roof or ceiling of the volume, in which case detection at or near the top of the volume would be responsive. In other cases, such as hot summer days or days with a high solar load, the plume might not reach the top of the volume, and the smoke can spread at a level lower than intended. In that case, detection near the top of the volume would not respond, and the smoke management system would not be started. There is no sure way of identifying what condition will exist at the start of a fire; however, beam smoke detectors can be used to detect smoke with and without smoke stratification.



FIGURE E.1 Pre-Fire Temperature Profile.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

E.2 Temperature Gradient. Another case for which a solution has been developed is depicted in Figure E.2.

In this case, the ambient interior air within the large space has a constant temperature gradient (temperature change per unit height) from floor level to ceiling. This case is less likely than temperatures that approximate a step function. For the linear temperature profile, the maximum height that smoke will rise can be derived from the pioneering work of Morton, Taylor, and Turner [83], as follows:

$$z_m = 14.7 Q_c^{1/4} \left(\frac{\Delta T}{dz} \right)^{-3/8} \quad \textbf{(E.2a)}$$

where:

z_m = maximum height of smoke rise above base of fuel (ft)
Q_c = convective portion of the heat release rate (Btu/sec)
$\Delta T/dz$ = rate of change of ambient temperature with respect to height (°F/ft)

The convective portion of the heat release rate, Q_c, can be estimated as 70 percent of the total heat release rate.

The minimum Q_c required to overcome the ambient temperature difference and drive the smoke to the ceiling ($z_m = H$) follows readily from the preceding equation, as follows:

$$Q_{c,\min} = 2.39 \times 10^{-5} H^{5/2} \Delta T_o^{3/2} \quad \textbf{(E.2b)}$$

where:

$Q_{c,\ min}$ = minimum convective heat release rate to overcome stratification (Btu/sec)
H = ceiling height above fire surface (ft)
ΔT_o = difference between ambient temperature at the ceiling and ambient temperature at the level of the fire surface

Alternatively, an expression is provided in terms of the ambient temperature increase from floor to ceiling, which is just sufficient to prevent a plume of heat release, Qc , from reaching a ceiling of height H, as follows:

$$\Delta T_o = 1300 Q_c^{2/3} H^{5/3} \quad \textbf{(E.2c)}$$

Finally, as a third alternative, the maximum ceiling clearance to which a plume of strength, Q_c, can rise for a given ΔT_o follows from rewriting Equation E.2c, as follows:

$$H_{\max} = 74 Q_c^{2/5} \Delta T_o^{3/5} \quad \textbf{(E.2d)}$$



FIGURE E.2 Unusual Case of Linear Temperature Profile.

Annex F Types of Stairwell Pressurization Systems

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

F.1 Noncompensated Systems. In a noncompensated system, supply air is injected into the stairwell by actuating a single-speed fan, thus providing one pressure difference with all doors closed, another difference with one door open, and so on.

F.2 Compensated Systems. Compensated systems adjust to various combinations of doors that are open and closed, while maintaining positive pressure differences across such openings.

Systems compensate for changing conditions either by modulating supply airflows or by relieving excess pressure from the stairwell. The response time of the control system should be closely evaluated to ensure that pressures do not fall below the values given in Table 4.4.2.1.1. The location of the exhaust inlet(s) from the stairwell relative to the supply outlet(s) into the stairwell should be such that short circuits will not occur.

F.3 Compensated Systems — Modulating Supply Airflow. In a modulating supply airflow system, the capacity of the supply fan should be sized to provide at least the minimum air velocity when the design number of doors are open. Figure F.3 illustrates such a system. The flow rate of air into the stairwell is varied by modulating bypass dampers, which are controlled by one or more static pressure sensors that sense the pressure difference between the stairwell and the building. When all the stairwell doors are closed, the pressure difference increases and the bypass damper opens to increase the bypass air and decrease the flow of supply air to the stairwell. In this manner, excessive pressure differences between the stairwell and the building are prevented. The same effect can be achieved by the use of relief dampers on the supply duct when the fan is located outside the building. Supply airflow modulation can also be accomplished by varying fan speed, inlet vanes, variable pitch fan blades, or the number of fans operating. Response times of the controls with any system should be considered.



Notes:
1. Fan bypass controlled by one or more static pressure sensors located between the stairwell and the building interior.
2. A ground-level supply fan is shown; however, fan(s) could be located at any level.

FIGURE F.3 Stairwell Pressurization with Bypass Around Supply Fan.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

F.4 Compensated Systems — Overpressure Relief. Compensated system operation can also be accomplished by overpressure relief. In this instance, pressure buildup in the stairwell as doors close is relieved directly from the stairwell to the outside.

The amount of air relieved varies with the number of doors open, thus attempting to achieve an essentially constant pressure in the stairwell. Where exterior relief openings are subject to adverse effects from the wind, windbreaks or windshields are recommended.

If overpressure relief is to be discharged into the building, the effects on the integrity of the stairwells and the interaction with other building HVAC systems should be closely studied.

Systems using this principle should have combination fire/smoke dampers in the stairwell wall penetrations.

Overpressure relief can be accomplished by one of the following four methods:

(1) Barometric dampers with adjustable counterweights can be used to allow the damper to open when the maximum interior pressure is reached. This represents the simplest, least expensive method of overpressure relief because there is no physical interconnection between the dampers and the fan. The location of the dampers should be chosen carefully because dampers located too close to the supply openings can operate too quickly and not allow the system to meet the pressure requirements throughout the stairwell. The dampers can be subject to chattering during operation. Figure F.4 illustrates overpressure relief using barometric dampers.
(2) Motor-operated dampers with pneumatic or electric motor operators are another option for overpressure relief. These dampers are to be controlled by differential pressure controls located in the stairwell. This method provides more positive control over the stairwell pressures than barometric dampers. It requires more control than the barometric dampers and therefore is more complicated and costly.
(3) An alternative method of venting a stairwell is through an automatic-opening stairwell door or vent to the outside at ground level. Under normal conditions, this door would be closed and, in most cases, locked for security reasons. Provisions should be made to ensure that this lock does not conflict with the automatic operation of the system. Possible adverse wind effects are also a concern with a system that uses an opening to the exterior at ground level as a vent. Occasionally, high local wind velocities develop near the exterior stairwell door. Such local winds are difficult to estimate in the vicinity of new buildings without expensive modeling. Adjacent objects can act as windbreaks or windshields. Systems utilizing vents to the outside at ground level are more effective under cold conditions, with the stack effect assisting the stair pressurization system for stairwells primarily above grade.
(4) An exhaust fan can be used to prevent excessive pressure when all stairwell doors are closed. The fan should be controlled by a differential pressure sensor configured so that the fan will not operate when the pressure difference between the stairwell and the building falls below a specified level. This should prevent the fan from pulling smoke into the stairwell when a number of open doors have reduced stairwell pressurization. Such an exhaust fan should be specifically sized so that the pressurization system will perform within design limits. To achieve the desired performance, it is believed that the exhaust fan control should be of a modulating type as opposed to an on–off type. If the exhaust fan will be adversely affected by the wind, a windshield is recommended.



FIGURE F.4 Stairwell Pressurization with Vent to the Outside.

Annex G HVAC Air-Handling System Types

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

G.1 HVAC Air-Handling System Types. Various types and arrangements of air-handling systems are commonly used in different types of buildings. Some types are more readily adaptable for smoke-control applications than others. Examples of typical air-handling systems are described below.

G.2 Individual Floor Systems. The use of individual air-handling units serving one floor or part of a floor is a common design approach. These HVAC units might or might not have separate return/exhaust fans. Where these fans are not separate, a means for providing relief of the fire floor pressures, either through relief dampers on the duct system or by other means, should be investigated. Outdoor air can be supplied to each air-handling unit by one of the following means:

(1) Exterior louvers and dampers
(2) A common duct system sized to handle the required quantities of air
(3) A common duct system having a variable-speed supply fan
(4) Individual variable-speed supply fans

Air-handling units can be used for smoke control if sufficient outside air and exhaust air capability are available.

G.3 Centralized Multifloor Systems. Some buildings utilize centralized HVAC equipment in main mechanical areas that serve multiple floors within the building. HVAC systems of this type might require fire and smoke shaft dampering to provide exhaust of the fire floor and pressurization of the adjacent floors with outside air. Because these central fans can be of large capacity, care must be taken in designing a system to include a means of avoiding excessive pressures within the duct system to prevent rupture, collapse, or other damage. Means should be provided to control pressures within exits and corridors that could inhibit doors from being opened or closed.

G.4 Fan/Coil Units and Water Source Heat Pump Units. Fan/coil and water source heat pump types of air-handling units

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

are often located around the perimeter of a building floor to condition the perimeter zones. They can also be located throughout the entire floor area to provide air conditioning for the entire space. Because the fan/coil and water source heat pump units are comparatively small in outside air capacity and are typically difficult to reconfigure for smoke-control purposes, they generally are not suitable for performing smoke-control functions. If these units have outside air-intake provisions, such units within the smoke zone should be shut down when the zone is to be negatively pressurized. The fan/coil and water source heat pump units are typically used in combination with larger central HVAC equipment or individual interior zone air-handling units. The zone smoke control functionality should be provided by the larger central or interior zone air-handling units.

G.5 Induction Systems. Induction-type air-handling units located around the perimeter of a building are primarily used to condition the perimeter zone of older multistory structures. A central HVAC system supplies high-pressure heated or cooled air to each perimeter induction unit. Room air is then induced into the induction unit, mixed with the primary air from the central HVAC system, and discharged into the room. Induction units within the smoke zone should be shut down or should have the primary air closed off on initiation of smoke control in smoke zones.

G.6 Dual Duct and Multizone Systems. HVAC units used in dual duct and multizone systems contain cooling and heating coils, each in a separate compartment or deck within the unit.

Dual duct systems have separate hot and cold ducts connected between the decks and the mixing boxes that mix the air supplied to the space served. For high-pressure systems, the mixing boxes also reduce the system pressure. Multizone systems mix heated and cooled air at the unit and supply the mixture through low-pressure ducts to each space. Smoke control can be achieved by supplying maximum air to areas adjacent to the smoke zone. This should be accomplished using the cold deck because it is usually sized to handle larger air quantities. For the smoke zone, supply fans should be shut off.

G.7 Variable Air Volume (VAV) Systems. Variable air volume (VAV) systems are either individual floor systems or centralized multifloor systems that are provided with terminal devices that typically supply cooling only. Individual areas served by the system usually have other sources of heating (e.g., baseboard or cabinet heaters). VAV systems vary the quantity of cold air supplied to the occupied space based on actual space demands. Some VAV systems bypass supply air to the return air inlet of the fan, reducing supply air volumes and resultant pressure to avoid fan or ductwork damage. In the smoke control mode, such bypasses must be closed. For smoke control, the speed of the VAV system supply fan(s) should be increased, and VAV terminal unit controls should be configured to open the terminals in the nonsmoke zone to supply maximum volume of outside air to pressurize spaces if sufficient air is available. Bypass dampers on systems using this method must be closed. It is possible to achieve smoke control with the VAV system supplying minimal air, but care must be taken to ensure that adequate pressure is developed in the space.

G.8 Fan-Powered Terminal Systems. A fan-powered terminal unit receives variable air volumes of primary cooled air and return air that blend in the terminal unit to provide a constant volume of variable temperature supply air to the occupied spaces. The terminal unit consists of a constant air volume fan for supplying the blended air to the occupied space, a damper-controlled primary air connection, and a return air opening.

Terminal units serving perimeter zones can have a heating coil to provide additional heat for the perimeter zone. In the smoke-control mode, terminal unit fans located in the smoke zone should be shut off and the primary air damper closed. Terminal units serving zones adjacent to the smoke zone can continue to operate.

G.9 Mixed Systems. When combinations of the examples described in this annex are used, care must be exercised in the application of different types of variable-volume terminal units to determine their effect on zoned smoke control. Designs must be based on the capability of system configurations to achieve positive or negative pressures as needed for smoke control.

G.10 Ventilation Systems with No Outside Air. In certain instances, specialized systems with no outside air are used for primary cooling and heating. These systems include self-contained air conditioners, radiant panel systems, and computer room units. Because these systems provide no outside air, they are not suitable for smoke-control application. Because building codes require ventilation for all occupied locations, a separate system for providing outside air is needed. The system supplying outside air can be used for smoke control, although the quantity of air provided might not be adequate for full pressurization.

G.11 Special-Use Systems. Laboratories, animal facilities, hospital facilities, and other unusual occupancies sometimes use once-through outdoor air systems to avoid contamination and could have special filtration and pressurization requirements. These special-use systems can be suitable for a smoke-control application. Care should be exercised to avoid contamination of bacteria-free areas, experiments, processes, and similar areas.

Annex H Fire Fighters' Smoke-Control Station (FSCS) Considerations

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

H.1 Considerations for a fire fighters' smoke-control station (FSCS) should include the following:

(1) *Location and Access.* The FSCS should be located as close in proximity to other fire fighters' systems as can be provided within the building. Means should be provided to ensure only authorized access to the FSCS. Where acceptable to the authority having jurisdiction, the FSCS should be provided within a specific location or room, separated from public areas by a suitably marked and locked door. If the FSCS is located in a separate room, the room location, size, access means, and other physical design considerations should be acceptable to the authority having jurisdiction.

(2) *Physical Arrangement.* The FSCS should be designed to graphically depict the physical building arrangement, smoke-control systems and equipment, and the areas of the building served by the equipment. Following is a summary of the status indicators and smoke-control capability applicable to the FSCS smoke-control graphic(s). Status indicators should be provided for all smoke-control equipment by pilot lamp–type indicators. The positions of multiposition control switches should not be used to indicate the status of a controlled device in lieu of pilot lamp–type status indicators.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

(a) Smoke-control fans and other critical operating equipment in the operating state: green.
(b) Smoke-control equipment and other critical equipment that can have two or more states or positions, such as dampers: green (i.e., open), yellow (i.e., closed). The position of each piece of equipment should be indicated by lamps and appropriate legends. Intermediate positions (e.g., modulating dampers that are not fully open or fully closed) can be indicated by not illuminating either of their pilot lamps.
(c) Smoke-control system or equipment faults: amber/orange.

(3) *Smoke-Control Capability.* The FSCS should provide control capability over all smoke-control system equipment or zones within the building. Wherever practical, it is recommended that control be provided by zone, rather than by individual equipment. This approach will aid fire fighters in readily understanding the operation of the system and will help to avoid problems caused by manually activating equipment in the wrong sequence or by neglecting to control a critical component. Control by zone should be accomplished as follows: PRESSURE-AUTO-EXHAUST control over each zone that can be controlled as a single entity relies on system programming to properly sequence all devices in the zone to produce the desired effect. In systems utilizing common supply or return ducts, or both, inclusion of an ISOLATE mode is desirable. To enable use of the system to flush smoke out of a zone after the fire has been extinguished, a PURGE (equal supply and exhaust) mode can also be desirable. If control over individual pieces of equipment is deemed necessary, the following control options should be provided:

(a) ON-AUTO-OFF control over each individual piece of operating smoke-control equipment that can also be controlled from other sources within the building. Controlled components include all stairway pressurization fans; smoke exhaust fans; HVAC supply, return, and exhaust fans in excess of 2000 ft^3/min (57 m^3/min); elevator shaft fans; atrium supply and exhaust fans; and any other operating equipment used or intended for smoke-control purposes.
(b) ON-OFF or OPEN-CLOSE control over all smoke control and other critical equipment associated with a fire or smoke emergency and that can be controlled only from the FSCS.
(c) OPEN-AUTO-CLOSE control over all individual dampers relating to smoke control that are also controlled from other sources within the building. HVAC terminal units, such as VAV mixing boxes that are all located within and serve one designated smoke-control zone, can be controlled collectively instead of individually. HVAC unit coil face bypass dampers that are arranged so as not to restrict overall airflow within the system can be exempt. Additional controls might be required by the authority having jurisdiction.

(4) *Control Action and Priorities.* The FSCS control action should be as follows:

(a) ON-OFF, OPEN-CLOSE. These control actions should have the highest priority of any control point within the building. Once issued from the FSCS, no automatic or manual control from any other control point within the building should contradict the FSCS control action.
i. If automatic means are provided to interrupt normal nonemergency equipment operation or produce a specific result to safeguard the building or equipment (e.g., duct freezestats, duct smoke detectors, high-temperature cutouts, temperature actuated linkage, and similar devices), such means should be capable of being overridden or reset to levels not exceeding levels of imminent system failure, by the FSCS control action, and the last control action as indicated by each FSCS switch position should prevail.
ii. Control actions issued from the FSCS should not override or bypass devices and controls intended to protect against electrical overloads, provide for personnel safety, and prevent major system damage. These devices include overcurrent protection devices and electrical disconnect switches, high limit static pressure switches, and combination fire/smoke dampers beyond their degradation temperature classifications meeting ANSI/UL 555, *Standard for Fire Dampers*, or ANSI/UL 555S, *Standard for Smoke Dampers*.
(b) AUTO. Only the AUTO position of each three-position FSCS control should allow automatic or manual control action from other control points within the building. The AUTO position should be the normal, nonemergency, building, control position. When an FSCS control is in the AUTO position, the actual status of the device (on, off, open, closed) should continue to be indicated by the status indicator(s).
(c) *FSCS Response Time.* For purposes of smoke control, the FSCS response time should be the same as for automatic or manual smoke-control action initiated from any other building control point. FSCS pilot lamp indication of the actual status of each piece of equipment should not exceed 15 seconds after operation of the respective feedback device.

(5) *Graphic Depiction.* The location of smoke-control systems and equipment within the building should be indicated by symbols within the overall FSCS graphic panel. Where zoned smoke control is used, a sufficient number of smoke-control components to convey the intended operation of the smoke-control systems and equipment should be shown. These components normally would include major ducts, fans, and dampers that are part of the smoke control system. Where control is provided over individual fans and dampers used for smoke control, these components should be shown on the FSCS graphic panel and, where appropriate, should be shown connected to their respective ducts, with a clear indication of the direction of airflow. In either case, the building areas served by the smoke-control systems should be shown on the FSCS graphic panel. Status indications for damper positions should be shown where their inclusion would aid in understanding the operation of the system and can be omitted where their inclusion would hinder understanding of the system, such as on an already densely populated panel. Damper position indication can also be omitted where no separate control over damper position is provided.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Annex I Information on Testing for Leakage Between Smoke Zones

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

I.1 Although not part of the formal testing procedure, the testing of buildings to determine the amount of leakage between smoke zones can be of value in developing the initial system. Testing for this purpose can often use airflow-measuring equipment existing in the systems. This section describes the normal arrangement of a variety of systems and testing methods that can be used to determine the leakage of enclosures. Leakage in buildings comes from a variety of sources, such as the following:

(1) Curtain wall construction, where leakage paths can be formed between the outer surface and the floor slab
(2) Drywall partitions, where gaps in the drywall behind cover moldings can form leakage paths
(3) Electric switches and outlets in drywall partitions that form leakage paths through the partitions
(4) Installation of doors with undercuts, latching mechanisms, and other gaps forming leakage paths
(5) Interface of drywall partitions at fluted metal deck requiring seals in the flute
(6) Electric outlets in floor slabs within the space or above the space and providing leakage to other floors of the building
(7) Duct penetrations through walls, where there can be leakage around the duct behind angles that hold fire dampers in place
(8) Perimeter induction systems, which often have gaps around ducts through floor slabs that are hidden behind air distribution enclosures
(9) Pipe, conduit, and wire way penetrations through walls and floors requiring listed through-penetration seals

I.2 Building HVAC Systems Suitable for Enclosure Tightness Testing. Many building HVAC systems can be used to measure the leakage through enclosures. These systems typically contain a central fan that can draw large quantities of outside air into the building for pressurizing. Because all these systems contain openings, ductwork, and sometimes fans to return the air from the enclosure to the central air handler, it is important that these systems be shut off during the test. The use of smoke dampers at the points where the ducts leave the enclosure will give more assurance that leakage from the space through this source will be minimized.

I.2.1 Single-Floor VAV Systems. Many modern office buildings are provided with a separate air handler on each floor of the building to supply conditioned air to the space. These systems are arranged as variable volume systems, whereby the thermostats vary the amount of air delivered to the space rather than the temperature of that air. This arrangement requires a variable frequency controller on the fan that responds to pressure in the duct system. As the variable volume control device is closed, the pressure builds up in the duct and the fan speed is slowed in response to that pressure. Normally these systems contain air-measuring devices in the supply and return ducts that are used to synchronize the return fan operation with the supply fan, so a constant quantity of outside air can be introduced into the space to maintain indoor air quality. These airflow-measuring devices can be used to measure the airflow introduced into the space, and the speed of the fan can be adjusted to control the pressure across the enclosure barriers.

I.2.2 Central Fan VAV Systems. Central fan VAV systems are a variation of the single-floor VAV system. A single fan will supply 10 or more floors, each of which has a number of variable volume boxes. As in the case of the single-floor system, the fan responds to a pressure sensor in the duct. A flow-measuring station at the fan is used to track the return fan with the supply fan in order to maintain constant outside air, as in the case of the single-floor VAV system. Generally, these systems are provided with a motor-operated shut-off damper at each floor, since the system can be economically used to supply only a portion of the floors when other floors are vacant.

These systems can be used for testing of spaces by commanding that all the supply dampers to the floors be closed except on the floor being tested. In this manner, the airflow onto the floor can be measured as the pressure across the barriers is adjusted. The leakage characteristics of the main duct system as well as those of the dampers that are to be shut must be known so the corrections for duct and damper leakage in the system of the floor under test can be determined ahead of time. This can be accomplished by shutting all the dampers on the system, pressurizing the duct system to various pressures using the supply fans, and measuring the airflow at the air measuring station in the supply duct. One variation of a multifloor VAV system has air-measuring stations on each floor of the building. The purpose of these stations is to verify that a particular tenant is not creating so much load on the floor that more airflow is used than is designed into the system. When overload is encountered, the airflow can be measured directly on the floor so that adjustments for main duct leakage are unnecessary.

I.2.3 Constant-Volume Multizone Systems. Constant-volume multizone systems mix hot and cold air at a central air handling unit and have a separate duct system that goes out to various spaces. Typically, they are not provided with air-measuring stations that would have to be retrofitted to the ducts delivering air to the spaces. The spaces need to coincide with the enclosures being tested. Typically, there is also no means of varying the flow to each space. Varying the flow requires the addition of either manual or motorized dampers in the duct system that are adjusted to achieve the test pressure or pressures.

I.2.4 Constant-Volume Terminal Reheat System. Constant-volume terminal reheat systems are the most difficult to use for testing for enclosure tightness. Typically, these systems contain central fans that deliver air to a duct system at a set temperature. The duct system is distributed throughout the building, and reheated coils are placed at various locations to temper the air to maintain space conditions. There are typically no measuring stations or any automatic dampers in the system. To use this system for testing, it is first necessary to retrofit it with air-measuring stations and dampers to coincide with the enclosures being tested.

I.3 Building HVAC Systems Not Suitable for Enclosure Tightness Testing. A number of HVAC systems have little or no value in testing the tightness of an enclosure, because they introduce a limited amount of airflow into the space or are arranged so that there are multiple duct entrances into the space. Therefore, making airflow measurement in such systems is impractical.

I.3.1 Unitary Heat Pump/Fan Coil Systems. Unitary heat pump/fan coil systems come in a number of configurations. These systems are similar, in that the space is provided with a number of separate units, each with limited airflow capacity. Outside air to the space is introduced in one of three ways:

(1) Units are located on the perimeter with a separate outside air duct for each unit. This arrangement typically has a

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

small penetration through the outside wall of the building with no ductwork attached. The amount of outside air introduced is so small and the capacity of the systems to pressurize the space is so limited that the systems cannot be used for testing the integrity of the space. In these instances, the units will be detrimental to the operation of any system in the space designed to pressurize it unless each outside air duct is fitted with a tight-closing automatic damper.

(2) Units are located only on the perimeter, and outside air is introduced through a separate duct system. In this instance, the units are used in conjunction with an interior duct system. The outside air duct for the perimeter is of limited capacity and should be fitted with tight-closing automatic dampers to maintain the integrity of the enclosure. Testing of the space should be done through the interior duct system.

(3) Units are distributed throughout both the perimeter and the interior. In this instance, outside air is introduced into the space through a separate duct system that distributes throughout the entire floor area. This duct system is sized to handle the minimum outside air quantities needed in the space and might or might not have sufficient flow to provide pressure in the space. Whether this system can be used for the pressure testing must be decided on a case-by-case basis. It will be necessary to provide the system with air-measuring stations and possibly shut-off dampers if the system serves multiple floors.

I.3.2 Perimeter Induction Systems. Perimeter induction systems are typically arranged to handle only the perimeter of the building. These systems are arranged with a terminal unit along the perimeter under the windows, each provided with a duct to a central air distribution system. The ducts typically are small [under 20 in.^{2} (129 cm^2) per unit] and either penetrate the floor to a distribution system on the floor below or connect to a vertical riser that extends up through the building and supplies four to six units per floor. These systems do not lend themselves to testing of spaces because of the multiple duct connections on each floor. The duct connections should be provided with tight-closing automatic dampers so that pressurization of the space will be possible. Generally an interior system, previously described, is provided, which is one of the types that can be used for the testing and pressurization.

Annex J Advisory Information on Acceptance Testing

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

J.1 One or more of the following persons should be present to grant acceptance:

(1) Authority having jurisdiction
(2) Owner
(3) Designer

All documentation from operational testing should be available for inspection.

J.2 Testing Documentation. On completion of acceptance testing, a copy of all operational testing documentation should be provided to the owner. This documentation should be available for reference during periodic testing and maintenance.

J.3 Owner's Manuals and Instruction. Information should be provided to the owner that defines the operation and maintenance of the system. Basic instruction on the operation of the system should be provided to the owner's representatives. Because the owner can assume beneficial use of the smoke control system on completion of acceptance testing, this basic instruction should be completed prior to acceptance testing.

J.4 Partial Occupancy. Acceptance testing should be performed as a single step when a certificate of occupancy is being obtained. However, if the building is to be completed or occupied in stages, multiple acceptance tests can be conducted in order to obtain temporary certificates of occupancy.

J.5 Simulated Smoke. Where the authority having jurisdiction requires demonstrations utilizing smoke or products that simulate smoke, they should be based on the objective of inhibiting smoke from migrating across smoke zone boundaries to other areas. Test criteria based on the system's ability to remove smoke from an area should not be used for zoned smoke-control systems designed for containment, not removal, of smoke.

J.6 Much can be accomplished to demonstrate smoke control system operation without resorting to demonstrations that use smoke or products that simulate smoke. The test methods described in 8 should provide an adequate means to evaluate the smoke-control system's performance. Other test methods have been used historically in instances where the authority having jurisdiction requires additional testing. These test methods have limited value in evaluating certain system performance, and their validity as methods of testing a smoke-control system is questionable. Examples of other test methods that have been used are as follows:

(1) Chemical smoke tests
(2) Tracer gas tests
(3) Real fire tests

Chemical smoke tests have achieved a degree of popularity out of proportion to the limited information they are capable of providing. The most common sources of chemical smoke are the commercially available "smoke candle" (sometimes called a smoke bomb) and the smoke generator apparatus. In this test, the smoke candle is usually placed in a metal container and ignited. The purpose of the metal container is protection from heat damage after ignition; it does not inhibit observation of the movement of the chemical smoke. Care needs to be exercised during observations, because inhalation of chemical smoke can cause nausea. This type of testing is less realistic than real fire testing because chemical smoke is cold and lacks the buoyancy of smoke from a flaming fire. Such buoyancy forces can be sufficiently large to overpower a smoke-control system that was not designed to withstand them. Smoke from a sprinklered fire has little buoyancy, and so it might be expected that such smoke movement is similar to the movement of unheated chemical smoke. This has not yet been confirmed by test data. Chemical smoke testing can identify leakage paths, and such tests are simple and inexpensive to perform. The question arises as to what information can be obtained from a cold chemical smoke test. If a smoke-control system does not achieve a high enough level of pressurization, the pressures due to hot, buoyant smoke could overcome that system. The ability to control cold chemical smoke provides no assurance of the ability to control hot smoke in the event of a real fire.

Chemical smoke is also used to evaluate the effectiveness of so-called smoke "purging" systems. Even though such systems are not smoke-control systems, they are closely related and

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

thus are briefly addressed here. For example, consider a system that has six air changes per hour when in the smoke purge mode. Some testing officials have mistaken this number of air changes to mean that the air is completely changed every 10 minutes and that 10 minutes after the smoke candle is out, all the smoke should be gone from the space. Of course, this is not what happens. In a purging system, the air entering the space mixes to some extent with the air and smoke in the space. If the purging system is part of the HVAC system, it has been designed to promote a rather complete degree of mixing. If the concentration of smoke is close to uniform within the space, then the method of analysis for purging presented in Section 4.1.2 of ASHRAE/SFPE *Principles of Smoke Management* is appropriate. Based on such perfect mixing, after 10 minutes, 37 percent of the original smoke remains in the space.

Annex K Example Problems Illustrating the Use of Equations

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

K.1 Problem Data. Given: Atrium with uniform rectangular cross-sectional area and the following:

(1) Height *(H)* = 120 ft
(2) Area *(A)* = 20,000 ft^2
(3) Design fire (stead state) = 5000 Btu/sec
(4) Highest walking surface = 94 ft

K.1.1 Problem 1. Determine the time when the first indication of smoke is 6 ft above the highest walking surface.

Solution:

(1) Use Equation 5.4.2.1:

$$\frac{z}{H} = 0.67 - 0.28 \ln\left(\frac{\frac{tQ^{1/3}}{H^{4/3}}}{\frac{A}{H^2}}\right) \qquad \textbf{(K.1.1a)}$$

where:
z = 100 ft
H = 120 ft
Q = 5000 Btu/sec
$Q^{1/3}$ = 17.1
$H^{4/3}$ = 591.9
A/H^2 = 1.4

$$0.83 = 0.67 - 0.28 \ln\left(\frac{\frac{17.1t}{591.9}}{1.4}\right)$$

where:
0.16 = $-0.28 \ln(0.02t)$
-0.57 = $\ln(0.02t)$
0.56 = $0.02t$
t = 28 seconds

(2) Use the mass flow method, based on Equation 5.5.1.1b.

Two calculation methods will be used. The first calculation will assume a smoke density of 0.075 lb/ft^3. This is equivalent to smoke at a temperature of 70°F. The second calculation assumes the layer temperature is equal to the average plume temperature at the height of the smoke layer interface. In both cases, no heat loss from the smoke layer to the atrium boundaries is assumed. A time interval of 1 second is chosen for each case.

Step 1. Calculate mass flow (lb/sec) at $z = H$, using Equation 5.5.1.1b.

Step 2. Determine temperature of the smoke layer, estimated as average smoke plume temperature at the height of the smoke layer interface:

$$T_p = T_o + \frac{Q_c}{mC_p} \qquad \textbf{(K.1.1b)}$$

where:
T_p = average plume temperature at elevation z (°F)
T_o = ambient temperature (°F)
Q_c = convective portion of heat release rate (Btu/sec)
m = mass flow rate in plume at height z (lb/sec)
C_p = specific heat of plume gases (0.24 Btu/lb-°F)

Step 3. Convert mass flow to volume flow, assuming smoke temperature is 70°F, as follows:

$$V = \frac{m}{\rho} \qquad \textbf{(K.1.1c)}$$

where:
V = volume flow (ft^3/min)
m = mass flow (lb/sec)
ρ = density of smoke (lb/ft^3)

Step 4. Assume that the smoke volume produced in the selected time interval is instantly and uniformly distributed over the atrium area. Determine the depth of the smoke layer, dz (ft), deposited during the selected time period.

Step 5. Calculate the new smoke layer interface height (ft). Repeat steps (1) through (5) until the smoke layer interface reaches the design height. Table K.1.1, showing sample values, illustrates the calculation technique.

K.1.2 Problem 2. Determine the volumetric exhaust rate required to keep smoke 6 ft above the highest walking level in the atrium, that is, the ninth floor balcony. Consider the fire to be located in the center of the floor of the atrium. With the fire located in the center of the atrium, an axisymmetric plume is expected. First, Equation 5.5.1.1a must be applied to determine the flame height.

Given:
$Q_c = 3500$ Btu/sec
$z_l = 0.533 Q_c^{2/5}$
$z_l = 0.533(3500)^{2/5}$
$z_l = 13.9$ ft

With the design interface of the smoke layer at 85 ft above floor level, the flame height is less than the design smoke layer height. Thus, using Equation 5.5.1.1b to determine the smoke production rate at the height of the smoke layer interface:

$z = 100$ ft
$m = 0.022 Q_c^{1/3} z^{5/3} + 0.0042 Q_c$
$m = 0.022(3500)^{1/3} (100)^{5/3} + 0.0042(3500)$
$m = 734$ lb/sec

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table K.1.1 Sample Calculated Values

Time (sec)	Mass (lb/sec)	Temperature (°F)	Volume (ft^3/sec)	Z (ft)
0		70		120
1	990	84.7	13,565	119.3
2	981	84.9	13,443	118.6
3	972	85.0	13,322	118.0
4	963	85.1	13,203	117.3
5	954	85.3	13,085	116.7
6	945	85.4	12,969	116.0
7	937	85.6	12,855	115.4
8	928	85.7	12,741	114.7
9	920	85.9	12,629	114.1
10	911	86.0	12,519	113.5
11	903	86.1	12,410	112.9
12	895	86.3	12,302	112.2
13	887	86.4	12,196	111.6
14	879	86.6	12,090	111.0
15	871	86.7	11,987	110.4
16	864	86.9	11,884	109.8
17	856	87.0	11,783	109.3
18	849	87.2	11,683	108.7
19	841	87.3	11,584	108.1
20	834	87.5	11,486	107.5
21	827	87.6	11,389	106.9
22	820	87.8	11,294	106.4
23	812	87.9	11,200	105.8
24	805	88.1	11,107	105.3
25	799	88.3	11,014	104.7
26	792	88.4	10,923	104.2
27	785	88.6	10,834	103.6
28	778	88.7	10,745	103.1
29	772	88.9	10,657	102.6
30	765	89.1	10,570	102.0
31	759	89.2	10,484	101.5
32	752	89.4	10,399	101.0
33	746	89.5	10,316	100.5
34	740	89.7	10,233	100.0

If the smoke exhaust rate is equal to the smoke production rate, the smoke layer depth will be stabilized at the design height. Thus, converting the mass flow rate to a volumetric flow rate is as follows:

$$V = \frac{m}{\rho} \qquad \textbf{(K.1.2)}$$

where:
ρ = 0.075 lb/ft^3
V = 734/0.075
V = 9790 ft^3/sec, or 587,400 scfm

K.1.3 Problem 3. Determine whether the plume will contact all of the walls prior to reaching the design height noted in Problem 2 (6 ft above the highest walking level). The calculation in Problem 2 assumes that the smoke plume has not widened to contact the walls of the atrium prior to reaching the design interface height. This calculation serves as a check.

Using Equation 5.5.4.1 with an interface height of 100 ft (z = 100 ft):

$d = 0.5z$
$d = 0.5(100)$
d = 50 ft

Thus, the smoke does not contact the walls of the atrium prior to reaching the design interface height.

K.1.4 Problem 4. Determine the temperature of the smoke layer after fan actuation.

The quality of the smoke contained in the smoke layer might be important in the context of tenability or damageability studies. Applying the ΔT equation for vented fires as indicated in Table D.1.3:

Given:
Q_c = 3500 Btu/sec
ρ = 0.075 lb/ft^3
c = 0.24 Btu/lb-°F
V = 9790 ft^3/sec (the value calculated in K.1.3)

$\chi_1 = 0$ (adiabatic case to obtain upper limit estimate of temperature rise)

Solution:
$\Delta T = Q_c/(\rho c V)$
$\Delta T = 3500/[(0.075)(0.24)(9790)]$
ΔT = 20°F

K.1.5 Problem 5. On the tenth floor, a 10 ft wide, 6 ft high opening is desired from the tenant space into the atrium. The bottom of this opening is 92 ft above the floor of the atrium.

(1) For a fire in the tenant space, determine the opposed airflow required to contain smoke in the tenant space (assume fire temperature is 1000°F).

Using Equation 5.10.1:

Given:
H = 6 ft
g = 32.2 ft/sec^2
T_f = 1000°F
T_o = 70°F

Solution:

$$v = 38\left[gH\frac{T_f - T_o}{T_f + 460}\right]^{1/2}$$

$$v = 38\left[(32.2)(6)\frac{1000 - 70}{1000 + 460}\right]^{1/2}$$

$$v = 422 \text{ ft/min}$$

(2) For a fire on the floor of the atrium, determine the opposed airflow required to restrict smoke spread into the tenant space.

Given:
H = 6 ft
g = 32.2 ft/sec^2
Q = 5000 Btu/sec
T_o = 70°F

Solution:

Determine T_f as the average plume temperature using Equation 5.5.5.

$$T_f = T_o\frac{Q_c}{mc}$$

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Determine m from Equation 5.5.1.1b using $z = 95$ ft (height of middle of opening above floor level) (flame height for this case <z; see Problem 2):

$$m = 0.022Q^{1/3}z^{5/3} + 0.0042Q$$
$$m = 0.022(3500)^{1/3}(95)^{5/3} + 0.0042(3500)$$
$$m = 675$$
$$T_f = 70 + \frac{3500}{(675)(0.24)}$$
$$T_f = 92°\text{F}$$

Using Equation 5.10.3:

$$v = 38\left[gH\frac{T_f - T_o}{T_f + 460}\right]^{1/2}$$
$$v = 38\left[(32.2)(6)\frac{92 - 70}{92 + 460}\right]^{1/2}$$
$$v = 105 \text{ ft/min}$$

Annex L Comparison of Equations

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

L.1 Calculation results using Equation 5.4.2.2 or 5.4.2.2a that yield $z/H > 1.0$ indicate that the smoke layer has not yet begun to descend. Equations 5.4.2.2 and 5.4.2.2a are based on limited experimental data.

Equations 5.4.2.1 and 5.4.2.2 are empirically based for estimating the smoke layer interface position during the smoke filling process. This review of Equations 5.4.2.1 and 5.4.2.2 is divided into two parts as follows:

(1) Comparison of the results of both Equations 5.4.2.1 and 5.4.2.2 with those from theoretically based equations (with empirically determined constants), hereafter referred to as ASET-based equations
(2) Evaluation of the predictive capability of Equation 5.4.2.1 and an ASET-based equation by comparing the output from the equations with experimental data

L.2 Comparisons with ASET-Based Equations. Comparisons of the NFPA 92 equations for smoke filling with ASET-based equations provide an indication of the differences between empirically based equations, for example, Equations 5.4.2.1 and 5.4.2.2, with those that are based principally on theory.

L.3 Steady Fires. A theoretically based equation for smoke filling can be derived using the laws of conservation of mass and energy to determine the additional volume being supplied to the upper layer (Milke and Mowrer [82]). Using Zukoski's plume entrainment correlation (Walton and Notorianni [84]),

$$\frac{z}{H} = \left(1 + \frac{2k_v\frac{tQ^{1/3}}{H^{4/3}}}{3\frac{A}{H^2}}\right)^{-3/2} \quad \textbf{(L.3a)}$$

where:

z = smoke layer interface position above base of fuel (m)
H = ceiling height (m)
kv = entrainment constant ≈0.064 $m^{4/3}/(\text{sec-kW}^{1/3})$
t = time from ignition (sec)
Q = heat release rate (kW)
A = cross-sectional area of space (m^2)

A comparison of z/H predicted by Equations 5.4.2.1 and L.3a is presented in Figure L.3(a) for a ceiling height of 30 m, a steady fire size of 5 MW, and a wide range of A/H^2 ratios. In general, the agreement between the two equations is reasonable.



FIGURE L.3(a) Comparison of Algebraic Equations, Equations 5.4.2.1 and L.3a: Steady Fire.

Equation 5.4.2.1 predicts a lower smoke layer interface position at most times, except in the case of the voluminous space represented by A/H^2 of 10. In this case, Equation 5.4.2.1 indicates a delay of approximately 100 seconds before a layer forms, while Equation L.3a indicates immediate formation of the layer. Such a delay is reasonable for such a large space. This delay can be addressed by including an additional term in Equation L.3a to account for the transport lag (Mowrer and Williamson [85]). The transport lag is estimated as 37 seconds for this case, with a height of 30 m and a cross-sectional area of 9000 m^2. While the comparison in Figure L.3(a) is useful, it applies only to selected values of A, H, and Q. This comparison can be generalized for all values of A, H, and Q by forming a ratio of the two equations expressed in terms of t, as follows:

$$\frac{t_{eqn\ 1.3a}}{t_{eqn\ 6.1.2.1}} = \frac{3}{2k_v}\frac{\left[\left(\frac{z}{H}\right)^{-2/3} - 1\right]}{\exp\left(\frac{1.11 - \frac{z}{H}}{0.28}\right)} \quad \textbf{(L.3b)}$$

Figure L.3(b) indicates the relationship of the time ratio with the normalized smoke layer depth, $(H - z)/H$. For perfect agreement between the two equations, the time ratio should have a value of 1.0. However, the time ratio varies appreciably and is within 20 percent of 1.0 for only a very small range. For normalized smoke layer depths less than 0.13 (or a normalized clear height of 0.87), Equation L.3a always predicts a shorter time to reach a particular depth than Equation 5.4.2.1. Conversely, Equation 5.4.2.1 predicts shorter times to attain any normalized smoke layer depth in excess of 0.13.

The time ratio is relatively insensitive for values of $(H - z)/H$, ranging from 0.4 to 0.6. Within this range, the time ratio is nominally 1.5, that is, the time predicted by Equation L.3a to obtain a smoke layer of a particular depth is 50 percent greater than that predicted by Equation 5.4.2.1. Alternatively, Equation 5.4.2.1 predicts a more rapid descent to this range of smoke layer depths than Equation L.3a.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.



FIGURE L.3(b) Comparison of Algebraic Equations, Equations 5.4.2.1 and L.3a: Steady Fire — Normalized Smoke Layer Depth.

L.4 *t*-Squared Fires. A similar comparison of the empirically based Equation 5.4.2.2 and a theoretically based equation for *t*-squared fires can be conducted. The ASET-based equation is as follows:

$$\frac{z}{H} = \left(1 + \frac{\dfrac{20 k_v t^{5/3}}{H^{-4/3}}}{t_g^{2/3} \dfrac{A}{H^2}} \right)^{-3/2} \qquad \text{(L.4a)}$$

where t_g = fire growth rate (sec).

A comparison of the predicted z/H values are presented in Figure L.4(a) for a ceiling height of 30 m, a moderate fire growth rate (tg = 300 seconds), and a wide range of A/H^2 ratios. For values of A/H^2 up to 1.0, the agreement appears very reasonable once the smoke layer has formed. Again, the empirically derived equation implicitly includes the transport lag. For A/H^2 of 10.0, the delay for a smoke layer to form is greater than that for smaller A/H^2 ratios such that reasonable agreement in smoke layer interface position is not achieved until approximately 800 seconds. The estimated transport lag is 206 seconds (Mowrer and Williamson [85]).

The value of z/H of 0.59 for the point of intersection of the various curves for the two equations is a constant, independent of the values for A, H, and Q. Thus, for values of $z/H >$ 0.59, Equation L.4a estimates a shorter time to attain a particular position of the smoke layer interface, whereas Equation 5.4.2.2 estimates a faster time for lesser values of z/H. Given the different exponents on the right side of the two equations, a general comparison is again possible only by solving for the times and expressing a ratio:

$$\frac{t_{eqn\ \text{L.4a}}}{t_{eqn\ 6.1.2.2}} = \left[\frac{(0.91)^{-0.69}}{4 k_v^{-0.6}} \right] \left[\frac{\left[\left(\dfrac{z}{H} \right)^{-2/3} - 1 \right]^{0.6}}{\left(\dfrac{z}{H} \right)^{-0.69}} \right] \qquad \text{(L.4b)}$$

The relationship of the time ratio for various normalized smoke layer depths, $(H - z)/H$ is provided in Figure L.4(b). In general, the agreement between the two predicted times for *t*-squared fires is much better than that for steady fires, with the predicted time using Equation L.4a being within 20 percent of that from Equation 5.4.2.2 for $(H - z)/H$ values from 0.26 to 0.80.



FIGURE L.4(a) Comparison of Algebraic Equations, Equations 5.4.2.2 and L.4a: *t*-Squared Fire.



FIGURE L.4(b) Comparison of Algebraic Equations, Equations 5.4.2.2 and L.4a: *t*-Squared Fire — Normalized Smoke Layer Depths.

As in the case of the steady fire, the time ratio is less than 1.0 for small normalized smoke layer depths. However, in this case, the time ratio does not exceed 1.0 until the normalized smoke layer depth is at least 0.40.

L.5 Large-Scale Experimental Programs in Tall Ceiling Spaces. The predictive capabilities of each equation can be examined by comparing the output to experimental data.

The predictive capability of Equation L.3a is examined by comparing the output to large-scale experimental data. Sources of the experimental data involving a range of ceiling heights from 2.4 m to 12.5 m as well as room sizes and fire scenarios are identified in Table L.5. Included in the table are the data sources referenced in the initial development of Equation 5.4.2.1 (Heskestad [10]). Two additional sets of experimental data have become available since the committee's initial analysis (Yamana and Tanaka [86]); Lougheed [87]). Comprehensive descriptions of the test programs are provided elsewhere (Hagglund, Jansson, and Nireus [6]; Mulholland et al. [38]; Cooper et al. [4]; Milke and Mowrer [82]). Because the two additional sets of data were collected from

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Table L.5 Summary of Full-Scale Experiments

Research Group	Fuel	Heat Release Rate	Dimension of Test Room	Measurements of Smoke Layer Position
New Data				
Yamana & Tanaka [86]	Methanol pool, 3.24 m^2	1.3 MW (steady)	30 m × 24 m; height, 26.3 m	Visual observations, first temperature rise
NRCC [87]	Ethanol pool, 3.6 m diameter	8 MW (steady)	55 m × 33 m; height, 12.5 m	First temperature rise
Committee Data				
Sandia, Test 7 [40]	Propylene burner, 0.91 m diameter	516 kW	18.3 m × 12.2 m; height, 6.1 m	First temperature rise, carbon dioxide concentration
Mulholland [38]	Acetylene burner	16.2 kW	3.7 m × 3.7 m; height, 2.4 m	Temperature rise, light obscuration
Cooper [4]	Methane burner	25 kW, 100 kW, 225 kW	89.6 m^2 room; corridor and lobby height, 2.4 m	Temperature rise
Hagglund [6]	Kerosene pool, 0.5 m^2	280 kW	5.62 m × 5.62 m; height, 6.15 m	Visual observations, first temperature rise

fires in spaces with significantly greater ceiling heights than in the initial sets of data, the new sets of data are of particular interest. The measured and predicted smoke layer positions as a function of time from the previous data and two new sets of data are presented in Figure L.5. The data identified as "the committee's" include all the data on which the committee based initial development of Equation 5.4.2.1. The new sets of data are identified separately. As indicated in Figure L.5, the smoke layer position from the data analyzed is between that measured by the National Research Council of Canada (NRCC) and the Building Research Institute (BRI). Thus, despite the differences in ceiling height, the new and initial sets of data appear to be reasonably similar. The graph labeled "NFPA 92" depicts the predictions of Equation 5.4.2.1. In general, agreement between the predictions from both Equations 5.4.2.1 and L.3a and the experimental data is very reasonable. Equation 5.4.2.1 provides a lower limit of the experimental data, including the new NRCC data. Equation L.3a appears to predict a midrange value of data.

Equations comparable to Equations 5.4.2.1 and L.3a can be derived for variable cross-sectional areas and for fires that follow a power law (e.g., *t*-squared fires). In addition, algebraic equations pertaining to a variety of smoke layer characteristics are available, including temperature, light obscuration, and species concentration (Milke and Mowrer [82]). These equations are applicable to evaluating transient conditions prior to operation of the smoke management system or equilibrium conditions with an operational smoke management system. Thus, a variety of algebraic equations are available and can serve as useful tools for relatively elementary designs or as checks of specific aspects of computer calculations for more complicated situations.



FIGURE L.5 Comparison of Smoke Layer Position, Experimental Data vs. Predictions.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Annex M Informational References

M.1 Referenced Publications. The documents or portions thereof listed in this annex are referenced within the informational sections of this standard and are not part of the requirements of this document unless also listed in Chapter 2 for other reasons.

M.1.1 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2010 edition.

NFPA 72®, *National Fire Alarm and Signaling Code*, 2010 edition.

NFPA 80, *Standard for Fire Doors and Other Opening Protectives*, 2010 edition.

NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, 2012 edition.

NFPA *101®*, *Life Safety Code®*, 2012 edition.

NFPA 204, *Standard for Smoke and Heat Venting*, 2012 edition.

NFPA 269, *Standard Test Method for Developing Toxic Potency Data for Use in Fire Hazard Modeling*, 2007 edition.

NFPA 909, *Code for the Protection of Cultural Resource Properties — Museums, Libraries, and Places of Worship*, 2010 edition.

NFPA 5000®, *Building Construction and Safety Code®*, 2012 edition.

M.1.2 Other Publications.

M.1.2.1 ASHRAE Publications. American Society of Heating, Refrigerating, and Air Conditioning Engineers, Inc., 1791 Tullie Circle, NE, Atlanta, GA 30329-2305.

ASHRAE *Handbook of Fundamentals*, 2001.

Principles of Smoke Management, by J. Klote and J. A. Milke, ASHRAE/SFPE, 2002.

M.1.2.2 ASME Publications. American Society of Mechanical Engineers, Three Park Avenue, New York, NY 10016-5990.

ASME/ANSI A17.1, *Safety Code for Elevators and Escalators*, 2004.

M.1.2.3 ASTM Publications. ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959.

ASTM E 1321, *Standard Test Method for Determining Material Ignition and Flame Spread Properties*, 1997.

ASTM E 1354, *Standard Test Method for Heat and Visible Smoke Release Rates for Materials and Products Using an Oxygen Consumption Calorimeter*, 1997.

M.1.2.4 SFPE Publications. Society of Fire Protection Engineers, 7315 Wisconsin Avenue, Suite 1225 W, Bethesda, MD 20814.

Handbook of Fire Protection Engineering, 2002.

SFPE *Engineering Guide to Performance-Based Fire Protection Analysis and Design of Buildings*, 2000.

M.1.2.5 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062-2096.

ANSI/UL 555, *Standard for Fire Dampers*, 2006, Revised 2010.

ANSI/UL 555S, *Standard for Smoke Dampers*, 1999, Revised 2010.

M.1.2.6 Other Publications.

1. Bennetts, I. D., Culton, M., Dickerson, M. L., Lewins, R., Poh, K. W., Poon, S. L., Ralph, R., Lee, A. C., Beever, P. F., Cooper, R. J., Haggar, P. I., Moore, I. P., Ramsay, G. C., and Timms, G. R., Simulated Shopping Centre Fire Tests, BHPR/SM/R.G/062, Broken Hill Proprietary Company Limited, Australia, 1997.

2. Beyler, C., "Fire Plumes and Ceiling Jets," *Fire Safety Journal*, 11, pp. 63–65, 1986.

3. CIBSE. "Relationships for smoke control calculations," Technical Memoranda TM19, Chartered Institution of Building Services Engineers. London, UK, 1995.

4. Cooper, L. Y., Harkleroad, M., Quintiere, J., and Rinkinen, W., "An Experimental Study of Upper Hot Layer Stratification in Full-Scale Multiroom Fire Scenarios," Paper 81-HT-9, the American Society of Mechanical Engineers, 1981.

5. Emmons, H., "The Use of Fire Test Data in Fire Models," The Home Fire Project Technical Report No. 78, Harvard University, Division of Applied Sciences, Februrary 1989.

6. Hagglund, B., Jansson, R., and Nireus, K., *Smoke Filling Experiments in a 6×6×6 Meter Enclosure*, FOA Rapport C20585-06, Forsavrets Forskningsanstalt, Sweden, September 1985.

7. Hansell, G. O., and Morgan, H. P., Design Approaches for Smoke Control in Atrium Buildings, BRE 258, Borehamwood, UK; Building Research Establishment, 1994.

8. Heskestad, G., "Determination of Gas Venting Geometry and Capacity of Air Pollution Control System at Factory Mutual Research Center," FMRC Ser. No. 20581, Fire Mutual Research Corp., Norwood, MA, November 1972.

9. Heskestad, G., "Fire Plumes, Flame Height, and Air Entrainment," Chapter 2-1, *SFPE Handbook of Fire Protection Engineering*, DiNenno et al. editors, National Fire Protection Association, Quincy, MA, 2002.

10. Heskestad, G., "Letter to the Editor," *Fire Technology*, 27, 2, pp. 174–185, May 1991.

11. Heskestad, G., Sprinkler/Hot Layer Interaction, NISTGCR-91-590, National Institute of Standards, Gaithersburg, MD, 1991.

12. Heskestad, G. and Delichatsios, M. A., *Environments of Fire Detectors—Phase 1 Effect of Fire Size, Ceiling Height and Materials*. Volume I — Measurements (NBS-GCR-77-86), Volume II - Analysis (NBS-GCR-77-95), National Bureau of Standards (now National Institute of Standards and Technology), Gaithersburg, MD, 1977.

13. Klote, J. H., "A Method for Calculation of Elevator Evacuation Time," *Journal of Fire Protection Engineering*, Vol. 5, 1993, pp. 83–96.

14. Klote, J. H., "Design of Smoke Control Systems for Areas of Refuge," ASHRAE Transactions, American Society of Heating, Refrigerating, and Air Conditioning Engineers, Atlanta, GA, Vol. 99, Part 2, 1993b, pp. 793–807.

15. Klote, J. H., "Design of Smoke Control Systems for Elevator Fire Evacuation Including Wind Effects," 2nd Symposium on Elevators, Fire and Accessibility, Baltimore, ASME, New York, NY, 1995, pp. 59–77.

16. Klote, J. H., D. M. Alvord, B. M. Levin, and N. E. Groner, "Feasibility and Design Considerations of Emergency Evacuation by Elevators," NISTIR 4870, National Institute of Standards and Technology, Gaithersburg, MD, 1992.

17. Klote, J. H., and E. Braun, "Water Leakage of Elevator Doors with Application to Building Fire Suppression," NISTIR 5925, National Institute of Standards and Technology, Gaithersburg, MD, 1996.

18. Klote, J. H., S. P. Deal, E. A. Donoghue, B. M. Levin, and N. E. Groner, "Fire Evacuation by Elevators," *ElevatorWorld*, 1993, pp. 66–75.

19. Klote, J. H., B. M. Levin, and N. E. Groner, "Feasibility of Fire Evacuation by Elevators at FAA Control Towers," NISTIR 5445, National Institute of Standards and Technology, Gaithersburg, MD, 1994.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

20. Klote, J. H., B. M. Levin, and N. E. Groner, "Emergency Elevator Evacuation Systems," 2nd Symposium on Elevators, Fire and Accessibility, Baltimore, ASME, New York, NY, 1995, pp. 131–150.

21. Klote, J., and Milke, J., "Principles of Smoke Management," ASHRAE/SFPE, Atlanta, GA, 2002.

22. Law, M., "A Note on Smoke Plumes from Fires in Multi-Level Shopping Malls," *Fire Safety Journal*, 10, p. 197, 1986.

23. Lougheed, G. D., "Expected Size of Shielded Fires in Sprinklered Office Buildings," ASHRAE Transactions, Volume 103, Part 1, 1997, p. 395.

24. Lougheed, G. D., and Hadjisophocleous, G. V., "Investigation of Atrium Smoke Exhaust Effectiveness," ASHRAE Transactions 103, pp. 1–15, 1997.

25. Lougheed, G. D., Hadjisophocleous, G. V., McCartney, C., and Taber, B. C., "Large-Scale Physical Model Studies for an Atrium Smoke Exhaust System," ASHRAE Transactions 104, 1999.

26. Lougheed, G. D., J. R. Mawhinney, and J. O'Neill, "Full-Scale Fire Tests and the Development of Design Criteria for Sprinkler Protection of Mobile Shelving Units," *Fire Technology*, Vol. 30, 1994, pp. 98–133.

27. Lougheed, G. D., and McCartney, C. J., "Balcony Spill Plumes: Full-Scale Experiments, Part 2 (RP-1247)," ASHRAE Transactions, to be published.

28. Lougheed, G. D., McCartney, C. J., and Gibbs, E., "Balcony Spill Plumes Final Report RP-1247," ASHRAE, Atlanta, Georgia, 2007.

29. Madrzykowski, D., and Vettori, R., "A Sprinkler Fire Suppression Algorithm," *Journal of Fire Protection Engineering*, 4, pp. 151–164, 1992.

30. Marshall, N. R., and Harrison, R., "Experimental studies of thermal spill plumes, Occasional Paper, OP1," Building Research Establishment, Garston, UK, 1996.

31. McCartney, C. J., Lougheed, G. D. and Weckman, E.J., "CFD Investigation of Balcony Spill Plumes in Atria," ASHRAE Transactions, to be published.

32. Modak, A. T., and Alpert, R. L., *Influence of Enclosures on Fire Growth — Volume I: Guide to Test Data*, FMRC 0A0R2.BU-8, Factory Mutual Research, Norwood, MA, 1978.

33. Morgan, H. P., *Smoke Control Methods in Enclosed Shopping Complexes of One or More Storeys: A Design Summary*, Building Research Establishment, 1979.

34. Morgan, H. P., Ghosh, B. K., Garrard, G., Pamlitschka, R., De Smedt, J. C., and Schoonbaert, L. R. "Design Methodologies for Smoke and Heat Exhaust Ventilation," Construction Research Communications Ltd, London, UK, 1999.

35. Morgan, H. P., and Marshall, N. R., *Smoke Control Measures in Covered Two-Story Shopping Malls Having Balconies and Pedestrian Walkways*, BRE CP 11/79, Borehamwood, 1979.

36. Mudan, K. S., and Croce, P. A., "Fire Hazard Calculations for Large Open Hydrocarbon Fires," *SFPE Handbook of Fire Protection Engineering*, National Fire Protection Association, Quincy, MA, 1988.

37. Mulholland, G., Section 1/Chapter 25 "Smoke Production and Properties," *SFPE Handbook of Fire Protection Engineering*, National Fire Protection Association, Quincy, MA, 1988.

38. Mulholland, G., Handa, T., Sugawa, O., and Yamamoto, H., "Smoke Filling in an Enclosure," Paper 81-HT-8, the American Society of Mechanical Engineers, 1981.

39. Nii, Nitta, Harada, and Yamaguchi, "Air Entrainment into Mechanical Smoke Vent on Ceiling," *Fire Safety Science*, Proceedings of the Seventh International Symposium, pp.729–740, 2003.

40. Nowler, S. P., *Enclosure Environment Characterization Testing for the Base Line Validation of Computer Fire Simulation Codes*, NUREG/CR-4681, SAND 86-1296, Sandia National Laboratories, March 1987.

41. Peacock, R. D., Davis, S., and Babrauskas, V., "Data for Room Fire Model Comparisons," *Journal of the National Institute of Standards and Technology*, 96, 4, July 1991.

42. Purser, D. A., "Toxicity Assessment of Combustion Products," *SFPE Handbook of Fire Protection Engineering*, National Fire Protection Association, Quincy, MA, 2002.

43. Quintiere, J. G., *Fire Safety Journal*, 1, 15, 1989.

44. Quintiere, J. G., McCaffrey, B. J., and Kashiwagi, T., *Combustion Science and Technology*, 18, 1978.

45. Shaw, C. Y., J. T. Reardon, and M. S. Cheung, "Changes in Air Leakage Levels of Six Canadian Office Buildings," *ASHRAE Journal*, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, 1993.

46. Soderbom, J., "Smoke Spread Experiments in Large Rooms. Experimental Results and Numerical Simulations," Statens Provningsanstalt, SR Report 1992:52, Swedish National Testing and Research Institute, Boras, Sweden, 1992.

47. Spratt, D., and Heselden, A. J. M., "Efficient Extraction of Smoke from a Thin Layer Under a Ceiling," Fire Research Note No. 1001, February 1974.

48. Steckler, K. D., Baum, H. R., and Quintiere, J. G., 21st Symposium (Int.) on Combustion, pp. 143–149, 1986.

49. Tamura, G. T., *Smoke Movement and Control in High-Rise Buildings*, 1994 edition.

50. Tamura, G. T., and C. Y. Shaw, "Studies on ExteriorWall Air Tightness and Air Infiltration of Tall Buildings," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 82, Part 1, 1976, pp. 122–134.

51. Tamura, G. T., and C. Y. Shaw, "Air Leakage Data for the Design of Elevator and Stair Shaft Pressurization Systems," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 82, Part 2, 1976b, pp. 179–190.

52. Tamura, G. T., and C. Y. Shaw, "Experimental Studies of Mechanical Venting for Smoke Control in Tall Office Buildings," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 86, Part 1, 1978, pp. 54–71.

53. Tamura, G. T., and A. G.Wilson, "Pressure Differences for a Nine-Story Building as a Result of Chimney Effect and Ventilation System Operation," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 72, Part 1, 1966, pp. 180–189.

54. Tewarson, A., "Generation of Heat and Chemical Compounds in Fires," *SFPE Handbook of Fire Protection Engineering*, 2nd ed., P. J. DiNenno (ed.), National Fire Protection Association, Quincy, MA, 2002.

55. Babrauskas, V., "Heat Release Rates," *SFPE Handbook of Fire Protection Engineering*, 3rd ed., P. J. DiNenno (ed.), National Fire Protection Association, Quincy, MA, 2002.

56. Babrauskas, V., and Krasny, J., *Fire Behavior of Upholstered Furniture*, NBS Monograph 173, National Bureau of Standards (now National Institute of Standards and Technology), November 1985.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

57. Nelson, H. E., and Forssell, E. W., "Use of Small-Scale Test Data in Hazard Analysis," Proceedings of the 4th International Symposium of IAFSS, Ottawa, Canada, 1994.

58. Hirsch, C., *Numerical Computation of Internal and External Flows, Vol. 1: Fundamentals of Numerical Discretization*,Wiley, New York, 1988.

59. Sako, S., and Hasemi, Y., "Response Time of Automatic Sprinklers Below a Confined Ceiling," Fire Safety Science-Proceedings of the Second International Symposium, Hemisphere Publishing Corporation, New York, p. 613, 1989.

60. Carslaw, H. S., and Jaeger, J. C., *Conduction of Heat in Solids*, Oxford University, Oxford, 1959.

61. Tien, C. L., Lee, K. Y., and Stretton, A. J., "Radiation Heat Transfer," *SFPE Handbook of Fire Protection Engineering*, 2nd ed., P. J. DiNenno (ed.), National Fire Protection Association, Quincy, MA, 2002.

62. Nelson, H. E., *An Engineering Analysis of the Early Stages of Fire Development—The Fire at the Du Pont Plaza Hotel and Casino-December 31, 1986*, Report NBSIR 87-3560, 1987.

63. Borisenko, A. I., and Tarapov, I. E., *Vector and Tensor Analysis with Applications*, Translated by R. A. Silverman, Dover, New York, 1968.

64. Hay, G. E., *Vector and Tensor Analysis*, Dover, New York, 1953.

65. Welty, J. R.,Wicks, C. E., and Wilson, R. E., *Fundamentals of Momentum, Heat and Mass Transfer*, John Wiley & Sons, New York, 1976.

66. Schetz, J. A., *Boundary Layer Analysis*, Prentice Hall, Englewood Cliffs, NJ, 1993.

67. Schlichting, H., *Boundary Layer Theory*, 4th ed., Kestin, J. translator, McGraw, New York, 1960.

68. Sherman, F. S., *Viscous Flow*, McGraw, New York, 1990.

69. Aris, R., *Vectors, Tensors, and the Basic Equations of Fluid Mechanics*, Dover, New York, 1962.

70. Anderson, D. A., Tannehill J. C., and Pletcher, R. H., *Computational Fluid Mechanics and Heat Transfer*, Hemisphere, New York, 1984.

71. Abbott, M. B., and Basco, D. R., *Computational Fluid Dynamics: An Introduction for Engineers*, Wiley, New York, 1989.

72. Hoffmann, K. A., *Computational Fluid Dynamics for Engineers, Engineering Education System*, Austin, TX, 1989.

73. Markatos, N. C., *The Mathematical Modelling of Turbulent Flows, Applied Mathematical Modeling*, Vol. 10, No. 3, pp. 190–220, 1986.

74. Hirsch, C., *Numerical Computation of Internal and External Flows, Vol. 2: Computational Methods for Inviscid and Viscous Flows*, Wiley, New York, 1990.

75. Kumar, S., *Mathematical Modelling of Natural Convection in Fire — A State of the Art Review of the Field Modelling of Variable Density Turbulent Flow, Fire and Materials*, Vol. 7, No. 1, pp. 1–24, 1983.

76. McGrattan, K. B., et al., *Fire Dynamics Simulator – Technical Reference Guide,* NISTIR 6467, National Institute of Standards and Technology, Gaithersburg, MD, 2000.

77. McGrattan, K. B., and Forney, G. P., *Fire Dynamics Simulator– User's Manual,* NISTIR 6469, National Institute of Standards and Technology, Gaithersburg, MD, 2000.

78. Friedman, R., *An International Survey of Computer Models for Fire and Smoke, Journal of Fire Protection Engineering*, Vol. 4, No. 3, pp. 81–92, 1992.

79. DiNenno, P. J., ed., *SFPE Handbook of Fire Protection Engineering*, National Fire Protection Association, Quincy, MA, 2002.

80. Drysdale, D. D., *An Introduction of Fire Dynamics*, John Wiley & Sons, New York, 1985.

81. Nelson, H. E., and Mowrer, F., "Emergency Movement," Chapter 3-14, *SFPE Handbook of Fire Protection Engineering*, DiNenno et al. editors, National Fire Protection Association, Quincy, MA, 2002.

82. Milke, J. A., and Mowrer, F. W., "An Algorithm for the Design Analysis of Atrium Smoke Management Systems," FP93-04, Department of Fire Protection Engineering, University of Maryland at College Park, May 1993

83. Morton, B. R., Taylor, Sir Geoffrey, and Turner, J. S., "Turbulent Gravitational Convection from Maintained and Instantaneous Sources," Proc. Royal Society A 234, 1–23, 1956.

84. Walton, W. D., and Notorianni, "A Comparison of Ceiling Jet Temperatures Measured in an Aircraft Hangar Test Fire with Temperatures Predicted by the DETECT and LAVENT Computer Models," NISTIR (Draft), Building and Fire Research Laboratory, National Institute of Standards and Technology, August 1992.

85. Mowrer, F.W., and Williamson, R. B., "Estimating Room Temperatures from Fires along Walls and in Corners," *Fire Technology 23*, 2, pp. 133–145, May 1987.

86. Yamana, T., and Tanaka, T. "Smoke Control in Large Scale Spaces—Part 2: Smoke Control in Large Scale Spaces," *Fire Science and Technology*, 5, 1, pp. 41–54, 1985.

87. Personal Communication, G. D. Lougheed, National Research Council of Canada, March 20, 1991.

M.2 Informational References. The following documents or portions thereof are listed here as informational resources only. They are not a part of the requirements of this document.

Alpert, R. L., and Ward, E. J., *Evaluating Unsprinklered Fire Hazards*, FMRC No. 01836.20, Norwood, MA, Factory Mutual Research Corporation, pp. 46 and 48, August 1982.

Bullen, M. C., and Thomas, P. A, "Compartment Fires with Non-Cellulosic Fuels; 17th Symposium (International) on Combustion," The Combustion Institute, pp. 1139–1148, 1979.

CIBSE, Relationships for Smoke Control Calculations, Technical Memoranda TM19, The Chartered Institution of Building Services Engineers, London, UK, 1995.

Cooper, L., *Smoke and Heat Venting, SFPE Handbook of Fire Protection Engineering*, National Fire Protection Association, Quincy, MA, pp. 3-160–3-173, 2002.

Cooper, L. Y., Harkleroad, M., Quintiere, J., and Rinkinen, W., "An Experimental Study of Upper Hot Layer Stratification in Full-Scale Multiroom Fire Scenarios," *Journal of Heat Transfer*, 104, pp. 741–749, 1982.

Emmons, H., "The Use of Fire Test Data in Fire Models," The Home Fire Project Technical Report No. 78, Harvard University, Division of Applied Sciences, February 1989.

Fang, J. B., and Breese, J. N., *Fire Development in Residential Basement Rooms*, NBSIR 80-2120, National Bureau of Standards, October 1980.

Ghosh, B. K., "Fires in Real Scenarios," International Symposium on Fire Science and Technology, ISFST 1997, Seoul, Korea, pp. 439–447, 1997.

Gottuk, D., Roby, R., and Eglo, C., "A Study of Carbon Monoxide and Smoke Yields from Compartment Fires with External Burning; 24th Symposium (International) on Combustion," The Combustion Institute, pp. 1729–1735, 1992.

Hadjisophocleous, G. V., Lougheed, G. D., and Cao, S., "Numerical Study of the Effectiveness of Atrium Smoke Exhaust Systems," ASHRAE Transactions 104, 1999.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Hansell, G. O., Morgan, H., and Marshall, N. R., "Smoke Flow Experiments in a Model Atrium," BRE Occasional Paper, July 1993.

Heskestad, G., *Engineering Relations for Fire Plumes*, SFPE TR 82-8, Boston, Society of Fire Protection Engineers, 1982.

Heskestad, G., *Inflow of Air Required at Wall and Ceiling Apertures to Prevent Escape of Fire Smoke*, FMRC J.I. 0Q4E4.RU, Factory Mutual Research Corporation, July 1989.

Heskestad, G., and Bill, R. G., Jr., "Modeling of Thermal Responsiveness of Automatic Sprinklers," *Fire Safety Science — Proceedings of the Second International Symposium*, Hemisphere Publishing Corporation, New York, p. 603, 1989.

Heskestad, G. and Delichatsios, M. A., "The Initial Convective Flow in Fire," Seventeenth Symposium (International) on Combustion, the Combustion Institute, Pittsburgh, PA, p. 1113, 1979.

Heskestad, G. and Delichatsios, M. A., "Update: The Initial Convective Flow in Fire," *Fire Safety Journal*, 15, p. 471, 1989.

Heskestad, G., and Hill, J. P., "Experimental Fire in Multiroom/Corridor Enclosures," FMRC J.I. 0J2N8.RU, Factory Mutual Research Corporation, October 1985.

Hinkley, P. L., Hansell, G. O., Marshall, N. R., and Harrison, R., "Experiments at the Multifunctioneel Training Centrum, Ghent, on the Interaction Between Sprinklers and Smoke Venting," Building Research Establishment Report, 1992.

Kanury, A. M., "Ignition of Liquid Fuels," *SFPE Handbook of Fire Protection Engineering*, 2nd ed., P. J. DiNenno (ed.), National Fire Protection Association, Quincy, MA, 1995.

Klote, J. H., and X. Bodart, "Validation of Network Models for Smoke Control Analysis," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 91, Part 2B, 1985, pp. 1134–1145.

Law, M., "Air Supported Structures: Fire and Smoke Hazards," *Fire Prevention*, 148, 1982.

Morgan, H. P., "Comments on a Note on Smoke Plumes from Fires in Multi-Level Shopping Malls," *Fire Safety Journal*, 12, p. 83, 1987.

Morgan, H. P., and Hansell, G. O., "Fire Sizes and Sprinkler Effectiveness in Offices-Implications for Smoke Control Design," *Fire Safety Journal*, volume 8, no. 3, pp. 187–198, 1985.

Mulholland, G., Handa, T., Sugawa, O., and Yamamoto, H., "Smoke Filling in an Enclosure," *Fire Science and Technology*, 1, p. 1, 1981.

Newman, J. S., and Hill, J. P., "Assessment of Exposure Fire Hazard to Cable Trays," NP-1675 Research Project 1165-1-1, Prepared for Electric Power Research Institute by Factory Mutual Research Corporation, January 1981.

Peacock, R. D., and Babrauskas, V., "Analyses of Large-Scale Fire Test Data," *Fire Safety Journal*, 17, pp. 387-414.

Spratt, D., and Heselden, A. J. M., "Efficient Extraction of Smoke from a Thin Layer Under a Ceiling," UK Joint Fire Research Organization, Fire Research Note No. 1001, 1994.

Thomas, P. H., "On the Upward Movement of Smoke and Related Shopping Mall Problems," *Fire Safety Journal*, 12, p. 191, 1987.

Thomas, P. H., Heselden, J. M., and Law, M., "Fully-Developed Compartment Fires — Two Kinds of Behavior," Fire Research Technical Paper No. 18.

Thomas, P. H., Hinckley, P. L., Theobald, C. R., and Sims, D. L., "Investigations into the Flow of Hot Gases in Roof Venting," Fire Research Technical Papers No. 7, HMSO, London, 1963.

Turner, J. S., *Buoyancy Effects in Fluids*, Cambridge University Press, Cambridge, 1973.

White, F. M. *Viscous Fluid Flow*, McGraw, New York, 1974.

Walton, G. N., "CONTAM96 User Manual," NISTIR-6056, National Institute of Standards and Technology, Gaithersburg, MD, 1997.

Wray, C. P., and G. K. Yuill, "An Evaluation of Algorithms for Analyzing Smoke Control Systems," ASHRAE Transactions, American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, Vol. 99, Part 1, 1993, pp. 160–174.

Yamana, T., and Tanaka, T., "Smoke Control in Large Scale Spaces," Fire Science and Technology, 5, p. 41, 1985.

Zukoski, E. E., Kubota, T., and Cetegen, B., "Entrainment in Fire Plumes," *Fire Safety Journal*, 3, pp. 107–121, 1980/1981.

M.3 References for Extracts in Informational Sections.

NFPA 204, *Standard for Smoke and Heat Venting*, 2012 edition.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Index

Copyright © 2011 National Fire Protection Association. All Rights Reserved.

The copyright in this index is separate and distinct from the copyright in the document that it indexes. The licensing provisions set forth for the document are not applicable to this index. This index may not be reproduced in whole or in part by any means without the express written permission of NFPA.

-A-

Acceptance testing ..... 8.4, A.8.4.1 to A.8.4.6.6.1, Annex J
- Measurement locations 8.4.3, A.8.4.3
- Procedures ..... 8.4.4, A.8.4.4.1 to A.8.4.4.4(2)
- Smoke containment systems ..... 8.4.6, A.8.4.6.1.4 to A.8.4.6.6.1
- Smoke management systems in large-volume spaces 8.4.5, A.8.4.5
- Stairwell pressurization systems 8.4.6.3
- Test parameters 8.4.2, A.8.4.2
- Zoned smoke-control systems 8.4.6.4, A.8.4.6.4

Activation of smoke control systems .....*see* Smoke control systems, Activation and deactivation

Airflow ..... 4.4.4, 8.4.5(1), A.4.4.4.1 to A.4.4.4.3
- Communicating spaces 4.4.4.2, A.4.4.4.2
- Elevator pressurization A.4.7
- Makeup air 4.4.4.1, A.4.4.4.1
- Modulating supply F.3
- Opposed ..... 4.3.2(6), 5.10, A.4.3.2(6)
- Periodic testing 8.6.3

Air supply fans 4.6.3, 6.4.5.2.2, A.4.6.3.1, F.1, F.3, G.2

Air supply source location 4.6.2

Alarm systems
- Acceptance testing 8.4.6.4.4.1, 8.4.6.4.4.6, 8.4.6.7.1.3, A.8.4.6.4.4.6
- Coordination with smoke-control system 6.4.2, 6.4.4.4.2.2, 6.4.6.2.1, 6.4.7.4

Animal facilities, ventilation systems for G.11

Approved (definition) 3.2.1, A.3.2.1

Atriums A.5.2.1
- Computer-based models for ..... Annex C
- Definition 3.3.1

Authority having jurisdiction (definition) 3.2.2, A.3.2.2

Automatic system activation
- Acceptance tests ..... 8.4.4.4(2), 8.4.4.7, A.8.4.4.4(2)
- Smoke control 4.5.2, 6.4.4.4.1
  - Manual override of 6.4.4.4.2.2, 8.4.7.2
  - Zoned system 6.4.6.2, A.6.4.6.2.1
- Stairwell pressurization 6.4.5.1, A.6.4.5.1.1

-B-

Barometric dampers ..... F.4(1)

Building equipment and controls ..... Chap. 6; *see also* Dampers; Heating, ventilating, and air conditioning (HVAC) systems
- Energy management 6.5
- Materials 6.6, A.6.6.3
- Smoke control systems 6.4, A.6.4
  - Coordination 6.4.2
  - HVAC system 6.4.2, 6.4.3, A.6.4.3
  - Smoke-control system activation/deactivation .... 6.4.3 to 6.4.5, A.6.4.3 to A.6.4.5.1.1
  - Stair pressurization system 6.4.5, A.6.4.5.1.1
  - Verification 6.4.7, A.6.4.7
  - Zoned smoke-control systems 6.4.6, A.6.4.6.2.1, A.6.4.6.3

Building inspections, preliminary 8.2

Buoyancy of hot smoke 4.4.2.1.4

By-pass dampers F.3

-C-

Calculation procedures ..... Chap. 5, C.1.3.1; *see also* Equations
- Complex geometries 5.9, A.5.9
- Cross-sectional geometries, varying 5.9, A.5.9, C.1.3.2
- Design approaches ..... 5.1, 7.2.2(8), A.5.1
  - Algebraic equations 5.1.1, A.5.1.1
  - Compartment fire models 5.1.3, A.5.1.3
  - Scale modeling 5.1.2, A.5.1.2
- Design fire ..... 5.2, A.5.2.1 to A.5.2.5
  - Steady fire ..... 5.2.2(1), 5.2.3
  - Unsteady fire ..... 5.2.2(2), 5.2.4, A.5.2.4.4
- Exhaust inlets, number of 5.6, A.5.6
- Height of first indication of smoke with no smoke exhaust operating 5.4.2, A.5.4.2.1, A.5.4.2.2
- Mass consumption 5.3
- Scale modeling 5.1.2, 5.11, A.5.1.2, A.5.11
- Smoke layer calculations ..... 5.4, A.5.4.1 to A.5.4.2.2
- Smoke mass production, rate of ..... 5.5, A.5.5.1.1 to A.5.5.5
- Volumetric flow rate 5.7, A.5.7

Ceiling jet C.1.2
- Definition 3.3.2, A.3.3.2

Centralized multifloor HVAC system G.3, G.7

Centrifugal supply fans 4.6.3.2

CFD (computational fluid dynamics) models 5.1.3, A.5.1.3, C.2

Combination smoke-control systems 4.9, 8.4.6.7, A.4.9

Communicating spaces ..... 4.1.1(2), 4.2.2, 4.3.2, A.4.3.2
- Airflow 4.4.4.2, A.4.4.4.2
- Definition 3.3.17.3, A.3.3.17.3
- Fire locations within 4.4.3
- Smoke spread management ..... 5.10.1 to 5.10.3

Compartment fire models 5.1.3, A.5.1.3

Compensated systems
- Definition 3.3.18.1
- Stairwell pressurization ..... F.2 to F.4

Component system testing 8.3, A.8.3

Computer room ventilation G.10

Covered malls A.5.2.1
- Computer-based models for ..... Annex C
- Definition 3.3.3

-D-

Dampers
- Barometric ..... F.4(1)
- By-pass F.3
- Fire G.3
- Materials 6.6.3, A.6.6.3
- Motor-operated ..... F.4(2), I.2.2, I.2.3
- Relief, duct system F.3, G.2
- Smoke ..... 6.2.3, 6.3, 7.2.2(10), 8.4.4.8, 8.4.5(2), A.6.4.4.1.4, A.6.4.7, G.3, H.1, I.2
  - Definition 3.3.19
  - Response time 6.4.4.5.2, 6.4.4.5.3
- Status indicators ..... H.1(2), H.1(5)
- Testing 8.6.1, A.8.6.1, I.2.2, I.2.3, I.3.1

Decay phase, fire 5.2.4, A.5.2.4.4

Dedicated smoke control systems .....*see* Smoke control systems

Definitions ..... Chap. 3

Design documentation ..... Chap. 7, J.2

Design fires ..... 5.2, A.5.2.1 to A.5.2.5, C.1.4

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Design fundamentals ..... Chap. 4
Additional objectives ..... Annex D
Approaches ..... 4.3, 7.2.2(3)
Basis 4.2, A.4.2.1
Combination of smoke control systems 4.9, A.4.9
Criteria 4.4, A.4.4.1
Detection systems ..... 4.5.3.2(1)
Objectives ..... 4.1, 7.2.2(2), A.4.1.1. A.4.1.2
System operation ..... 4.5, 7.2.2(13), A.4.5.1.1 to A.4.5.4.1
Design pressure difference ..... 4.2.1.1, 4.4.2, A.4.4.2.1.1, A.4.4.2.2; *see also* Pressure differences
Definition 3.3.4, A.3.3.4
Detection systems design ..... 4.5.3.2(1), 6.4.4.1.5, A.6.4.4.1.5; *see also* Fire detectors; Smoke detectors
Documentation
Design ..... Chap. 7, J.2
Testing ..... 7.3.1(2), 7.3.3, 8.5, A.8.5.1
Doors 8.4.5, A.8.4.5
Closed 8.4.6.4.2.1, 8.4.6.4.4.3, A.4.4.4.3
Door-opening forces 4.4.4.1.3, 8.4.4.5, 8.4.4.6, 8.4.6.2, A.4.4.2.2, A.8.4.6.2
Elevator A.4.4.7
Open ..... 4.6.1, 8.4.6.1.2, 8.4.6.1.4, 8.4.6.4.4.5, A.4.4.4.1, A.4.4.4.3, A.4.6.1, A.8.4.6.1.4, F.1 to F.3
Periodic testing 8.6.1, A.8.6.1
Pressure differences across ..... *see* Pressure differences
Self-closing/automatically closing 4.11, A.4.11
Smoke containment system test ..... 8.4.6.1.1, 8.4.6.1.2, 8.4.6.1.4, 8.4.6.2, 8.4.6.4.4.3 to 8.4.6.4.4.5, A.8.4.6.1.4, A.8.4.6.2
Stairwell overpressure relief, used for F.4
Draft curtains 5.5.2.4
Definition 3.3.5
Duct systems ..... 6.6.2, 7.2.2(9), F.3, G.2, H.1
Dual duct systems G.6
Leakage testing, HVAC systems ..... Annex I
Materials 6.6.3, A.6.6.3
Penetrations, leakage through ..... I.1(7)
Smoke detectors in 6.4.4.4.1.3, 6.4.4.6.13
Status indicators ..... H.1(5)
Duration, smoke control system 4.5.4, A.4.5.4.1

-E-

Egress analysis ..... 4.2.2(6), 4.5.1.2, 4.5.4.1(1), A.4.5.1.2, D.1.1
Electric services installation 6.7, I.1
Elevators ..... 1.2.1(1), A.4.4.4.3
Areas of refuge adjacent to 4.8.3.2
Pressurization systems 4.7, A.4.7
Elevator smoke control systems ..... 4.3.1(3), A.4.9
Combined with other systems 8.4.6.7.3
Testing 8.4.6.5, 8.4.6.7.3, A.8.4.6.5
Hoistway pressurization systems 8.4.6.5.1, 8.4.6.7.3.4, 8.4.6.7.3.6
Lobby pressurization systems ..... 8.4.6.5.2, 8.4.6.7.3.2, 8.4.6.7.3.5, 8.4.6.7.3.6, A.4.7, A.8.4.6.5.2.1(C)
End-to-end verification A.6.4.7
Definition 3.3.6
Energy management systems 6.5
Equations
Comparison of ..... Annex L
ASET-based equations L.2
Steady fires L.3
Tall ceiling spaces, large-scale experimental programs in L.5
t-squared (t^2) L.4
Example problems illustrating use of ..... Annex K
Zone fire model C.1.4
Equivalency to standard 1.4
Evacuation of occupants ..... 1.2.1(2), 4.4.2.1.3, 4.8.3.1, A.4.7
Exhaust, smoke ..... *see* Smoke exhaust
Exhaust fans ..... *see* Fans, Exhaust

-F-

Fan/coil units G.4, I.3.1
Fan motor controllers 6.4.4.6.13
Fan-powered terminals G.8
Fans ..... 4.4.4.1, 7.2.2(9), 8.4.4.8, 8.4.5(2), A.4.4.4.1.4, A.6.4.4.1.4, A.6.4.7
Air supply 4.6.3, 6.4.5.2.2, A.4.6.3.1, F.1, F.3, G.2, I.2
Centralized multifloor systems G.3
Constant-volume G.8
Exhaust ..... 5.6, 6.2.4, 6.6.3, A.4.4.4.1, A.5.6, A.6.2.4, A.6.6.3, F.4(4), G.2
Materials 6.6.3, A.6.6.3
Other types 4.6.3.2
Propeller 4.6.3.1, A.4.6.3.1
Response time 6.4.4.5.2
Return I.2.1, I.2.2
Single speed F.1
Stair pressurization 4.6.3, 6.4.5.1, 6.4.5.2.2, 6.4.5.4.2, A.4.6.3.1, A.6.4.5.1.1
Status indicators ..... 6.4.4.6.6, H.1(2), H.1(5)
Supply 6.2.4, A.6.2.4
Testing 8.6.1, A.8.6.1
Fire control A.4.2.1
Fire detectors ..... 6.4.4.1.1 to 6.4.4.1.3, 6.4.4.1.5, 6.4.4.4.2.2, A.6.4.4.1.1 to A.6.4.4.1.3, A.6.4.4.1.5
Fire fighters' smoke control station (FSCS) ..... 6.4.2, 6.4.4.6, A.6.4.4.6.2 to A.6.4.4.6.4.1
Considerations for ..... Annex H
Definition 3.3.8, A.3.3.8
Smoke control system activation 6.4.4.3, A.6.4.4.3.1, A.6.4.4.3.2
Stairwell pressurization system 6.4.5.4
Tests of 8.4.7
Fire location, large volume space/communication space 4.4.3
Fires
Design ..... 5.2, A.5.2.1 to A.5.2.5, C.1.4
Fuel limited 5.2.3.2, 5.2.4.2.2
Definition 3.3.7.1
Limiting size of A.4.8
Pool B.5.1
Sprinkler controlled (definition) 3.3.7.2
Steady ..... 5.2.2(1), 5.2.3, 5.2.4, 5.3.1, 5.4.2.1, A.5.2.4.4, A.5.4.2.1, B.3, C.1.4, L.3
Definition 3.3.7.3
t-squared (t^2) ..... 5.2.4.1(2), 5.2.4.2, 5.3.2, B.3, L.4
Definition 3.3.7.4
Unsteady ..... 5.2.2(2), 5.2.4, 5.4.2.2, A.5.2.4.4, A.5.4.2.2, C.1.4
Definition 3.3.7.5
Ventilation limited 5.5.3.1, A.5.5.3.1
Definition 3.3.7.6
Fire suppression systems 4.4.5, A.4.4.5, A.5.2.1
First indication of smoke ..... *see* Smoke
Flame spread B.6.5
Fuel limited fire ..... *see* Fires

-G-

Gaseous fire suppression systems 4.4.5, A.4.4.5
Gravity smoke venting ..... 4.3.2, 4.3.2(4), A.4.3.2
Ground-fault annunciation 6.4.7.5
Growth phase, fire 5.2.4, A.5.2.4.4, C.1.4
Growth time (t_g) 5.2.4.2.1, 5.2.4.2.2, 5.3.2, 5.4.2.2, A.5.4.2.2
Definition 3.3.9

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

-H-

Heat detectors 6.4.6.2.4
Heating, ventilating, and air conditioning (HVAC) systems ..... 4.5.3.2(2), 6.2, A.4.1.1, A.6.2
Air-handling system types ..... Annex G
Controls ..... 6.4.2, 6.4.3, A.6.4.3, H.1(3)
Coordination with other systems 6.4.2
Enclosure tightness testing, used for I.2, I.3
Mixed systems G.9
Outside air 6.2.2, G.10
Overpressure relief F.4
Special-use systems G.11
Testing 8.4.6.1.3, 8.4.6.4.2
Heat pumps/fan coil systems, unitary I.3.1
Heat release rate
Predicting heat release rate of fires ..... Annex B
Separation distance 5.2.5.4
Sprinklers, effect of A.4.2.1
Sprinkler systems, effect of A.5.2.1, C.1.1
Steady fires 5.2.3.1, 5.2.4.3, 5.4.2.1, A.5.4.2.1
t-squared (t^2) fires 5.2.4.2.1
Unsteady fires 5.2.4.2.1, 5.2.4.3, 5.2.4.4
Zone fire models C.1.1, C.1.2, C.2.3
Hospitals, ventilation systems for G.11

-I-

Individual floor HVAC units G.2, G.7, I.2.1
Induction systems ..... G.5, I.1(8), I.3.2
In-line axial air supply fans 4.6.3.2

-L-

Labeled (definition) 3.2.3
Laboratories, ventilation systems for G.11
Large-volume spaces ..... 4.1.1(2), 4.2.2, 4.3.2, 4.4.4.2.1.3, A.4.3.2
Definition 3.3.17.1
Fire locations within 4.4.3
Nonuniform cross-sectional area 5.9, A.5.9
Smoke containment testing in ..... 8.4.6, A.8.4.6.1.4 to A.8.4.6.6.1
Smoke layer interface ..... 4.1.2(4)
Smoke management testing in 8.4.5, A.8.4.5
Smoke spread from/to 4.4.4.2.2, 5.10.1, 5.10.2, A.4.4.4.2
Smoke stratification in ..... 6.4.4.1.5, A.6.4.4.1.5, C.1.1, Annex E
Leakage areas A.4.1.1, A.4.4.4.1, A.4.4.4.3
Pressure differences to control leakage 4.4.2.1.3, A.4.6.1
Smoke barrier openings and 4.4.4.3, A.4.4.4.3
Testing for leakage between smoke zones ..... Annex I
Limitations, smoke control system 4.5.1, A.4.5.1.1, A.4.5.1.2
Listed (definition) 3.2.4, A.3.2.4

-M-

Makeup air ..... 4.4.4.1, 6.2.4, 8.6.3(1), A.4.4.4.1, A.6.2.4
Malls, covered ..... *see* Covered malls
Manual, operations and maintenance ..... 7.1(2), 7.3, 8.5.2, A.7.3, J.3
Manual system activation
Acceptance tests 8.4.4.7, 8.4.7.2
Pull stations ..... 6.4.4.2.2 to 6.4.4.2.4, 6.4.5.3, 6.4.6.3, A.6.4.4.2.1, A.6.4.4.2.2, A.6.4.6.3
Smoke-control 6.4.4.2, 6.4.4.4.2, 6.4.6.3, A.6.4.4.2.1, A.6.4.6.3
Stairwell pressurization 6.4.4.2.3, 6.4.5.4
Mass consumption 5.3
Materials, smoke-control system 6.6, A.6.6.3
Means of egress ..... 1.2.1(1); *see also* Egress analysis
Mechanical smoke exhaust capacity 4.3.2, A.4.3.2
Motor-operated dampers ..... F.4(2)
Multiple-injection pressurization systems ..... *see* Pressurization systems
Multizone systems G.6

-N-

Natural smoke filling ..... 4.3.2(1)
Natural ventilation 4.8.2.2
Natural venting 4.4.4.4
Nondedicated smoke control systems ..... *see* Smoke control systems
Nonpressurized vestibules 4.10.2, A.4.10.2

-O-

Occupancies
Partial J.4
Type and location of ..... 4.2.2(4)
Once-through outdoor air ventilation systems G.11
Openings, large
Elevator hoistway A.4.7
Large ..... 4.4.4.2.1.3, 8.4.5(1)
Makeup air through 4.4.4.1, A.4.4.4.1
Operation, smoke management system ..... 4.5, 7.2.2(13), A.4.5.1.1 to A.4.5.4.1
Operations and maintenance manual ..... *see* Manual, operations and maintenance
Outside air 6.2.2, G.2
Leakage testing, HVAC systems I.2, I.3.1
Once-through outdoor air ventilation systems G.11
Ventilation systems without G.10
Overpressure relief for compensated systems F.4
Owner's manuals and instruction ..... *see* Manual, operations and maintenance

-P-

Periodic testing 8.6, A.8.6.1
Plugholing 5.5.5.2, 5.6.1, 5.6.3, 5.6.9, A.5.6.3
Definition 3.3.10
Plumes ..... 6.4.4.1.5(3), A.5.1.2, A.6.4.4.1.5(3), C.1.1, C.1.2
Average temperature 5.5.5, A.5.5.5
Axisymmetric 5.5.1, 5.5.4, A.4.4.4.2, A.5.5.1.1, A.5.5.4, C.1.1, C.1.4
Definition 3.3.11.1, A.3.3.11.1
Balcony spill ..... 5.5.2, A.5.5.2.1 to A.5.5.2.8, C.1.4
Definition 3.3.11.2, A.3.3.11.2
Definition 3.3.11, A.3.3.11
Deflection A.4.4.4.1.4
Spill A.4.4.4.2
Walls, contact with 5.5.4.2, A.5.5.1.1
Window 5.5.3, A.5.5.3, C.1.4
Definition 3.3.11.3, A.3.3.11.3
Pressure differences ..... 4.4.2, 7.2.2(6), A.4.4.2.1.1, A.4.4.2.2
Doors, across ..... 4.4.2.2, 8.4.5(3), A.4.4.2.2, A.4.9
Smoke barriers, across ..... *see* Smoke barriers
Smoke control zone boundaries, across ..... 4.8.1.2, 8.4.6.4.2.1, 8.4.6.4.4.2 to 8.4.6.4.4.5
Smoke zone boundaries, across ..... 4.1.1(1)
Spaces, across 4.4.2.1, A.4.4.2.1.1
Stairwell pressurization systems ..... 4.6.1, A.4.6.1, Annex F
Pressurization systems
Elevators 4.7, A.4.7
Multiple-injection systems 4.6.3.2, 4.6.4.2, A.4.6.4.2
Definition 3.3.18.4.1
Single-injection systems 4.6.3.1, 4.6.3.2, 4.6.4.1, A.4.6.3.1, A.4.6.4.1.1, A.4.6.4.1.2
Definition 3.3.18.4.2
Pressurized stairwells ..... 4.3.1(1), 4.6, A.4.6.1 to A.4.6.4.2, A.4.9, A.4.11, A.6.4.4.2.2; *see also* Vestibules
Air supply 4.6.2
Combined with other systems 8.4.6.3.2, 8.4.6.7.1
Compensated systems ..... F.2 to F.4
Controls 6.4.4.2.3, 6.4.5, A.6.4.5.1.1
Definition 3.3.12
Fans 4.6.3, A.4.6.3.1
Noncompensated systems F.1
Single- and multiple-injection systems 4.6.3, 4.6.4, A.4.6.3.1, A.4.6.4
Testing 8.4.6.3, 8.4.6.7.1
Types of ..... Annex F
Pressurized vestibules 4.10.2, A.4.10.2
Propeller fans 4.6.3.1, A.4.6.3.1
Purpose of standard 1.2

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

-R-

Radiant panel systems G.10
References ..... Chap. 2, Annex M
Relief dampers, duct system F.3, G.2
Report, design ..... 7.1(1), 7.2
Response time, smoke-control system ..... 6.4.4.5, A.6.4.4.5.1.2, F.2, F.3, H.1(4)
Retroactivity of standard 1.3

-S-

Scale modeling 5.1.2, 5.11, A.5.1.2, A.5.11
Scope of standard 1.1, A.1.1
Self-contained air conditioners G.10
Separated spaces (definition) 3.3.17.2
Separation distance, design fires 5.2.5, A.5.2.5
Shall (definition) 3.2.5
Should (definition) 3.2.6
Simulated smoke J.5
Single-injection pressurization systems ..... *see* Pressurization systems
Single-speed fans F.1
Smoke
Definition 3.3.13
First indication of smoke
Definition 3.3.13.1, A.3.3.13.1
With no indication of smoke exhaust operating 5.4.2, A.5.4.2.1, A.5.4.2.2
Mass production, rate of ..... 5.5, A.5.5.1.1 to A.5.5.5
Simulated J.5
Stratification of ..... 6.4.4.1.5, A.6.4.4.1.5, C.1.1, Annex E; *see also* Smoke layers
Smoke barriers ..... 4.2.2(5), 4.4.4.2.1.1(2), 4.8.1.1, 6.3.1, A.4.8.1.1.1
Definition 3.3.14, A.3.3.14
Doors in 4.11, 8.4.6.4.2.1, 8.4.6.4.4.3, A.4.11
Openings and leakage areas 4.4.4.3, A.4.4.4.3
Pressure differences across ..... Table 4.4.2.1.1, 4.4.4.2.1.2, 8.4.6.1.1, 8.4.6.1.4, 8.4.6.1.5, 8.4.6.4.4.2 to 8.4.6.4.4.5, 8.6.3(1), A.8.4.6.1.4
Smoke containment ..... 4.1.1(1), 4.4.2, 6.4.4.5.3, A.4.1.1, A.4.4.2.1.1, A.4.4.2.2
Definition 3.3.15, A.3.3.15
Passive system A.4.1.1
Testing of system ..... 8.4.6, A.8.4.6.1.4 to A.8.4.6.6.1
Smoke control mode
Definition 3.3.16
For each smoke control zone 8.4.6.4.4, A.8.4.6.4.4.6
Smoke control systems ..... 4.4.4.3, 6.1, 6.4, 7.2.2(12), 7.2.2(13), A.4.1.1, A.4.4.4.3, A.6.4; *see also* Fire fighters' smoke control station (FSCS)
Activation and deactivation ..... 4.5.2, 6.4.3 to 6.4.5, 7.2.2(12), 8.6.1, A.6.4.3 to A.6.4.5.1.1, A.8.6.1
Combination of multiple systems 4.9, A.4.9
Dedicated smoke control systems ..... 6.4.4.6.6(1), 8.6.7
Definition 3.3.18.2
Smoke-control subsystems, verification of 6.4.7.1
Definition 3.3.18.5
Interaction with other fire protection systems 6.4.2, 6.4.3, 6.4.6.2, A.6.4.3, A.6.4.6.2.1
Nondedicated smoke control systems 6.4.4.7.13.1
Definition 3.3.18.3
Smoke-control subsystems, verification of 6.4.7.1
Status indicators ..... 6.4.4.6.6(2)
Testing 8.6.8
Pressurized stairwell controls 6.4.4.2.3, 6.4.5, A.6.4.5.1.1
Sequence of control priorities ..... 6.4.4.4, 8.4.4.4, A.8.4.4.4(2)
Zoned smoke control systems, controls for 6.4.6, A.6.4.6.2.1, A.6.4.6.3
Smoke control zones ..... *see* Zones, Smoke control
Smoke dampers ..... *see* Dampers, Smoke
Smoke detectors 6.4.4.1.2, 6.4.4.4.1.3, 6.4.4.6.13, 6.4.5.2, 6.4.5.4.2, 6.4.6.2.2, 6.4.6.2.3, A.6.4.4.1.2
Smoke exhaust systems ..... 4.4.4.1.2, 4.4.4.2.2.2, 4.6.2, 5.5.5.1, 5.10.3.2, 7.2.2(11), A.5.4.1
Communicating spaces 5.10.1, 5.10.3.2
Definition 3.3.18.6, A.3.3.18.6
Elevators A.4.7
Inlets, number of 5.6, A.5.6
Periodic tests ..... 8.6.3(3)
Smoke zone exhaust 4.8.2
Smoke layers ..... 6.4.4.1.5, A.6.4.4.1.5, Annex E
Calculations ..... 5.4, A.5.4.1 to A.5.4.2.2
Definition 3.3.20, A.3.3.20
Minimum design depth 4.5.1.3
Zone fire model C.1.4
Smoke layer interfaces
Communicating spaces
Smoke management from 4.4.4.2.2.1
Smoke management within 4.3.2, A.4.3.2
Smoke spread to ..... 4.4.4.2.1.1(1), 5.10.2, 5.10.3
Definition 3.3.21, A.3.3.21
Design height ..... 4.1.2(4), 4.3.2, A.4.3.2
Height at first indication of smoke, calculations 5.4.2, A.5.4.2.1, A.5.4.2.2
Makeup air supply points below 4.4.4.1.1
Zone fire model C.1.1, C.1.4
Smoke management ..... 4.1.1(2), 4.2.2, 4.3.2, 6.4.4.5.4, A.4.1.1, A.4.3.2
Communicating spaces 4.4.4.2, A.4.4.4.2
Definition 3.3.22
Makeup air for 4.4.4.1, 6.2.4, A.4.4.4.1, A.6.2.4
Testing of system 8.4.5, A.8.4.5
Smoke refuge areas ..... 1.2.1, 4.1.2(3), 4.2.2(7), 4.3.1(5), 4.8.3, A.4.8.3, A.4.9
Combined with smoke-control systems 8.4.6.7.2
Definition 3.3.23
Testing 8.4.6.6, 8.4.6.7.2, A.8.4.6.6.1
Smoke zones ..... *see* Zones, Smoke
Spaces ..... *see also* Communicating spaces; Large-volume spaces
Separated spaces (definition) 3.3.17.2
Sprinkler systems ..... 4.2.1.1(1), 5.2.4.4(2), A.4.1.1, A.4.2.1, A.4.4.4.2, A.4.8, A.5.2.1, A.5.2.4.4, C.1.1
Stack effect 4.4.2.1.4, A.4.1.1, A.4.7
Definition 3.3.24
Stairwells ..... 1.2.1(1)
Areas of refuge adjacent to 4.8.3.2
Pressurized ..... *see* Pressurized stairwells
Tenable environment in ..... 4.1.2(2)
Standard (definition) 3.2.7
Standby electrical power ..... 6.7.3, 8.4.4.2, 8.4.4.4(3), 8.6.5.4, A.8.4.4.2
Startup, system 4.5.3
Status indicators ..... 6.4.4.6.3 to 6.4.4.6.8, A.6.4.4.6.3.1, A.6.4.4.6.4.1, H.1(2), H.1(5)
Steady fires ..... *see* Fires
Systems ..... *see also* Pressurization systems; Smoke control systems; Smoke exhaust systems; Zoned smoke control systems
Compensated systems
Definition 3.3.18.1
Stairwell pressurization ..... F.2 to F.4

-T-

Temperature ratings 4.2.3
Tenable environment ..... 1.2.1(2), 4.5.1.1, A.4.5.1.1, D.1.2
Definition 3.3.25, A.3.3.25
Maintenance of 4.1.2, 4.4.2.1.3, 4.5.4.2, A.4.3.2
Tenability thresholds reached, exiting prior to 4.5.4.1, A.4.5.4.1
Terminal units ..... G.7 to G.9, H.1(3)
Testing ..... Chap. 8; *see also* Acceptance testing
Component system 8.3, A.8.3
Documentation ..... 7.3.1(2), 7.3.3, 8.5, A.8.5.1, J.2
Of modifications 8.7, A.8.7.1
For partial occupancy J.4
Periodic 8.6, A.8.6.1
Preliminary building inspections 8.2
Transition zone (definition) 3.3.26.3, A.3.3.26.3

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

-U-

Unsteady fires ..... *see* Fires

-V-

Variable air volume systems (VAV) ..... G.7 to G.9, I.2.1, I.2.2
Ventilation 4.4.4.4, 4.8.2.2, C.1.2
Ventilation limited fires 5.5.3.1, A.5.5.3.1
Definition 3.3.7.6
Venting
Gravity smoke 4.3.2, A.4.3.2
Natural 4.4.4.4
Vents 4.6.2, 4.7, A.4.4.4.1, A.4.4.4.2, A.4.7, C.1.2, C.2.3
Vestibules ..... 4.3.1(4), 4.10, 8.4.6.3.3, A.4.10.1, A.4.10.2

-W-

Waterflow switches 6.4.6.2.4
Water source heat pump units G.4
Weather conditions C.2.3
Weather data 4.4, A.4.4.1
Windbreaks (windshields) 4.6.3.1, A.4.6.3.1, F.4
Wind effect 4.4.2.1.4, A.4.1.1, C.2.3, F.4

-Z-

Zoned smoke control systems ..... 4.3.1(2), 4.8, A.4.8, A.4.9
Combined with other systems 8.4.6.3.2, 8.4.6.7
Controls for 6.4.6, A.6.4.6.2.1, A.6.4.6.3
Definition 3.3.18.7
Smoke control mode for each zone 8.4.6.4.4, A.8.4.6.4.4.6
Testing 8.4.6.4, 8.4.6.7, A.8.4.6.4
Vestibules as part of 8.4.6.3.3
Zone fire models ..... 5.1.3, A.5.1.3, Annex C
Zones
Non-smoke 4.8.1.2, 4.8.3.1
Smoke ..... 1.2.1, 4.1.1(1), 4.1.2(1), 4.2.1.1(2), 7.2.2(5), A.6.4.4.1.4
Definition 3.3.26.2
Smoke control 4.8.1, A.4.8.1.1.1, A.6.4.4.1.4
Definition 3.3.26.1
Pressure differences across ..... *see* Pressure differences
Transition (definition) 3.3.26.3, A.3.3.26.3

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

Sequence of Events Leading to Issuance of an NFPA Committee Document

Step 1: Call for Proposals

- Proposed new Document or new edition of an existing Document is entered into one of two yearly revision cycles, and a Call for Proposals is published.

Step 2: Report on Proposals (ROP)

- Committee meets to act on Proposals, to develop its own Proposals, and to prepare its Report.
- Committee votes by written ballot on Proposals. If two-thirds approve, Report goes forward. Lacking two-thirds approval, Report returns to Committee.
- Report on Proposals (ROP) is published for public review and comment.

Step 3: Report on Comments (ROC)

- Committee meets to act on Public Comments to develop its own Comments, and to prepare its report.
- Committee votes by written ballot on Comments. If two-thirds approve, Report goes forward. Lacking two-thirds approval, Report returns to Committee.
- Report on Comments (ROC) is published for public review.

Step 4: Technical Report Session

- "*Notices of intent to make a motion*" are filed, are reviewed, and valid motions are certified for presentation at the Technical Report Session. ("Consent Documents" that have no certified motions bypass the Technical Report Session and proceed to the Standards Council for issuance.)
- NFPA membership meets each June at the Annual Meeting Technical Report Session and acts on Technical Committee Reports (ROP and ROC) for Documents with "certified amending motions."
- Committee(s) vote on any amendments to Report approved at NFPA Annual Membership Meeting.

Step 5: Standards Council Issuance

- Notification of intent to file an appeal to the Standards Council on Association action must be filed within 20 days of the NFPA Annual Membership Meeting.
- Standards Council decides, based on all evidence, whether or not to issue Document or to take other action, including hearing any appeals.

Committee Membership Classifications

The following classifications apply to Technical Committee members and represent their principal interest in the activity of the committee.

M *Manufacturer:* A representative of a maker or marketer of a product, assembly, or system, or portion thereof, that is affected by the standard.

U *User:* A representative of an entity that is subject to the provisions of the standard or that voluntarily uses the standard.

I/M *Installer/Maintainer:* A representative of an entity that is in the business of installing or maintaining a product, assembly, or system affected by the standard.

L *Labor:* A labor representative or employee concerned with safety in the workplace.

R/T *Applied Research/Testing Laboratory:* A representative of an independent testing laboratory or independent applied research organization that promulgates and/or enforces standards.

E *Enforcing Authority:* A representative of an agency or an organization that promulgates and/or enforces standards.

I *Insurance:* A representative of an insurance company, broker, agent, bureau, or inspection agency.

C *Consumer:* A person who is, or represents, the ultimate purchaser of a product, system, or service affected by the standard, but who is not included in the *User* classification.

SE *Special Expert:* A person not representing any of the previous classifications, but who has a special expertise in the scope of the standard or portion thereof.

NOTES:
1. "Standard" connotes code, standard, recommended practice, or guide.
2. A representative includes an employee.
3. While these classifications will be used by the Standards Council to achieve a balance for Technical Committees, the Standards Council may determine that new classifications of members or unique interests need representation in order to foster the best possible committee deliberations on any project. In this connection, the Standards Council may make appointments as it deems appropriate in the public interest, such as the classification of "Utilities" in the National Electrical Code Committee.
4. Representatives of subsidiaries of any group are generally considered to have the same classification as the parent organization.

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

NFPA Document Proposal Form

NOTE: All Proposals must be received by 5:00 pm EST/EDST on the published Proposal Closing Date.

For further information on the standards-making process, please contact the Codes and Standards Administration at 617-984-7249 or visit www.nfpa.org/codes.

For technical assistance, please call NFPA at 1-800-344-3555.

FOR OFFICE USE ONLY

Log #: _____

Date Rec'd: _____

Please indicate in which format you wish to receive your ROP/ROC ☐ **electronic** ☐ **paper** ☒ **download**
(Note: If choosing the download option, you must view the ROP/ROC from our website; no copy will be sent to you.)

Date April 1, 200X **Name** John J. Doe **Tel. No.** 716-555-1234

Company Air Canada Pilot's Association **Email**

Street Address 123 Summer Street Lane **City** Lewiston **State** NY **Zip** 14092

******If you wish to receive a hard copy, a street address MUST be provided. Deliveries cannot be made to PO boxes.***

Please indicate organization represented (if any)

1. (a) NFPA Document Title National Fuel Gas Code **NFPA No. & Year** 54, 200X Edition

(b) Section/Paragraph 3.3

2. Proposal Recommends (check one): ☐ new text ☒ revised text ☐ deleted text

3. Proposal (include proposed new or revised wording, or identification of wording to be deleted): [Note: Proposed text should be in legislative format; i.e., use underscore to denote wording to be inserted (inserted wording) and strike-through to denote wording to be deleted (~~deleted wording~~).]

Revise definition of effective ground-fault current path to read:

3.3.78 Effective Ground-Fault Current Path. An intentionally constructed, permanent, low impedance electrically conductive path designed and intended to carry ~~underground~~ electric fault current ~~conditions~~ from the point of a ground fault on a wiring system to the electrical supply source.

4. Statement of Problem and Substantiation for Proposal: (Note: State the problem that would be resolved by your recommendation; give the specific reason for your Proposal, including copies of tests, research papers, fire experience, etc. If more than 200 words, it may be abstracted for publication.)

Change uses proper electrical terms.

5. Copyright Assignment

(a) ☐ **I am the author of the text or other material (such as illustrations, graphs) proposed in the Proposal.**

(b) ☒ **Some or all of the text or other material proposed in this Proposal was not authored by me. Its source is as follows:** (please identify which material and provide complete information on its source)

ABC Co.

I hereby grant and assign to the NFPA all and full rights in copyright in this Proposal and understand that I acquire no rights in any publication of NFPA in which this Proposal in this or another similar or analogous form is used. Except to the extent that I do not have authority to make an assignment in materials that I have identified in (b) above, I hereby warrant that I am the author of this Proposal and that I have full power and authority to enter into this assignment.

Signature (Required) John J. Doe

PLEASE USE SEPARATE FORM FOR EACH PROPOSAL

Mail to: Secretary, Standards Council · National Fire Protection Association
1 Batterymarch Park · Quincy, MA 02169-7471 OR
Fax to: (617) 770-3500 OR Email to: proposals_comments@nfpa.org

06/09-B

SAMPLE

Copyright 2012 National Fire Protection Association (NFPA). Licensed, by agreement, for individual use and single download on November 6, 2012 to SSC for designated user MIODRAG MASIC. No other reproduction or transmission in any form permitted without written permission of NFPA. For inquires or to report unauthorized use, contact licensing@nfpa.org.

NFPA Document Proposal Form

NOTE: All Proposals must be received by 5:00 pm EST/EDST on the published Proposal Closing Date.

For further information on the standards-making process, please contact the Codes and Standards Administration at 617-984-7249 or visit www.nfpa.org/codes.

For technical assistance, please call NFPA at 1-800-344-3555.

FOR OFFICE USE ONLY

Log #: _____

Date Rec'd: _____

Please indicate in which format you wish to receive your ROP/ROC ☐ electronic ☐ paper ☐ download
(Note: If choosing the download option, you must view the ROP/ROC from our website; no copy will be sent to you.)

Date _____ **Name** _____ **Tel. No.** _____

Company _____ **Email** _____

Street Address _____ **City** _____ **State** _____ **Zip** _____

******If you wish to receive a hard copy, a street address MUST be provided. Deliveries cannot be made to PO boxes.***

Please indicate organization represented (if any) _____

1. (a) NFPA Document Title _____ **NFPA No. & Year** _____

(b) Section/Paragraph _____

2. Proposal Recommends (check one): ☐ new text ☐ revised text ☐ deleted text

3. Proposal (include proposed new or revised wording, or identification of wording to be deleted): [Note: Proposed text should be in legislative format; i.e., use underscore to denote wording to be inserted (inserted wording) and strike-through to denote wording to be deleted (~~deleted wording~~).]

4. Statement of Problem and Substantiation for Proposal: (Note: State the problem that would be resolved by your recommendation; give the specific reason for your Proposal, including copies of tests, research papers, fire experience, etc. If more than 200 words, it may be abstracted for publication.)

5. Copyright Assignment

(a) ☐ I am the author of the text or other material (such as illustrations, graphs) proposed in the Proposal.

(b) ☐ Some or all of the text or other material proposed in this Proposal was not authored by me. Its source is as follows: (please identify which material and provide complete information on its source)

_____

I hereby grant and assign to the NFPA all and full rights in copyright in this Proposal and understand that I acquire no rights in any publication of NFPA in which this Proposal in this or another similar or analogous form is used. Except to the extent that I do not have authority to make an assignment in materials that I have identified in (b) above, I hereby warrant that I am the author of this Proposal and that I have full power and authority to enter into this assignment.

Signature (Required) _____

PLEASE USE SEPARATE FORM FOR EACH PROPOSAL

Mail to: Secretary, Standards Council · National Fire Protection Association
1 Batterymarch Park · Quincy, MA 02169-7471 OR
Fax to: (617) 770-3500 OR Email to: proposals_comments@nfpa.org

06/09-C